



PLANTING SCHEDULE

| Number | Plant Name | Abbreviation | Height | Girth | Specification |
|--------|---------------------------------------|--------------|-----------|---------|--|
| 1 No. | Parrotia persica | P p | 400-450cm | 14-16cm | Extra Heavy Standard: 5 brks: 3x: RB: Clear Stem 175-200cm |
| 2 No. | Pyrus calleryana 'Chanticleer' | P c 'Ch' | 450-500cm | 18-20cm | Extra Heavy Standard: clear stem minimum 200cm |
| 3 No. | Parrotia persica | P p | 350-425cm | 12-14cm | Heavy Standard: 5 brks: C: Clear Stem 175-200cm |
| 2 No. | Amelechier lamarkii | A lam | 300-350cm | 14-16cm | Extra Heavy Standard: 5 brks: C: Clear Stem 175-200cm |
| 2 No. | Magnolia grandiflora 'Ferruginea' | MaGrFe | 175-200cm | 8-10cm | Multi-stem: Bushy: 3 brks: C |
| 6 No. | Ligustrum lucidum 'Excelsum Superbum' | Li es | 350-400cm | 18-20cm | Extra Heavy Standard: C: Clear Stem min 200cm |

Total: 16 No.

| Number | Plant Name | Height | Container | Specification | Density |
|--------|------------------------------------|----------|-----------|---------------------|------------------|
| 56 No. | Choisya 'Aztec Pearl' | 40-60cm | 5L | Bushy: 7 brks: C | 5/m ² |
| 7 No. | Cornus sanguinea 'Midwinter Fire' | 80-100cm | 10L | Branched: 5 brks: C | 2/m ² |
| 12 No. | Cornus stolonifera 'Flaviramea' | 80-100cm | 10L | Branched: 5 brks: C | 2/m ² |
| 21 No. | Euonymus fortunei 'Emerald Gaiety' | 25-30cm | 5L | Bushy: 9 brks: C | 5/m ² |
| 21 No. | Skimmia confusa 'Kew Green' | 40-60cm | 5L | Bushy: 5 brks: C | 5/m ² |
| 36 No. | Viburnum davidii | 30-40cm | 5L | Bushy: 5 brks: C | 5/m ² |
| 25 No. | Viburnum x hillieri 'Winton' | 40-60cm | 5L | Bushy: 7 brks: C | 7/m ² |

Total: 178 No.

| Number | Plant Name | Container | Specification | Density |
|--------|-------------------------------------|-----------|--|------------------|
| 41 No. | Ajuga reptans | 2L | Full Pot: Sept to April planting: British Native-origin: C | 7/m ² |
| 8 No. | Anemone x hybrida 'Honorine Jobert' | 5L | Full Pot: C | 5/m ² |
| 23 No. | Aster divaricatus | 3L | Full Pot: C | 6/m ² |
| 16 No. | Aster divaricatus | 3L | Full Pot: C | 5/m ² |
| 13 No. | Bergenia 'Bressingham Ruby' | 5L | Full Pot: C | 5/m ² |
| 14 No. | Bergenia 'Silberlicht' | 3L | Full Pot: C | 6/m ² |
| 25 No. | Geranium Rozanne | 5L | Full Pot: C | 6/m ² |
| 16 No. | Hemerocallis lilioasphodelus | 3L | Full Pot: C | 6/m ² |

Total: 156 No.

| Number | Plant Name | Abbreviated Text | Height | Container | Specification | Density |
|--------|-------------------|------------------|---------|-----------|-------------------------------|------------------|
| 15 No. | Pinus mugo 'Mops' | P mu 'M' | 30-40cm | 10-15L | Bushy: C | 3/m ² |
| 6 No. | Taxus baccata | T b | 40-60cm | 15-20L | Ball Shape: C: Neatly Clipped | Counted |

Total: 21 No.

| Number | Plant Name | Height | Container | Specification | Density |
|--------|---------------------|----------|-----------|---------------------------|------------------|
| 23 No. | Phyllostachys nigra | 80-100cm | 5L | Several Shoots: 7 brks: C | 5/m ² |
| 12 No. | Phyllostachys nigra | 80-100cm | 5L | Several Shoots: 7 brks: C | Counted |

Total: 35 No.

| Number | Plant Name | Container | Specification | Density |
|--------|---|-----------|---------------|------------------|
| 17 No. | Dryopteris affinis 'Cristata Angustata' | 5L | Full Pot: C | 5/m ² |
| 13 No. | Dryopteris filix-mas | 5L | Full Pot: C | 5/m ² |

Total: 30 No.

| Number | Plant Name | Height | Container | Specification | Density |
|--------|-----------------------------------|--------|-----------|---------------|------------------|
| 23 No. | Carex buchananii | | 5L | Full Pot: C | 5/m ² |
| 19 No. | Liriope muscari | | 5L | Full Pot: C | 5/m ² |
| 11 No. | Miscanthus sinensis 'Gracillimus' | | 5L | Full Pot: C | 5/m ² |
| 7 No. | Pennisetum alopecuroides 'Hameln' | | 5L | Full Pot: C | 2/m ² |

Total: 60 No.