



Planting Schedule

Trees - *Singular specimens located as per planting plan

No.	Abb.	Botanical Name	Common Name	Height	Specification
19	BLU	<i>Betula utilis jacquemontii</i>	White-barked Himalayan Birch	250-300cm	RB :2x :Standard :Clear Stem 175-200cm :4 brks
27	CBF	<i>Carpinus betulus 'Frans Fontaine'</i>	Hornbeam 'Frans Fontaine'	250-300cm	RB :2x :Standard :Clear Stem 175-200cm :3 brks
24	PCH	<i>Pyrus calleryana 'Charcticolor'</i>	Flowering Pear 'Charcticolor'	250-300cm	RB :2x :Standard :Clear Stem 175-200cm :3 brks
20	PpW	<i>Prunus padus 'Watereri'</i>	Bird Cherry 'Watereri'	250-300cm	RB :2x :Standard :Clear Stem 175-200cm :3 brks
26	SAL	<i>Sorbus aria 'Lutescens'</i>	Whitebeam 'Lutescens'	250-300cm	RB :2x :Standard :Clear Stem 175-200cm :3 brks
24	SJR	<i>Sorbus 'Joseph Rock'</i>	Rowan 'Joseph Rock'	250-300cm	RB :2x :Standard :Clear Stem 175-200cm :3 brks
Total :140					

Formal Hedges - *Hedgerows planted in double staggered rows at 300mm centres

No.	Abb.	Botanical Name	Common Name	Height	Specification	Total Linear Length
6748	FSY	<i>Fagus sylvatica</i>	Common Beech	125-150cm	B :2x :Feathered :2 brks	1011.5251m

Ornamental Shrubs

No.	Abb.	Botanical Name	Common Name	Height	Specification	Pot Size	Density
195	Shd	<i>Sarcococca hookeriana digyna</i>	Sweet Box 'Digyna'	30-40cm	Bushy :6 brks	5L	3/m ²
475	Vda	<i>Viburnum davidii</i>	David Viburnum	30-40cm	Bushy :4 brks	5-7.5L	2/m ²
98	WBR	<i>Weigela 'Bristol Ruby'</i>	Weigela Bristol Ruby	40-60cm	Branched :3 brks	2L	3/m ²
Total :768							

NTM1-Native Thicket Mix - *Planted at 1m centres

No.	Abb.	Botanical Name	Common Name	Height	Specification	% Cont.
781	Cav	<i>Corylus avellana</i>	Common Hazel	40-60cm	B :1+1 :Transplant - seed raised :Branched :2 brks	20%
391	Cla	<i>Crataegus laevigata</i>	Midland Hawthorn	40-60cm	B :1+1 :Transplant - seed raised	10%
781	CMO	<i>Crataegus monogyna</i>	Common Hawthorn	40-60cm	B :1+1 :Transplant - seed raised	20%
391	Csa	<i>Cornus sanguinea</i>	Common Dogwood	40-60cm	B :1+1 :Transplant - seed raised :Branched :2 brks	10%
391	Heq	<i>Ilex aquifolium</i>	Common Holly	40-60cm	150cc min. 11+0 :Seedling :Calli grown	10%
391	Lvu	<i>Ligustrum vulgare</i>	Common Privet	40-60cm	B :0/1 :Cutting :Branched :2 brks	10%
391	PSP	<i>Prunus spinosa</i>	Blackthorn	40-60cm	B :1+1 :Transplant - seed raised :Branched :2 brks	10%
391	Vop	<i>Viburnum opulus</i>	Guedler Rose	40-60cm	B :1+1 :Transplant - seed raised :Branched :2 brks	10%
Total :3908						

NSM1-Native Shrub Mix - *Planted at 1m centres

No.	Abb.	Botanical Name	Common Name	Height	Specification	% Cont.
170	Cav	<i>Corylus avellana</i>	Common Hazel	40-60cm	B :1+1 :Transplant - seed raised :Branched :2 brks	20%
340	Cla	<i>Crataegus laevigata</i>	Midland Hawthorn	40-60cm	B :1+1 :Transplant - seed raised	40%
128	Csa	<i>Cornus sanguinea</i>	Common Dogwood	40-60cm	B :1+1 :Transplant - seed raised :Branched :2 brks	15%
86	Ee	<i>Eunymus europaeus</i>	Common Spindle Tree	40-60cm	B :1+1 :Transplant - seed raised :Branched :3 brks	10%
44	Heq	<i>Ilex aquifolium</i>	Common Holly	40-60cm	150cc min. 11+0 :Seedling :Calli grown	5%
86	Lvu	<i>Ligustrum vulgare</i>	Common Privet	40-60cm	B :0/1 :Cutting :Branched :2 brks	10%
Total :854						

Herbaceous Planting

No.	Abb.	Botanical Name	Common Name	Specification	Pot Size	Density
462	BcP	<i>Bergenia cordifolia 'Purpurea'</i>	Elephant's Ears 'Purpurea'	Full Pot	2L	5/m ²
827	GmA	<i>Geranium macrorrhizum 'Album'</i>	Balkan Cranesbill 'Album'	Full Pot	3L	4/m ²
425	Mst	<i>Matteuccia struthiopteris</i>	Shuttlecock Fern	Full Pot	3L	2/m ²
Total :1724						

Bulbs - *Planted at 10cm spacings

No.	Abb.	Botanical Name	Common Name	Specification
2020	Hns	<i>Hyacinthoides non-scripta</i>	Common Bluebell	Grade 6/7
1746	Ntt	<i>Narcissus 'Tete a Tete'</i>	Daffodil 'Tete a Tete'	Grade 10/12
Total :3826				

Germinal-RE1 Traditional Hay Meadow (MGS Grassland) - *2800m2 total area coverage

Abb.	Botanical Name	Common Name	% Cont.
Acap	<i>Agrostis capillaris</i>	Common Bent	3%
Aea	<i>Agrimonia eupatoriolum</i>	Agrimony	1%
Ami	<i>Achillea millefolium</i>	Yarrow	1%
Aod	<i>Anthoxanthum odoratum</i>	Sweet Vernal-grass	1%
Ocr	<i>Cynosurus cristatus</i>	Crested Dog's-tail	25%
Chl	<i>Centaurea nigra</i>	Common Knapweed	3%
Fov	<i>Festuca ovina</i>	Sheep's-fescue	7%
Fpr	<i>Festuca pratensis</i>	Meadow Fescue	5%
Frl	<i>Festuca rubra litoralis</i>	Slender Creeping Red Fescue	30%
Ful	<i>Filipendula ulmaria</i>	Meadow Sweet	1%
Gve	<i>Gallium verum</i>	Lady's Bedstraw	2%
Lco	<i>Lotus corniculatus</i>	Common Bird's-foot-trefoil	1%
Lvu	<i>Leucanthemum vulgare</i>	Oxeye Daisy	1%
Pbe	<i>Phleum bertolonii</i>	Teno	5%
Pia	<i>Plantago lanceolata</i>	Ribwort Plantain	3%
Pvu	<i>Prunella vulgaris</i>	Selfheal	1%
Rbu	<i>Ranunculus bulbosus</i>	Bulbous Buttercup	2%
Rmi	<i>Rhinanthus minor</i>	Yellow-rattle	1%
Smi	<i>Sanguisorba minor</i>	Saint Burnet	1%
Tll	<i>Taraxacum officinale</i>	Golden Oat Grass	5%
Tpr	<i>Trifolium pratense</i>	Red Clover	2%
Tre	<i>Trifolium repens</i>	White Clover	2%

NOTES

All dimensions to be verified on site. Scale for the purpose of planting. All discrepancies to be clarified with project landscape architect.

This drawing is the property of Urban Wilderness Ltd and is issued on the condition it is not reproduced, altered or disclosed in any unauthorised person, either wholly or in part without written consent of Urban Wilderness Ltd.

- Site Boundary
- Grassland
RE1 Traditional Hay Meadow Seed Mix (MGS Grassland), Germinal
- Ornamental Shrub & Herbaceous Planting
Low level border planting of shrubs and ferns
- Native Thicket Mix
Low grown native scrub/thicket planting to existing bund
- Native Shrub Mix
Native whip planting, notch planted at 1m interval matrix
- Formal Hedging
Formal hedging to car park boundary, maintained at 1.5m high
- Proposed trees
- Ornamental bulb planting
- Insect hotels (as recommended by Delta Simons Ecology Report)
- Insect hotels (as recommended by Delta Simons Ecology Report)
- Trees for removal (as per Tree Constraints Plan by Delta Simons)
- Existing trees & hedgerows (grouped) for removal (as per Tree Constraints Plan by Delta Simons)
- Existing lawn areas to be retained

Planting specification assumes planting in dormant season, between mid November and the end of March



Rev	Description	Date
1	Issued for architectural layout	27 Sep 21
2	Change	31 Oct 21
3	Issued for architectural layout	27 Sep 21
4	Final issue	27 Sep 21

URBAN WILDERNESS

7 Saw Mill Yard, Water Lane, Hildesheim, Leicestershire LE15 5WH
www.urbanwilderness.co.uk
design@urbanwilderness.co.uk
0153 622 0000
registered in Scotland SC219799

client
Lysander
project
Banbury 200 Site, Southam Road, Banbury

drawing title
Softworks General Arrangement Plan

drawing status
TENDER

drawn by	checked by	date
LJM	TBR	27 Sep 21

scale
1:500

paper size
A0

job/dwg no.
388-UW-T-001

rev.
C