DO NOT SCALE

CBR'S TO BE CONFIRMED BY INSITU TESTS CARRIED OUT IN ACCORDANCE ITH THE SPECIFICATION.

WORKS TO BE CARRIED OUT IN ACCORDANCE WITH THE SPECIFICATION FOR HIGHWAY WORKS (SHW), SHW INCLUDES INTERIM ADVICE NOTE 101/07 (AMENDMENT 1) FOR 900 SERIES.

4. ALL MATERIALS WITHIN 450MM OF FINISHED SURFACE SHALL BE NON FROST SUSCEPTIBLE IN ACCORDANCE WITH CL 602.19 AND 801.7.

5. THESE DETAILS INCLUDE THE USE OF HEAVY KERB/PAVING PRODUCTS WHICH THE CONTRACTOR IS EXPECTED TO HANDLE USING APPROPRIATE MECHANICAL HANDLING AIDS IN ACCORDANCE WITH HEALTH AND SAFETY EXECUTIVE (HSE) GUIDANCE.

6. FOUNDATION TYPE A TO BE USED FOR THE INITIAL 500m OF THE SPINE ROAD FROM MIDDLETON STONEY ROAD HEADING SOUTH. FOUNDATION TYPE B TO BE USED THEREAFTER. EXTENTS OF FOUNDATION TYPES TO BE CONFIRMED AFTER SITE TESTING OF SUBGRADE CBR.

7. ALL SURFACE COURSE MATERIAL AGGREGATE COLOURS AND SOURCES TO BE APPROVED AT LEAST 4 WEEKS BEFORE INSTALLATION. SEE HRA AGGREGATES TABLE.

	:				
	03/12/08	HL	ISSUED FOR TECHNICAL APPROVAL	JAM	7
_	16/09/08	JH	INITIAL ISSUE	H	WL
~	DATE	ВҮ	DESCRIPTION	CHK	APD
ш					

FOR TECHNICAL APPROVAL

Mountbatten House, Basing View, Basingstoke, Hampshire RG21 4HJ Tel: +44 (0)1256 318800 Fax: +44 (0)1256 318700 http://www.wspgroup.com

COUNTRYSIDE PROPERTIES

TYPICAL HIGHWAY CONSTRUCTION BICESTER, OXFORDSHIRE SOUTH WEST BICESTER SPINE ROAD A

E @ A3:	CHECKED:	APPROVED:	
N.T.S.	Н		JM
FILE	DESIGN-DRAWN:	DATE	
1903-SD-202	JH	Janua	January 2008
JECT No:	DRAWING No:		REV
11011903	1903/SD/202)2	В