

- 39no Corylus Avellana
 - 39no Cornus Sanguinea
 - 39no Cornus Alba
 - 39no Cornus Kelsey
 - 382no Crataegus Monogyna
 - 76no Hammamelis Mollis
 - 19no Ribes Sanguineum
 - 19no Salix Alba
 - 19no Sambucus Nigra
 - 19no Viburnum Opulus
 - 38no Viburnum Lanata
 - 38no Euonymus Red Cascade
- plants to be bare root 450-600 high at planting, with Tubex quills and cane.

- 14no Corylus Avellana
 - 14no Cornus Sanguinea
 - 14no Cornus Alba
 - 14no Cornus Kelsey
 - 133no Crataegus Monogyna
 - 27no Hammamelis Mollis
 - 7no Ribes Sanguineum
 - 7no Salix Alba
 - 7no Sambucus Nigra
 - 7no Viburnum Opulus
 - 14no Viburnum Lanata
 - 14no Euonymus Red Cascade
- plants to be bare root 450-600 high at planting, with Tubex quills and cane.

- 488no Corylus Avellana
 - 488no Cornus Sanguinea
 - 488no Cornus Alba
 - 488no Cornus Kelsey
 - 4881no Crataegus Monogyna
 - 976no Hammamelis Mollis
 - 244no Ribes Sanguineum
 - 244no Salix Alba
 - 244no Sambucus Nigra
 - 244no Viburnum Opulus
 - 488no Viburnum Lanata
 - 488no Euonymus Red Cascade
- plants to be bare root 450-600 high at planting, with Tubex quills and cane.

- Hedge
- 183no Acer Campestre
 - 92no Ulmus Glabra
 - 912no Crataegus Monogyna
 - 92no Sambucus Nigra
 - 92no Cornus Sanguinea
 - 183no Corylus Avellana
 - 92no Euonymus Europeans
 - 92no Prunus Spinosa
 - 92no Rosa Canina
- to be planted bare root two staggered rows at 350mm centres with 450mm between rows. to be protected with rabbit guard and stout cane

KEY

- wildflower grass seed mix
- short mown grass
- long grass strimmed annually
- new tree planting see species notes
- new hedge and shrub planting see species notes
- existing trees and hedges
- planning application boundary

Wildflower mix :
from BSH tel 01522 868714
www.bshamenity.com
seed mix type RE1

Festuca rubra ssp litoralis 36%
Cynosurus cristatus 24%
Agrostis capillans 14%
Trisetum Flavescence 6%
Anthoxanthum odoratum 2%
Plantago lanceolata 2%
Prunella vulgaris 1.5%
Ranunculus acris 1.5%
Filipendula ulmaria 1.5%
Ranunculus bulbosus 1.5%

- Achillea millefolium 1.5%
- Centaurea nigra 1.5%
- Galium verum 1.5%
- Leucanthemum vulgare 1.5%
- Leontodon hispidus 1%
- Agrimonia eupatorium 1%
- Rhinanthus minor 1%
- Lotus corniculatus 0.5%
- Sanguisorba minor 0.5%

- Tree Species**
- A Fraxinus Excelsior
 - B Quercus Robur
 - C Quercus Petraea
 - D Tilia Cordata
 - E Sorbus Ana
 - F Sorbus Aucupana Sheerwater Seedling
 - G Alnus Glutinosa
 - H Prunus Avium
 - J Carpinus Betulus
 - K Betula Pendula
 - L Pinus Nigra
- All trees to be feathered 150-175 high at planting bare root with Tubex quill and stake.

REVISION "C" HATCHING ADDED AUG 2009
REVISION "B" FOOTPATH / SWALE POSITION REVISED AUG 2009
REVISION "A" FOOTPATH POSITION REVISED AUG 2009

Countryside Properties (Special Projects) Ltd
The Drive Brentwood Essex CM13 3AT
Telephone 01277 260000 Facsimile 01277 690690
www.countryside-properties.co.uk E-mail Countryside@dal.pipex.com

david fountain designs ltd
Architectural and Landscape Design Consultants

The Design Studio
17y Lodge
71 Belmont Avenue
Wickford
Essex SS12 0HG

tel: 01268 461344
email: davidfountain@blueyonder.co.uk
mobile: 07730 064853
www.davidfountain.com
www.ascapes.dfm
www.gardenforkids.com

| | |
|---|--|
| Description LANDSCAPING DETAILS TO PERIMETER ROAD SL1, SL11, SL13, SL20 | Drawing Name BICESTER OXFORD |
| Drawn by DAVID FOUNTAIN | Dwg number DFD/BIG/L12 SHEET 3 OF 4 |
| Scale(s) 1:500@AO | Rev C |
| Date 8/4/2009 | |

