



KEY

- wildflower grass seed mix
- short mown grass
- long grass strimmed annually
- new tree planting see species notes
- new hedge and shrub planting see species notes
- existing trees and hedges
- planning application boundary

- 127no Corylus Avellana
 - 127no Cornus Sanguinea
 - 127no Cornus Alba
 - 127no Cornus Kelsey
 - 127no Crataegus Monogyna
 - 254no Hammamelis Mollis
 - 64no Ribes Sanguineum
 - 64no Salix Alba
 - 64no Sambucus Nigra
 - 64no Viburnum Opulus
 - 128no Viburnum Lanata
 - 128no Euonymus Red Cascade
- plants to be bare root 450-600 high at planting, with Tubex quills and cane.

- close mown grass
- 37no Lavandula Angustifolia 10-12L
 - 12no Phormium Tenax Variegated 25L
 - 19no Buddleia Davidi Empire Blue 10-12L
 - 4no Photinia Red Robin 25L
 - 69no Prunus Lisitanica 10-12L
 - 29no Photinia Red Robin 25L
 - 27no Phormium Tenax Variegated 25L
 - 28no Fuchsia Riccartonii 10-12L
 - 33no Hebe Great Orme 10-12L
 - 45no Lavandula Angustifolia 10-12L
 - 29no Photinia Red Robin 25L
 - 27no Phormium Tenax Variegated 25L
 - 4no Photinia Red Robin 25L
 - 5no Quercus Robur 35-40cm girth

- Hedge
- 36no Acer Campestre
 - 18no Ulmus Glabra
 - 216no Crataegus Monogyna
 - 18no Sambucus Nigra
 - 18no Cornus Sanguinea
 - 36no Corylus Avellana
 - 18no Euonymus Europeans
 - 18no Prunus Spinosa
 - 18no Rosa Canina
- to be planted bare root two staggered rows at 350mm centres with 450mm between rows, to be protected with rabbit guard and stout cane

- 26no Corylus Avellana
 - 26no Cornus Sanguinea
 - 26no Cornus Alba
 - 26no Cornus Kelsey
 - 26no Crataegus Monogyna
 - 52no Hammamelis Mollis
 - 13no Ribes Sanguineum
 - 13no Salix Alba
 - 13no Sambucus Nigra
 - 13no Viburnum Opulus
 - 26no Viburnum Lanata
 - 26no Euonymus Red Cascade
- plants to be bare root 450-600 high at planting, with Tubex quills and cane.

- Tree Species**
- A Fraxinus Excelsior
 - B Quercus Robur
 - C Quercus Petraea
 - D Tilia Cordata
 - E Sorbus Ana
 - F Sorbus Aucuparia Sheerwater Seedling
 - G Alnus Glutinosa
 - H Prunus Avium
 - J Carpinus Betulus
 - K Betula Pendula
 - L Pinus Nigra
- All trees to be feathered 150-175 high at planting bare root with Tubex quill and stake.

- Wildflower mix :
from B5H tel 01522 868714
www.bshamenity.com
seed mix type RE1
- Festuca rubra ssp litoralis 36%
 - Cynosurus cristatus 24%
 - Agrostis capillaris 14%
 - Trisetum Flavescens 6%
 - Anthoxanthum odoratum 2%
 - Plantago lanceolata 2%
 - Prunella vulgaris 1.5%
 - Ranunculus acris 1.5%
 - Filipendula ulmaria 1.5%
 - Ranunculus bulbosus 1.5%
 - Achillea millefolium 1.5%
 - Centaurea nigra 1.5%
 - Galium verum 1.5%
 - Leucanthemum vulgare 1.5%
 - Leontodon hispidus 1%
 - Agrimonia eupatorium 1%
 - Rhinanthus minor 1%
 - Lotus corniculatus 0.5%
 - Sanguisorba minor 0.5%

REVISION 'D' HATCHING ADDED AUG 2009
REVISION 'C' FOOTPATH / SWALE POSITION REVISED AUG 2009
REVISION 'B' FOOTPATH POSITION REVISED AUG 2009
REVISION 'A' PLANTING ADJACENT TO ENTRANCE ADDED JULY 2009

Countryside Properties (Special Projects) Ltd
Countyside House
The Drive, Brentwood, Essex, CM13 3AT
Telephone 01277 260000 Facsimile 01277 690900
www.countryside-properties.co.uk E-mail Countryside@dal.gipex.com

david fountain designs ltd
Architectural and Landscape Design Consultants

The Design Studio
Ivy Lodge
71 Belmont Avenue
Wickford
Essex SS12 2 OHG

tel/fax: 01268 461344
email: davidfountain@bucyonder.co.uk
mobile: 07730 064853
www.davidfountain.com
www.gardensforkids.com

Description
LANDSCAPING DETAILS TO PERIMETER ROAD
5L1, 5L1.1, 5L1.3, 5L20

Dwg number DFD/BIC/L13 SHEET 4 OF 4
Rev D

Scale(s) 1:500@A0
Date 2/4/2009