

ing trees and hedges retained

DEVELOPMENT

grass

de footpath/cycleway

wide footpath/cycleway

Revision D general revisions Feb 2010
Revision C drainage added Jan 2010
Revision B general revisions 18th Dec 2008



Countryside

STRATEGIC

Countryside Properties (Special Projects) Ltd

Countryside House

The Drive, Broomwood, Essex, CM13 3AT

Telephone 01277 360000, Facsimile 01277 690600

www.countryside-properties.co.uk, E-mail: Countryside@dial.pipes.com

david fountain designs ltd

Architectural and Landscape Design Consultants

The Design Studio

Ivy Lodge

71 Belmont Avenue

Wickford

Essex, SS12 0HG

tel/fax: 01268 461344

email: david.fountain@blueyonder.co.uk

mobile: 07730 064653

www.davidfountain.com

www.dscapes.com

www.gardenforhire.com

Description

LANDSCAPING DETAILS TO

PINGLE BROOK

Drawing Name

BICESTER, OXFORD

Dwg number

DPD/BIG/PB/L5 SHEET 1 OF 2

Scale(s)

1:500@AO

Date

11/12/2008

Drawn by

DAVID FOUNTAIN

Planting Schedule for thicket areas

Thicket Planting

Species	Percentage Mix	Size / Type
Crataegus Monogyna	30%	600-900 BR
Salix Caprea	20%	600-900 BR
Acer Campestre	15%	600-900 BR
Prunus Spinosa	15%	600-900 BR
Corylus Avellana	5%	600-900 BR
Cornus Sanguinea	5%	600-900 BR
Rosa Arvensis	5%	600-900 BR
Viburnum Opulus	2.5%	600-900 BR
Ulmus Glabra	2.5%	600-900 BR

plants to be 600-900 bare root stock at 1m centres each with stake and tie, plus rabbit spiral

Specimen Trees

Ref		
TA	Quercus Robur	10-12cm girth Standard RB
TB	Betula Pendula	10-12cm girth Standard RB
TC	Prunus Avium Plena	10-12cm girth Standard RB
TD	Sorbus Ana	10-12cm girth Standard RB
TE	Alnus Glutinosa	10-12cm girth Standard RB
TF	Fraxinus Excelsior	10-12cm girth Standard RB
TG	Fagus Sylvatica	10-12cm girth Standard RB
TH	Salix Alba	10-12cm girth Standard RB
TJ	Tilia Cordata	10-12cm girth Standard RB
TK	Acer Platanoides	10-12cm girth Standard RB

Long grass to be cut 4 times a year, selective weed killed throughout year

seed mix type A19

from BSH tel 01522 868714

www.bshamenity.com

Short mown grass - max 100mm minimum 25mm

Wildflower mix :

seed mix type A19

from BSH tel 01522 868714

www.bshamenity.com

Wildflower mix :

from BSH tel 01522 868714

www.bshamenity.com

seed mix type RE1

Festuca rubra ssp litoralis 36%

Cynosurus cnsatus 24%

Agrostis capillans 14%

Trisetum Flavescens 6%

Anthoxanthum odoratum 2%

Plantago lanceolata 2%

Prunella vulgaris 1.5%

Ranunculus acris 1.5%

Filipendula ulmaria 1.5%

Ranunculus bulbosus 1.5%

Achillea millefolium 1.5%

Centaurea nigra 1.5%

Galium verum 1.5%

Leucanthemum vulgare 1.5%

Leontodon hispidus 1%

Agrimonia eupatorium 1%

Rhinanthus minor 1%

Lotus corniculatus 0.5%

Sanguisorba minor 0.5%

Calcareous wildflower mix :

from BSH tel 01522 868714

www.bshamenity.com

seed mix type WFG5

Achillea millefolium

Anthyllus vulnina

Campanula glomerata

Centaurea nigra

Centaurea scabiosa

Clinopodium vulgare

Daucus carota

Galium verum

Geranium pratense

Leucanthemum vulgare

Lotus corniculatus

Medicago lupulina

Fragaria Vesca

Plantago media

Prunella vulgaris

Scabiosa columbana

Stachys officinalis

Festuca arundinacea

Cynosurus cnsatus

Festuca rubra ssp litoralis