



- TREES**
- A Sorbus Aucuparia Sheerwater Seedling 14-16cmg RB
 - B Sorbus Aria 12-14cmg RB
 - C Betula Pendula 12-14cmg RB
 - D Tilia Cordata 12-14cmg RB
 - E Prunus Avium 12-14cmg RB
 - F Acer Campestre 12-14cmg RB
 - G Pinus Sylvestris 60 litre CG
 - H Quercus Robur 12-14cmg RB
- Wildflower mix :
 from BSH tel 01522 868714
 www.bshamenity.com
 seed mix type RE1
- | | |
|---------------------------------|---------------------------|
| Festuca rubra ssp litoralis 36% | Achillea millefolium 1.5% |
| Cynosurus cristatus 24% | Centaurea nigra 1.5% |
| Agrostis capillans 14% | Galium verum 1.5% |
| Trisetum Flavascence 6% | Leucanthemum vulgare 1.5% |
| Anthoxanthum odoratum 2% | Leontodon hispidus 1% |
| Plantago lanceolata 2% | Agrimonia eupatorium 1% |
| Prunella vulgaris 1.5% | Rhinanthus minor 1% |
| Ranunculus acris 1.5% | Lotus corniculatus 0.5% |
| Filipendula ulmaria 1.5% | Sanguisorba minor 0.5% |
| Ranunculus bulbosus 1.5% | |
- Native Bulb Mix
 to be planted at 10 per sqm in groups of no less than 30 and no more than 60 consisting of:-
 Hyacinthoides - Non Scripta (English Bluebell)
 Pseudo Narcissus Lobulans (Wild Native Daffodil)
 Galanthus Nivalis (Native single Snowdrop)
 Leucojum Aestivum (Snowflake Bulbs)
- New Native Hedging and infilling :-
 50% Crataegus Monogyna
 10% Acer Campestre
 10% corylus Avellana
 5% Sambucus Nigra
 5% Ulmus Glabra
 5% Cornus Sanguinea
 5% Euonymus Europeans
 5% Rosa Canina
 to be planted bare root two staggered rows at 350mm centres with 450mm between rows, to be protected with rabbit guard and stout cane

Revision "D" General revisions Feb 2010
 Revision "C" General revisions Feb 2010
 Revision "B" General revisions 6th August 2009
 REVISION A 3M WIDE FOOTPATH / CYCLEWAY REVISED FEB 2009

| | | |
|---|--|------------------|
| Countryside Properties (Special Projects) Ltd Countryside House The Drive Brentwood Essex CM13 3AT Telephone 01277 260000 Facsimile 01277 690690 www.countryside-properties.co.uk E-mail Countryside@dial.pipex.com | david fountain designs ltd Architectural and Landscape Design Consultants The Design Studio Ivy Lodge 71 Belmont Avenue Wickford Essex SS12 0HG | |
| | tel/fax: 01268 461344 email:- davidfountain@blueyonder.co.uk mobile:- 07730 064853 www.davidfountains.com www.4scapes.com www.gardensforkids.com | |
| Description LANDSCAPING DETAILS TO GREENWAY SHEET 2 OF 2 SL6A | Drawing Name BICESTER OXFORD | Rev D |
| Drawn by DAVID FOUNTAIN | Dwg number DFD/BIC/SL6/L8 | Date 4/1/2009 |
| | Scale(s) 1:500@A1 | |