



Thicket Planting

Species	Percentage Mix	Size / Type
197no Crataegus Monogyna	50%	600-900 BR
594no Acer Campestre	15%	600-900 BR
594no Prunus Spinosa	15%	600-900 BR
20no Corylus Avellana	5%	600-900 BR
20no Cornus Sanguinea	5%	600-900 BR
20no Rosa Arvensis	5%	600-900 BR
10no Viburnum Opulus	2.5%	600-900 BR
10no Ulmus Glabra	2.5%	600-900 BR

plants to be 600-900 bare root stock at 1m centres each with stake and tie, plus rabbit spiral

NOTES

SPECIMEN TREES

Ref	Species
TA	Fraxinus Excelsior
TB	Sorbus Ana
TC	Betula Pendula
TD	Pinus Sylvestris 25L CG
TE	Prunus Avium
TF	Acer Campestre
TG	Quercus Robur

All trees to be feathered 150-175 high at planting bare root with Tubex quill and stake.

Thicket Hedge Planting - clipped to 1200 high

Species	Percentage Mix	Size / Type
507no Crataegus Monogyna	50%	600-900 BR
152no Acer Campestre	15%	600-900 BR
152no Prunus Spinosa	15%	600-900 BR
51no Corylus Avellana	5%	600-900 BR
51no Cornus Sanguinea	5%	600-900 BR
51no Rosa Arvensis	5%	600-900 BR
26no Viburnum Opulus	2.5%	600-900 BR
26no Ulmus Glabra	2.5%	600-900 BR

plants to be 600-900 bare root stock at 1m centres each with stake and tie, plus rabbit spiral

Thicket hedge planting
 2228no Crataegus monogyna 600mm br
 3714no Acer Campestre 600mm br
 3714no Prunus Spinosa 600mm br
 3714no Euonymus Europaeus 600mm br
 3714 Ligustrum Vulgare 600mm br
 to be planted bare root two staggered rows at 350mm centres with 450mm between rows, to be protected with rabbit guard and stout cane



Wildflower Grass seed mix :
 from BSH tel 01522 868714
 www.bshtmenty.com
 seed mix type RE1

Festuca rubra ssp litoralis 36%	Achillea millefolium 1.5%
Cynosurus cnistatus 24%	Centaurea nigra 1.5%
Agrostis capillans 14%	Galium verum 1.5%
Trisetum Flavescence 6%	Leucanthemum vulgare 1.5%
Anthoxanthum odoratum 2%	Leontodon hispidus 1%
Plantago lanceolata 2%	Agrimonia eupatorium 1%
Prunella vulgaris 1.5%	Rhnanthus minor 1%
Ranunculus acris 1.5%	Lotus corniculatus 0.5%
Filipendula ulmana 1.5%	Sanguisorba minor 0.5%
Ranunculus bulbosus 1.5%	

Grass (general amenity)
 seed mix type A19
 from BSH tel 01522 868714
 www.bshtmenty.com

REVISION "C" PLANNERS COMMENTS ADDED FEB 2010
 REVISION "B" GENERAL REVISIONS 26TH AUGUST 2009
 REVISION "A" GENERAL REVISIONS 6TH AUGUST 2009

Countryside
 STRATEGIC

Countryside Properties (Special Projects) Ltd
 Countryside House
 The Drive Brentwood Essex CM13 3AT
 Telephone 01277 260000 Facsimile 01277 690690
 www.countryside-properties.co.uk E-mail Countryside@dial.pipex.com

david fountain designs ltd
 Architectural and Landscape Design Consultants

The Design Studio
 Ivy Lodge
 71 Belmont Avenue
 Wickford
 Essex SS12 0HG

tel/fax- 01268 461344
 email- davidfountain@blueyonder.co.uk
 mobile- 07730 064853
 www.davidfountaindesigns.com
 www.4scapes.com
 www.gardenstorkids.com

Description	Drawing Name	Rev
SL3 LANDSCAPING DETAILS SHEET 2 OF 2	BICESTER OXFORD	C
Drawn by DAVID FOUNTAIN	Dwg number DFD/BIC/L15	Date
	Scale(s) 1:500@A1	

