

SL26

Planting Schedule for thicket areas

Thicket Planting

Species	Percentage Mix	Size / Type	A	B	C	D	E
Crataegus Monogyna	30%	600-900 BR	A 199no	B 189no	C 71no	D 120no	E 27no
Salix Caprea	20%	600-900 BR	A 133no	B 126no	C 47no	D 80no	E 18no
Acer Campestre	15%	600-900 BR	A 100no	B 95no	C 35no	D 60no	E 14no
Prunus Spinosa	15%	600-900 BR	A 100no	B 95no	C 35no	D 60no	E 14no
Corylus Avellana	5%	600-900 BR	A 34no	B 32no	C 12no	D 20no	E 7no
Cornus Sanguinea	5%	600-900 BR	A 34no	B 32no	C 12no	D 20no	E 7no
Rosa Arvensis	5%	600-900 BR	A 34no	B 32no	C 12no	D 20no	E 7no
Viburnum Opulus	2.5%	600-900 BR	A 17no	B 18no	C 6no	D 10no	E 3no
Ulmus Glabra	2.5%	600-900 BR	A 17no	B 18no	C 6no	D 10no	E 3no

plants to be 600-900 bare root stock at 1m centres
each with stake and tie, plus rabbit spiral

KEY

- existing trees to remain and be protected
- existing hedges and trees removed see Arb report

Primary School Site

HEDGES

Ref	Nr	Plant Name	Ht/Sprd/Gr	Root
Ac	505	Acer campestre	60-80	B
Cmg	3534	Crataegus Monogyna	90-100	B
Psp	505	Euonymus europaeus	80-90cm	B
Euon eur	505	Prunus spinosa	90-100	B

5049

REVISION "C" MINOR COMMENTS ADDED FEB 2010
REVISION "B" PLANNERS COMMENTS ADDED FEB 2010
REVISION "A" PLANNERS COMMENTS ADDED FEB 2010

Countryside
STRATEGIC

Countryside Properties (Special Projects) Ltd
Countryside House
The Drive Brentwood Essex CM13 3AT
Telephone 01277 260000 Facsimile 01277 690690
www.countryside-properties.co.uk E-mail Countryside@dial.pipex.com

david fountain designs ltd

International Architectural and Landscape Design Consultants

The Design Studio
Ivy Lodge
71 Belmont Avenue
Wickford
Essex SS12 0HG

tel/fax- 01268 461344
email- davidfountain@blueyonder.co.uk
mobile- 07730 064853
www.davidfountain.com
www.ascapes.com
www.gardensforkids.com

Description LANDSCAPING DETAILS TO SL 14, SL16, SL17, SL23	Drawing Name BICESTER OXFORD	Rev C
Dwg number DFD/BIC/L23	Scale(s) 1:500	Date JAN 2010