



|  |                         |
|--|-------------------------|
| Filipendula ulmaria 1.5%   | Lotus corniculatus 0.5% |
| Ranunculus bulbosus 1.5%   | Sanguisorba minor 0.5%  |
| Grass (general amenity)<br>seed mix type A19<br>from BSH tel 01522 868714<br>www.bshsamenity.com |                         |

**KEY**

|  |                                   |
|--|-----------------------------------|
|  | long grass                        |
|  | new shrub planting                |
|  | existing tree and shrub planting  |
|  | new tree planting                 |
|  | indicative line of mown path      |
|  | wildflower seed mix               |
|  | area of existing calcareous grass |

New Hedge Planting - clipped to 1200 high

| Species                  | Percentage Mix | Size / Type |
|--------------------------|----------------|-------------|
| 777no Crataegus Monogyna | 55%            | 600-900 BR  |
| 212no Fagus Sylvatica    | 15%            | 600-900 BR  |
| 212no Carpinus Betulus   | 15%            | 600-900 BR  |
| 212no Ligustrum Vulgare  | 15%            | 600-900 BR  |

plants to be 600-900 bare root stock at 450mm centres in two staggered rows 450mm apart each with stake and tie, plus rabbit spiral

**NOTES**

**SPECIMEN TREES**

| Ref | Species                 |
|-----|-------------------------|
| TA  | Fraxinus Excelsior      |
| TB  | Sorbus Ana              |
| TC  | Betula Pendula          |
| TD  | Pinus Sylvestris 25L CG |
| TE  | Prunus Avium            |
| TF  | Acer Campestre          |
| TG  | Quercus Robur           |

All trees to be feathered 150-175 high at planting bare root with Tubex quill and stake.

REVISION "F" LAP PLAY AREA REVISED JAN 2011  
 REVISION "E" PLANNERS COMMENTS ADDED MARCH 2010  
 REVISION "D" PLANNERS COMMENTS ADDED MARCH 2010  
 REVISION "C" PLANNERS COMMENTS ADDED MARCH 2010  
 REVISION "B" GENERAL REVISIONS 26TH AUGUST 2009  
 REVISION "A" GENERAL REVISIONS 6TH AUGUST 2009

**Countryside**  
 STRATEGIC

Countryside Properties (Special Projects) Ltd  
 Countryside House  
 The Drive Brentwood Essex CM13 3AT  
 Telephone 01277 260000 Facsimile 01277 698690  
 www.countryside-properties.co.uk E-mail Countryside@dial.pipex.com

**david fountain designs ltd**  
 Architectural and Landscape Design Consultants

The Design Studio  
 Ivy Lodge  
 71 Belmont Avenue  
 Wickford  
 Essex SS12 0HG

tel/fax- 01268 461344  
 email- davidfountain@blueyonder.co.uk  
 mobile- 07730 064853  
 www.daviddesigns.com  
 www.4scapes.com  
 www.gardenforkids.com

|  |                                 |                      |
|--|---------------------------------|----------------------|
| Description<br>SL3 LANDSCAPING DETAILS<br>SHEET 1 OF 2 | Drawing Name<br>BICESTER OXFORD | Rev<br>F             |
| Drawn by<br>DAVID FOUNTAIN                             | Dwg number<br>DFD/BIC/L14       | Scale(s)<br>1:500@A1 |
| Date   |                                 |                      |