



**Thicket Planting**

Species	Percentage Mix	Size / Type
197no Crataegus Monogyna	50%	600-900 BR
59no Acer Campestre	15%	600-900 BR
594no Prunus Spinosa	15%	600-900 BR
20no Corylus Avellana	5%	600-900 BR
20no Cornus Sanguinea	5%	600-900 BR
20no Rosa Arvensis	5%	600-900 BR
10no Viburnum Opulus	2.5%	600-900 BR
10no Ulmus Glabra	2.5%	600-900 BR

plants to be 600-900 bare root stock at 1m centres each with stake and tie, plus rabbit spiral

**Temporary Hedge Planting to top of haul road mound**

Species	Percentage Mix	Size / Type
1594no Crataegus Monogyna	55%	1000 BR
435no Fagus Sylvatica	15%	1000 BR
435no Carpinus Betulus	15%	1000 BR
435no Ligustrum Vulgare	15%	1000 BR

plants to be 1000 bare root stock at 450mm centres in two staggered rows 450mm apart each with stake and tie, plus rabbit spiral

**New Hedge Planting - clipped to 1200 high**

Species	Percentage Mix	Size / Type
1594no Crataegus Monogyna	55%	600-900 BR
435no Fagus Sylvatica	15%	600-900 BR
435no Carpinus Betulus	15%	600-900 BR
435no Ligustrum Vulgare	15%	600-900 BR

plants to be 600-900 bare root stock at 450mm centres in two staggered rows 450mm apart each with stake and tie, plus rabbit spiral

**New Hedge Planting - clipped to 1200 high**

Species	Percentage Mix	Size / Type
602no Crataegus Monogyna	55%	600-900 BR
164no Fagus Sylvatica	15%	600-900 BR
164no Carpinus Betulus	15%	600-900 BR
164no Ligustrum Vulgare	15%	600-900 BR

plants to be 600-900 bare root stock at 450mm centres in two staggered rows 450mm apart each with stake and tie, plus rabbit spiral

- NOTES**
- SPECIMEN TREES**
- Ref TA Fraxinus Excelsior
  - TB Sorbus Ana
  - TC Betula Pendula
  - TD Pinus Sylvestris 25L CG
  - TE Prunus Avium
  - TF Acer Campestre
  - TG Quercus Robur
- All trees to be feathered 150-175 high at planting bare root with Tubex quill and stake.

- KEY**
- long grass
  - new shrub planting
  - existing tree and shrub planting
  - new tree planting
  - indicative line of mown path
  - wildflower seed mix
  - area of existing calcareous grass

- Wildflower Grass seed mix :**  
 from BSH tel 01522 868714  
 www.bshamenity.com  
 seed mix type RE1
- |                                 |                           |
|---------------------------------|---------------------------|
| Festuca rubra ssp litoralis 36% | Achillea millefolium 1.5% |
| Cynosurus cnstatus 24%          | Centaurea nigra 1.5%      |
| Agrostis capillans 14%          | Galium verum 1.5%         |
| Trisetum Flavescence 6%         | Leontodon hispidus 1.5%   |
| Anthoxanthum odoratum 2%        | Leonodon hispidus 1%      |
| Plantago lanceolata 2%          | Agrimonia eupatorium 1%   |
| Prunella vulgaris 1.5%          | Rhinanthus minor 1%       |
| Ranunculus acris 1.5%           | Lotus corniculatus 0.5%   |
| Filipendula ulmana 1.5%         | Ranunculus bulbosus 1.5%  |
| Ranunculus bulbosus 1.5%        | Sanguisorba minor 0.5%    |
- Grass (general amenity)  
 seed mix type A19  
 from BSH tel 01522 868714  
 www.bshamenity.com

**Countryside**  
 STRATEGIC  
 Countryside Properties (Special Projects) Ltd  
 Countryside House  
 The Drive Brentwood Essex CM13 3AT  
 Telephone 01277 260000 Facsimile 01277 690690  
 www.countryside-properties.co.uk E-mail Countryside@dial.pipex.com

**david fountain designs ltd**  
 Architectural and Landscape Design Consultants  
 The Design Studio  
 Ivy Lodge  
 71 Belmont Avenue  
 Wickford  
 Essex SS12 0HG  
 tel/fax- 01268 461344  
 email- davidfountain@blueyonder.co.uk  
 mobile- 07730 064853  
 www.davidfountaindesigns.com  
 www.4scapes.com  
 www.gardenstorkids.com

<b>Description</b> LANDSCAPING TO HAUL ROAD ADJACENT TO SL3	<b>Drawing Name</b> BICESTER OXFORD	<b>Rev</b>
<b>Dwg number</b> DFD/BIC/L24	<b>Scale(s)</b> 1:500@A1	<b>Date</b> 31.08.2010

**Drawn by** DAVID FOUNTAIN