



147 No. Hypericum 'Hidcote'
 1 No. Carpinus betulus
 3 No. Cornus alba
 HEBE MIX
 72 No. Hebe albicans 'Red Edge' 30%
 72 No. Hebe 'White Gem' 30%
 95 No. Hebe rakaiensis 40%

28 No. Croisiya ternata

HEBE MIX
 117 No. Hebe albicans 'Red Edge' 30%
 117 No. Hebe 'White Gem' 30%
 155 No. Hebe rakaiensis 40%
 59 No. Cytisus scoparius

91 No. Cytisus scoparius

19 No. Cytisus scoparius

HEBE MIX
 166 No. Hebe albicans 'Red Edge' 30%
 166 No. Hebe 'White Gem' 30%
 221 No. Hebe rakaiensis 40%

364 No. Eucrymyrus fortunei 'Emerald 'n' Gold'

618 No. Mahonia aquifolium

47 No. Cornus alba

HEBE MIX
 165 No. Hebe albicans 'Red Edge' 30%
 165 No. Hebe 'White Gem' 30%
 220 No. Hebe rakaiensis 40%

261 No. Elaeagnus pungens

21 No. Philadelphus coronarius

NOTES:
 Based upon the Ordnance Survey map with permission of The Controller of Her Majesty's Stationery Office. © Crown Copyright.
 Aspect Landscape Planning Ltd, West Court, Hardwick Business Park, Noral Way, Banbury OX16 2AF.
 Licence 100045345
 Copyright reserved
 No Dimensions to be scaled from this drawing.

- KEY:**
- Site Boundary
 - Existing Trees
 - Proposed Trees
 - Proposed Hedge
 - Proposed Feature Shrub
 - Proposed Shrubs
 - Proposed Turf

PLANTING NOTES
 All plants to be supplied in accordance with the HTA 'National Plant Specification' and from a HTA certified nursery. All plants and trees to be planted in accordance with BS3936 and BS8545. Delivery and handling of all plant material to be in accordance with BS4428/JCL/CPSE Code of Practice for 'Handling and Establishing Landscape Plants' Parts I, II and III and BS8545.
Planting Pit and Trench Preparation
 Tree pits in soft landscape to be excavated to 1mx1mx1m depth prior to topsoiling and all shrub planting areas excavated to 450mm depth. All proposed hedge planting trenches to be excavated to 500mm depth. Unless otherwise specified, all tree pits in hard landscape to be 2mx2mx1m, backfilled with compacted Urban Tree Soil.
 The preparation of planting pits, bed or trenches shall comply with the appropriate British Standards, namely BS4043, BS4428, BS5837 and BS8545.
 Excavation of planting pits, bed or trenches shall not take place when the ground is frozen or waterlogged such that damage may occur to the structure of the soil. All excavated areas to be backfilled with either site won topsoil or imported topsoil to be BS3882-General purpose grade. All topsoiled areas to be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants. The Contractor shall break up and cultivate at the base of the trenches or planting pits. The sides of the trenches or planting pits shall be loosened with a fork or other similar implement. All stones and the like over 75mm in any dimension, deleterious matter, weeds and weed roots brought to the surface by any cultivation or excavation shall be removed off site. The Contractor shall remove off site the excavated subsoil material when preparing planting pits. The imported topsoil should make up any deficiencies caused by the removal of the subsoil material. Trenches and pits shall have the topsoil and any subsoil material thoroughly broken up and mixed prior to backfilling.
 All trees shall be supplied root balled, unless otherwise stated. Root balled trees shall be well grown, healthy and with a compact, contained rootball. They shall be nursery grown and have been regularly watered. Prior to planting, all plant material shall be stored and sorted at in accordance with best practice.
Planting
 All plants shall be planted in a random fashion avoiding formal regimented lines at densities indicated in the schedule, unless otherwise specified. Unless otherwise specified, all hedgerows shall be planted in a double staggered rows and hedgerow mixes shall be planted in groups of 7, 9 & 13s at densities indicated on the schedule. Ornamental shrub planting mixes shall be planted in groups of 5, 7 & 11s and relative shrub planting mixes shall be planted in groups of 9, 13 & 15s. The selection, procurement, handling, storage and planting operations of all proposed trees shall be in accordance with BS5854:2014 - Trees: from nursery to independence in the landscape, recommendations.
 Planting and associated operations shall comply with BS4043, BS4428, BS5837 and BS8545. Unless otherwise stated planting shall be carried out during the period of 1 Nov to 31 March when the ground is not frozen or water logged. If planting is required outside this period agreement shall be sought and all bare root plants shall be substituted with container grown stock.
Watering
 Proposed hedgerows should be maintained at a height of 1.2m.
 All plants shall be watered in to field capacity immediately after planting and mulched with 50mm depth of medium grade crushed mulch. The Contractor shall water the trees, shrubs and hedges once planted so that the entire tree pit or planted area is moistened to field capacity, i.e. "the amount of water retained by previously saturated soil once full drainage has ceased". Watering to field capacity shall continue frequently and on a regular basis as considered necessary by the landscape contractor and as necessary to ensure the successful establishment and continued thriving of all planting. Additional watering shall be undertaken during summer months and/or periods of drought. Post planting management and maintenance specifically for new tree planting shall include ongoing irrigation and formative pruning as outlined in BS8545. The period over which regular irrigation required for transplanted trees is likely to be at least two full growing seasons to ensure successful establishment. As the root system develops the frequency of irrigation can be reduced.
Staking
 All trees within soft landscape areas to be double staked with cross bar and tied, using 1.5m long, 75mm diameter rounded tree stakes 75mm brace, rubber tie and spacer block. Stakes not to extend more than 650mm above ground level. All trees within hardstanding/highways visibility splays to be clear stem to 1.5m high unless otherwise specified. Trees within hardstanding / specific pits to be underground guyed unless otherwise specified.
Root Barriers
 Root barriers (ReRoot 1000 or equivalent) to be included adjacent to buildings and services where necessary. Landscape contractor shall check all planting operations comply with appropriate standards and that in the absence of detailed surveys, any necessary underground investigations are undertaken to ensure there are no conflicts with existing or proposed utilities, services or foundations.
PROTECTION OF EXISTING VEGETATION TO BE RETAINED
 Existing trees to be retained shall be protected in accordance with BS5837, from commencement to completion of all works on site.

REV	DATE	NOTE	SLB	AM
H	05.15	Updated layout	SLB	AM
G	20.4.15	Updated to new layout	SLB	AM
F	03.15	Updated to Client Comments	SLB	AM
E	03.15	Updated layout	SLB	AM
D	03.15	Tree retention update	SLB	AM
C	18.2.15	Updated to Client comments	SLB	AM

REVISIONS

aspect landscape planning

TITLE
 Land at Mondelez International,
 Southam Road, Banbury
 Planting Plan (sheet 2 of 2)

CLIENT
 Barwood Capital & Mondelez International

SCALE	DATE	DRAWN	CHK'D
1:250@A1	NOV 2014	SLB	AM

DRAWING NUMBER	REVISION
5419/ ASP4-2	I