

Mountbatten House
 Basing View
 Basingstoke RG21 4HJ
 Date 18/02/2016
 File Area 2 Permeable Paving Design...

Area 2
 P.Paving
 10yr Rainfall Event
 Designed by UKLXB334
 Checked by UKJXW040
 Source Control 2015.1



Summary of Results for 10 year Return Period

Half Drain Time : 181 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Overflow (l/s)	Max Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	99.377	0.127	0.0	3.9	0.0	3.9	50.1	O K
30 min Summer	99.402	0.152	0.0	4.5	0.0	4.5	65.3	O K
60 min Summer	99.424	0.174	0.0	4.9	0.0	4.9	78.4	O K
120 min Summer	99.438	0.188	0.0	5.1	0.0	5.1	86.8	O K
180 min Summer	99.441	0.191	0.0	5.2	0.0	5.2	88.9	O K
240 min Summer	99.443	0.193	0.0	5.2	0.0	5.2	89.8	O K
360 min Summer	99.443	0.193	0.0	5.2	0.0	5.2	89.6	O K
480 min Summer	99.440	0.190	0.0	5.2	0.0	5.2	88.0	O K
600 min Summer	99.436	0.186	0.0	5.1	0.0	5.1	85.7	O K
720 min Summer	99.432	0.182	0.0	5.0	0.0	5.0	83.0	O K
960 min Summer	99.422	0.172	0.0	4.9	0.0	4.9	77.3	O K
1440 min Summer	99.405	0.155	0.0	4.5	0.0	4.5	66.7	O K
2160 min Summer	99.384	0.134	0.0	4.1	0.0	4.1	54.3	O K
2880 min Summer	99.370	0.120	0.0	3.8	0.0	3.8	45.3	O K
4320 min Summer	99.352	0.102	0.0	3.1	0.0	3.1	34.8	O K
5760 min Summer	99.341	0.091	0.0	2.6	0.0	2.6	28.2	O K
7200 min Summer	99.334	0.084	0.0	2.3	0.0	2.3	23.6	O K
8640 min Summer	99.328	0.078	0.0	2.0	0.0	2.0	20.3	O K
10080 min Summer	99.323	0.073	0.0	1.8	0.0	1.8	17.9	O K
15 min Winter	99.390	0.140	0.0	4.2	0.0	4.2	57.4	O K
30 min Winter	99.418	0.168	0.0	4.8	0.0	4.8	74.6	O K
60 min Winter	99.442	0.192	0.0	5.2	0.0	5.2	89.6	O K
120 min Winter	99.459	0.209	0.0	5.5	0.0	5.5	99.8	O K
180 min Winter	99.463	0.213	0.0	5.6	0.0	5.6	101.8	O K
240 min Winter	99.463	0.213	0.0	5.6	0.0	5.6	102.1	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Overflow Volume (m³)	Time-Peak (mins)
15 min Summer	60.901	0.0	52.3	0.0	18
30 min Summer	39.040	0.0	69.8	0.0	33
60 min Summer	24.003	0.0	88.1	0.0	62
120 min Summer	14.387	0.0	107.4	0.0	120
180 min Summer	10.582	0.0	119.4	0.0	150
240 min Summer	8.487	0.0	128.1	0.0	180
360 min Summer	6.204	0.0	141.1	0.0	246
480 min Summer	4.965	0.0	150.8	0.0	316
600 min Summer	4.175	0.0	158.6	0.0	384
720 min Summer	3.622	0.0	165.2	0.0	452
960 min Summer	2.895	0.0	175.8	0.0	586
1440 min Summer	2.109	0.0	191.4	0.0	838
2160 min Summer	1.535	0.0	207.5	0.0	1212
2880 min Summer	1.225	0.0	219.0	0.0	1560
4320 min Summer	0.891	0.0	235.0	0.0	2292
5760 min Summer	0.711	0.0	245.6	0.0	3008
7200 min Summer	0.596	0.0	253.2	0.0	3744
8640 min Summer	0.517	0.0	258.7	0.0	4416
10080 min Summer	0.458	0.0	262.8	0.0	5152
15 min Winter	60.901	0.0	59.8	0.0	18
30 min Winter	39.040	0.0	79.4	0.0	32
60 min Winter	24.003	0.0	99.9	0.0	60
120 min Winter	14.387	0.0	121.6	0.0	116
180 min Winter	10.582	0.0	135.0	0.0	168
240 min Winter	8.487	0.0	144.8	0.0	190

Mountbatten House
 Basing View
 Basingstoke RG21 4HJ
 Date 18/02/2016
 File Area 2 Permeable Paving Design...
 Micro Drainage

Area 2
 P.Paving
 10yr Rainfall Event
 Designed by UKLXB334
 Checked by UKJXW040
 Source Control 2015.1



Summary of Results for 10 year Return Period

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (1/s)	Max Control (1/s)	Max Overflow (1/s)	Max Σ Outflow (1/s)	Max Volume (m³)	Status
360 min Winter	99.460	0.210	0.0	5.5	0.0	5.5	100.5	O K
480 min Winter	99.455	0.205	0.0	5.4	0.0	5.4	97.1	O K
600 min Winter	99.448	0.198	0.0	5.3	0.0	5.3	92.9	O K
720 min Winter	99.441	0.191	0.0	5.2	0.0	5.2	88.5	O K
960 min Winter	99.426	0.176	0.0	4.9	0.0	4.9	79.9	O K
1440 min Winter	99.402	0.152	0.0	4.5	0.0	4.5	64.7	O K
2160 min Winter	99.375	0.125	0.0	3.9	0.0	3.9	48.4	O K
2880 min Winter	99.359	0.109	0.0	3.4	0.0	3.4	38.7	O K
4320 min Winter	99.341	0.091	0.0	2.6	0.0	2.6	27.7	O K
5760 min Winter	99.330	0.080	0.0	2.1	0.0	2.1	21.4	O K
7200 min Winter	99.322	0.072	0.0	1.8	0.0	1.8	17.5	O K
8640 min Winter	99.316	0.066	0.0	1.6	0.0	1.6	14.8	O K
10080 min Winter	99.311	0.061	0.0	1.4	0.0	1.4	12.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Overflow Volume (m³)	Time-Peak (mins)
360 min Winter	6.204	0.0	159.4	0.0	266
480 min Winter	4.965	0.0	170.3	0.0	342
600 min Winter	4.175	0.0	179.2	0.0	416
720 min Winter	3.622	0.0	186.6	0.0	486
960 min Winter	2.895	0.0	198.6	0.0	626
1440 min Winter	2.109	0.0	216.4	0.0	882
2160 min Winter	1.535	0.0	234.8	0.0	1256
2880 min Winter	1.225	0.0	248.1	0.0	1612
4320 min Winter	0.891	0.0	266.7	0.0	2336
5760 min Winter	0.711	0.0	279.5	0.0	3056
7200 min Winter	0.596	0.0	288.8	0.0	3752
8640 min Winter	0.517	0.0	295.9	0.0	4496
10080 min Winter	0.458	0.0	301.3	0.0	5240

Mountbatten House
 Basing View
 Basingstoke RG21 4HJ
 Date 18/02/2016
 File Area 2 Permeable Paving Design...
 Micro Drainage

Area 2
 P.Paving
 10yr Rainfall Event
 Designed by UKLXB334
 Checked by UKJXW040
 Source Control 2015.1



Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	10	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.000	Shortest Storm (mins)	15
Ratio R	0.420	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.547

Time (mins)		Area
From:	To:	(ha)
0	4	0.547

Mountbatten House
 Basing View
 Basingstoke RG21 4HJ

Area 2
 P.Paving
 10yr Rainfall Event



Date 18/02/2016

Designed by UKLXB334

File Area 2 Permeable Paving Design...

Checked by UKJXW040

Micro Drainage

Source Control 2015.1

Model Details

Storage is Online Cover Level (m) 100.000

Porous Car Park Structure

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	45.0
Membrane Percolation (mm/hr)	1000	Length (m)	45.0
Max Percolation (l/s)	562.5	Slope (1:X)	500.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	99.250	Cap Volume Depth (m)	0.000

Orifice Outflow Control

Diameter (m) 0.080 Discharge Coefficient 0.600 Invert Level (m) 99.250

Weir Overflow Control

Discharge Coef 0.544 Width (m) 1.200 Invert Level (m) 99.463