



© 2012 RPS Group
 Notes
 1. This drawing has been prepared in accordance with the scope of RPS's appointment with its client and is subject to the terms and conditions of that appointment. RPS accepts no liability for any use of this document other than by its client and only for the purposes for which it was prepared and provided.
 2. If received electronically it is the recipient's responsibility to print to correct scale. Only written dimensions should be used.
 3. This drawing should be read in conjunction with all other relevant drawings and specifications.

FINISHES KEY

ADAPTIVE

- Backstop Road Construction
- Backstop Footway Construction
- Footway Construction (Concrete Paving Slabs)
- Vehicle Crosser Construction (Concrete Paving Slabs)
- Blockwork Road Construction: Impermeable Service Margins and Crossings
- Blockwork Road Construction: Permeable
- Verge Construction
- Blockwork Drive Construction: Permeable
- Patio Slabs

FINISHES

- Blockwork Road Construction: Permeable
- Blockwork Drive Construction: Permeable

MATERIAL KEY

- Tactile paving (colour to be confirmed) with Flush (0-5mm upstand) Conservation Kerbs and Channel Block
- Conservation Dropper Kerbs
- Conservation Kerbs and Channel Block: Silver Grey, 100mm upstand
- Conservation Kerbs and Channel Block: Silver Grey, 25mm upstand
- Conservation Kerbs and Channel Block: Silver Grey, Flush (0-5mm upstand)
- Conservation Kerbs: Silver Grey, Flush
- Edging Kerbs Type EF: Flush

BOUNDARY TREATMENT KEY

- 1.8m Close Boarded Fence
- Dashed Line Indicates Gravel Board
- Timber Knee Rail
- Natural Waste Fencing
- 1.8m Masonry Wall
- 1.5m Masonry Wall with 0.3m Treils
- 0.6m Versacore Brick Wall
- 0.9m Black Metal Railing with Formal Hedge
- 1.2m Black Metal Railing
- 1.2m Black Metal Railing with Finials

P2 Updated to latest base layout. JB KMc: 26.09.16

P1 FIRST ISSUE JB KMc: 29.07.16

Rev	Description	By	Chk	Date

For guidance only. Do not scale off this drawing.

RPS

Mobile House
 Capital Drive, Linford Wood, Milton Keynes MK14 6DP
 T: +44 (0)1908 666698 E: rpsmk@rpsgroup.com F: +44 (0)1908 666699

Client **Bellway**

Project **Kingsmere, Bicester
 KM5 & KM22**

Title **Finishes Drawing
 Sheet 2 of 3**

Status	Scale	Date Created
Preliminary	1:200 @A0	29.07.2016

Project Leader	Drawn By	Checked By
KMc	JB	KMc

Drawing Number	Rev
JJK8310 _105	P2

rpsgroup.com

