



new planting around substation to be a continuation of existing hedge

Species	Percentage Mix	Size / Type
Crataegus Monogyna	60%	600-900 BR
Prunus Spinosa	10%	600-900 BR
Corylus Avellana	10%	600-900 BR
Cornus Sanguinea	10%	600-900 BR
Viburnum Opulus	10%	600-900 BR

plants to be 600-900 bare root stock at 600mm centres in staggered double row 600 apart each with stake and tie, plus rabbit spiral

- Revision ZR Play areas revised 3/2/2014
- Revision ZQ Planners comments added 12/12/2013
- Revision ZP Planners comments added 28/08/2013
- Revision ZM Sub Station repositioned and landscaping revised accordingly 13/2/2013
- Revision ZL Play Areas combined and repositioned, landscaping redesigned accordingly Jan 2013
- Revision ZK Ash trees replaced - maintenance access added 12/12/12
- Revision ZJ Play Area repositioned
- Revision ZH Play Area repositioned 17/9/2012
- Revision ZF Footpath lighting-bollards and maintenance access added 23/8/2012
- Revision ZE Play area moved away from Bovis Development / landscaping to rear of play area repositioned to front 22/06/2012
- Revision ZD minor revisions 30/05/2012
- Revision ZC Planners comments added 28/05/2012
- Revision ZB Planners comments added 25/01/2012
- Revision ZA minor revisions 21/02/2012
- Revision Z Junction Barriers added 19/01/2012
- Revision Y Planners comments added 17/01/2012
- Revision X Substation Removed revised 11/11/2011
- Revision V Bench Positions revised 9/11/2011
- Revision U Planners comments added 31/10/2011
- Revision T Buffer Zone revised 26/7/2011
- Revision S Bridge numbers added 13/05/2011
- Revision R footpaths revised March 2011
- Revision Q footpath adjacent to existing woodland re-aligned Feb 2011 therefore planting revised
- Revision P Planting removed to allow visibility from housing Feb 2011
- Revision N red lines added for reserved matter drawings Dec 2010
- Revision M Sub Station added Dec 2010
- Revision L Planners comments added June 2010
- Revision K general revisions June 2010
- Revision J Planners comments added April 2010
- Revision H Planners comments added April 2010
- Revision G Planners comments added April 2010
- Revision F Planners comments added April 2010
- Revision E note ref grass reinforced strip added March 2010
- Revision D general revisions Feb 2010
- Revision C drainage added Jan 2010
- Revision B general revisions 18th Dec 2008

Orcha  
Whistl  
51 Tr  
Warbc  
Oxon  
Telep  
Facsir  
Email:  
or any

Countryside Properties (Special Projects) Ltd  
Countryside House  
The Drive Brentwood Essex CM13 3AT  
Telephone 01277 260000 Facsimile 01277 690690  
www.countryside-properties.co.uk E-mail: Countryside@dial.pipex.com

<b>Architectural and Landscape Design Consultants</b> The Design Studio Ivy Lodge 71 Belmont Avenue Wickford Essex S51 2 OHG		tel/fax: 01268 461344 email: davidfountain@blueyonder.co.uk mobile: 07730 064853 www.davidfountains.com www.4scapes.com www.gardensfortdcs.com
<b>Description</b> LANDSCAPING DETAILS TO PINGLE BROOK		<b>Drawing Name</b> BICESTER OXFORD <b>Dwg number</b> DFD/BIC/PB/LG SHEET 2 OF 2 <b>Rev</b> ZR <b>Scale(s)</b> 1:500@A1 <b>Date</b> 11/12/2008
<b>Drawn by</b> DAVID FOUNTAIN		<b>Date</b> 11/12/2008

Existing Woodland  
Woodland to be deadwooded as per the approved Arboncultural Report and recommendations, Existing regeneration including all Sycamore saplings to be cleared and the shrub layer within the woodland replaced with additional planting to include equal quantities of Illex Aquifolium, Corylus Avellana, and Crataegus Monogyna planted 450 - 600 bare root at 2.1m centres with cane and rabbit guards.