




FRONT ELEVATION

-  Safety Glazing
-  Obscure Glazing
-  E - Escape Window

BT Customer splice point - BT entry point to external brickwork and internal spur point. Cable to run through the floor void to BT point (where fibre equipment is stored).

Chimney 553 x 890mm

Roof pitch: 40°

Eaves to be constructed in accordance with eaves detail.

Entrance canopy style 1.

Facing brick to all elevations as indicated : to be constructed in accordance with manufacturer's recommendations and structural engineer's design.

Casement windows with horizontal bar to all elevations.

Stone heads and cills all elevations.

Refer to Site general Door and Window schedules for details.

Provide Code 4 leadwork flashing with cavity tray over to all abutments.

All entrance doors to have flush threshold and internal transition strip to suit mobility standards in accordance with Approved Document M, refer to standard detail SUP/DPC/LT.

Refer to development engineers site layout for locations of ramp / steps. Provide stepped DPC 150mm above top of threshold.

Movement joints in accordance with Structural Engineers requirements.

***NOTE:**

If upper floor openable window is within 800mm of floor, internal guarding will be required in accordance with standard detail INT/M/G/1. Additionally safety glazing will also be required if within 800mm of finished floor level.

Revisions:

Ref.	Date	Details
B	20/12/16	BT Customer splice point shown as clients markub.
A	11/08/16	Drive through opening reduced as per letter 12/08/16.

Belway

BELWAY HOMES NORTHERN-HOME-COUNTIES MILTONKEYNES

Site Location KINGSMERE KM5 & KM22

BICESTER

TOVE - PLOTS 103, 104 & 117

FRONT ELEVATION

SHEET 5 of 16

Scale	1:50	Date	08.02.16
Drawing No.	113/281	Rev.	B
Drawn By:	CDA	Checked By:	CDA
Cad Ref:			

THIS DRAWING IS A COPYRIGHT. All dimensions to be checked on site or in the workshop before work commences. Only figured dimensions to be worked to. Any discrepancies to be reported to the Architect.

HANDINGS	PLOTS
AS	15, 104 & 117
OPP	26, 64 & 103

Carlton Design Architecture Ltd
 Architectural Consultants
 7 The Old Dairy Buildings, Winburn, Northamptonshire, NN22 8PQ.
 Tel: 01636 656333 Facsimile: 01636 656123
 E MAIL: carlton.design@virgin.net