

Declaration of Performance

EC Construction Products Regulation
EN 12326 Roofing & Cladding Slate



PRIMERA
SLATE COMPANY LIMITED

16 Woodlands
Warboys
Huntingdon
Cambridgeshire
PE28 2UR
Tel: +44 (0)1487 825 222
Fax: +44 (0)1487 825 240
info@primeraslate.co.uk
www.primeraslate.co.uk

DOP Number:		17/018			
1. Unique identification code of the product-type:		Elapi			
2. Type, batch or serial number or any other element allowing identification of the construction product:		30X20 35x20 40x20 40x25 50x25 50X30 60X30			
3. Intended use or uses of the construction product, in accordance with the applicable harmonized technical specification, as foreseen by the manufacturer:		Slate for discontinuous roofing and cladding			
4. Name, registered trade name or registered trade mark and contact address of the manufacturer:		Pizarras Elapi Conde Fenosa 10. 32300 barco De Valdeorras, Spain			
5. Where applicable, name and contact address of the authorised representative:		N/A			
6. System or systems of assessment and verification of consistency of performance of the construction product:		System 4			
7. In case of the declaration of performance concerning a construction product covered by a harmonized standard:		The manufacturer has carried out factory production control and determination of product type based upon System 4 within the Assessment of Conformity Tasks.			
8. In case of the declaration of performance concerning a construction product covered by a European Technical Assessment:		N/A			
9. Declared Performance:					
Essential Characteristic for Pitched Roof Coverings:	Performance:		Harmonized Technical Specification:		
Mechanical Resistance:	Mean Failure Load:		EN12326-2:2011		
	Transverse: 442.9 N	Longitudinal: 578.5 N			
	Characteristic MOR:				
	Transverse: 50.2 Mpa	Longitudinal: 66.3 Mpa			
External Fire Performance:	Deemed to satisfy		EC Decision 2000/553/EC		
Reaction to Fire:	Deemed to satisfy Class A1		EC Decision 96/603/EC as amended		
Dimensional Variation:			EN12326-2:2011		
Slate Type:	Very Smooth	Smooth		Normal	Textured
Deviation from flatness:		<1.0%			
Nominal thickness and variation:		5mm +/- 35%			
Deviation from declared width:	+/- 5mm				
Deviation from declared length:	+/- 5mm				
Deviation from straightness of edges:	+/- 5 mm				
Deviation from rectangularity:	+/- 1%				
Durability:					
Water absorption:	Code A1 0.25%				
Freeze thaw:	Not Required				
Thermal cycle test:	Code T1				
Carbonate content:	0.04%				
Sulphur dioxide exposure tests:	Code S1				
Non-carbonate carbon content:	1.20%				
Release of dangerous substances:	None in conditions of use as roofing or external cladding		EN12326-2:2011		
10. Declaration: The product(s) identified in Points 1 and 2 is in conformity with the declared performance under point 9. This declaration of performance is the sole responsibility of the manufacturer identified in point 4.					
Place & Date of Issue: PRIMERA SLATE COMPANY LIMITED 16 Woodlands, Warboys, Huntingdon, Cambs PE282UR 21 st April 2017		Name: Mr. Stephen Harding Position: Managing Director Signature:			