



Total area = 2456m²
75% imp = 1842m²
Cellular Soakaway (Polystorm)
0.8m deep
Area of Soakaway = 156m²
Volume of Soakaway = 125m³
Soakaway Soffit Level = 72.82
Pipe in (outfall) Invert Level = 72.47
Soakaway Invert Level = 71.82

Total area = 2055m²
75% imp = 2218m²
Cellular Soakaway (Polystorm)
0.8m deep
Area of Soakaway = 180m²
Volume of Soakaway = 143m³
Soakaway Soffit Level = 72.46
Pipe in (outfall) Invert Level = 72.46
Soakaway Invert Level = 71.86

Total imp area = 1779m²
Cellular Soakaway (Polystorm Xtra)
0.4m deep
Area of Soakaway = 710m²
Volume of Soakaway = 88m³
Soakaway Soffit Level = 72.26
Pipe in (outfall) Invert Level = 72.06
Soakaway Invert Level = 71.86

RC15	457516.042	221954.227	72.788
SB15	457544.293	222104.939	72.570
LS1	457122.571	222104.799	72.684
LS2	457239.436	221984.374	72.584
LS3	457369.116	221904.181	72.954
LS4	457496.171	221904.567	71.906
LS5	457455.368	222160.829	71.641

2m HIGH TIMBER FENCING ADJACENT TO COMMERCIAL BUILDINGS TO BE IN ACCORDANCE WITH COUNTRYSIDE PROPERTIES APPROVED DETAILS.

Notes

- The Contractor shall check all levels for line and level with existing before commencing any works. The Engineer shall be notified immediately in writing should any errors be found.
- Any discrepancies, of whatever nature, must be reported to the Engineer prior to the commencement or continuation of any further work.
- It is the responsibility of the Contractor to execute the works at all times in strict accordance with the requirements of the Health and Safety at Work Act 1974 and the C.M.A. Regulations 2015. The Contractor will be deemed to have allowed for full compliance, including full liaison with the principal designer, with no exceptions.
- All private drainage works to be in accordance with the requirements of Building Regulations 2000, Part H, "Drainage and waste disposal". Pipes with less than 100mm cover to be protected in accordance with Part H, Diagram 11.
- All pipes to be 100 or 110mm dia. All foul to be laid at 1 in 80 unless stated otherwise. All Storm to be laid at minimum 1 in 100 unless stated otherwise.
- All pipes, chambers and fittings to be installed, bedded and backfilled in accordance with the manufacturers instructions.
- Pipes which run adjacent to buildings shall be installed in strict accordance with Part H, Clause 2 to 2.5.
- All manholes and inspection chambers situated in areas subject to vehicular loading to have min class B125 covers and frames to BS EN1241:2010 will be required (showed on drawings and not part of these drawings should be sought from B.H.E. Engineers). Those not subject to vehicular loading are to have class A15 covers and frames.
- All drains in the vicinity of existing or proposed trees to be constructed in accordance with the requirements of N.H.E.C. Practice Note 3.
- Private drainage frames must be tied to manhole risers by use of manufacturers ties (eg. Polystorm ref FR3000 being an FR3000 back tie). The ground works contractor will be held fully responsible for any accidents due to incorrect fitting or failure to use the correct manufacturer's fixing equipment.
- All existing land drains encountered on site during construction to be reconnected.
- Should any departure from the slab level be considered, agreement shall be sought from the Engineer immediately and prior to commencement or continuation of any works, and should take full account of all restrictions to the slab level.
- Where a drive slopes towards a garage there is to be a 20mm upstand to the garage slab.
- All dimensions in metres unless otherwise stated.

Key - Refer to Bovis Homes Standard Details

- 400mm dia shallow inspection chamber (Max depth to invert 600mm)
- 400mm dia inspection chamber (Not max entry 350mm restricted access required depths greater than 1m)
- Foul backdrop manhole
- Surface water 400mm dia inspection chamber (Not max entry 350mm restricted access required for depths greater than 1m)
- Surface water backdrop manhole
- ACO Drainage Channel (refer to standard details drawing for specification)
- Roading Eye
- Yard Gully (refer to standard details drawing for specification)
- Land Drain
- CP refers to catch pit 300mm deep sump (refer to standard details drawings)
- Retaining Wall Drain - 80mm dia perforated pipe (refer to standard details drawings)
- External wall protected by tanking. Face breakback to 150mm above retained level.
- External wall where showing more than 150mm of exposed brickwork. Max. dimension from FTL to external ground level.
- Double Damp Proof course. See standard tanking detail.
- Brickwork Retaining Wall (RW) 750 number denotes retained height. Dist. represent numbers where falls are greater than 600mm. Handrail minimum 1100mm high.
- Slab on Edge (SE) 450 number denotes retained height.
- Gravel Board (GB) 450 number denotes retained height.
- Steps. Each step to have a rise of 150mm with a girth of 200mm. Every flight with 3 or more risers to have a suitable handrail on one side. This grabrail handrail to be 500-1000mm above the pitch line of the flight and extend 300mm beyond the top and bottom nosings.
- Garden or drive gradient.
- Proposed spot level.
- Banking works. 1:3 unless stated otherwise.

FFL 95.70 Finished Floor level
LSL 94.10 Garage slabs are given as Lowest Slab Level (LSL) and relate to the finished level of concrete at the front entrance of the garage.

Infiltration Key - Refer to PJS Details

- Indicates location of Polystorm Soakaway. Refer to PJS drawing 117 Private drainage infiltration details.
- Indicates location of Polystorm Dfuser wrapped in 2mm mesh. Refer to PJS drawing 117 Private drainage infiltration details.

Rainwater pipe positions are assumed - Bovis Homes to confirm

A	Jan 18	Soakaway removed from LP.	TM	RP
Rev.	Date	Amendments	By	CHK. by

PJS CONSULTING ENGINEERS
PJS Consulting Engineers Ltd (Limited Liability Company) Registered in England, No. 10137891
Registered office: 101, The Quadrant, Bicester, Oxfordshire, OX9 3DQ
Registered number: 10137891. Tel: 01295 781000. Email: info@pjs.co.uk

Client: **BOVIS HOMES**
Project: **BICESTER KME**
Drawing title: **PRIVATE DRAINAGE & EXTERNAL WORKS**

Drawn	Checked	Status	Scale
TM	RP	TENDER	A0 @ 1:200
Date	10 OCT 17	17	
Project No.	PJS17-06	Drawing No.	118
		Sheet	A