

Method statement

Here is a method statement regarding the rebuild of the wall at Ceder lodge.

We are using the original stone which will be from the demolition of the existing dangerous wall. The rebuild will consist of using sand lime mortar mix which is left in the mixer for 20 minutes to allow for it to aerinite before use. There will be no need to source any stone as there will be enough to rebuild the new wall, from the old wall. Capping of the wall with original ridge tiles to match existing wall.

I have attached photos of the test panel and also all measurements and any other paperwork you should need from the architect (David Stuart)