


THE FINEST TIMBER WINDOWS & DOORS

Order confirmation : 2001028

(Please Note: Images viewed from outside. Arrow denotes hinge position)

Item	Quantity	Description	Per Item	Total															
1	1 No.	 <p>MIAN HOUSE - KITCHEN Product: Concealed Spring Sash V/Slider Size: 1340 mm x 1973 mm Weight: 94 kg Frame Timber: Red Grandis / Engineered Hardwood Sash Timber: Laminated Larch / Red Grandis Finish: Fully Finished Paint 3 Coat Colour: RAL 9003 Signal White Frame Width: Head 94 Cill 68 Left 61 Right 61 Sash Width:</p> <table border="1"> <thead> <tr> <th>SNo</th> <th>Top</th> <th>Bottom</th> <th>Left</th> <th>Right</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>64</td> <td>43</td> <td>64</td> <td>64</td> </tr> <tr> <td>2</td> <td>43</td> <td>94</td> <td>64</td> <td>64</td> </tr> </tbody> </table> <p>Frame Profile: Square Liner Sash Profile: Ovolo Bar: 22mm Ovolo Applied Glazing Bars Sash: Top Sash with Horns Bottom Sash without Horns Openings: Concealed Spring Sash - Top Sash Concealed Spring Sash - Bot Sash Hardware: White 4600 mm2 Trickle Vent Sash Hook Catch - Antique Brass - 2 No. No Sash Pulls Antique Brass Security Lock - 2 No. White Spring Balances No Sash Restrictors -- FSC Material Used -- White Canopy 4600 mm2 SashLifts - Antique Brass - 2 No. {sent loose} 120mm Head Stop Suitable as Fire Escape (on equal split windows only) Attachments: Flush Cill Grooved for Window Board Only Glass Specification: 1.1 4mm Clear Toughened / 16mm Argon / 4mm Clear Toughened Soft Coat Low-E PLUS Black WarmEdge Spacer (Std) 2.1 4mm Clear Toughened / 16mm Argon / 4mm Clear Toughened Soft Coat Low-E PLUS Black WarmEdge Spacer (Std)</p>	SNo	Top	Bottom	Left	Right	1	64	43	64	64	2	43	94	64	64	£ 1,727.92	£ 1,727.92
SNo	Top	Bottom	Left	Right															
1	64	43	64	64															
2	43	94	64	64															

GLAZED WITH BLACK GLAZING TAPE



FM624029 EMS624030