

**KEY**

- Site boundary
- Existing trees/hedgerow to be retained
- Existing trees/hedgerow to be removed
- Existing pond retained
- Proposed footpath links
- Proposed attenuation basins
- Proposed residential parcels
- Proposed 2m wide surfaced footpaths
- Proposed on plot / front garden trees
- Proposed fitness equipment station
- Proposed bench seating

LEAP Proposed LEAP  
LAP Proposed LAP  
P Proposed trim trail station  
Proposed 2m wide bark mulch footpath

**STREET TREES INDICATIVE PLANT SCHEDULE**

**PRIMARY ROAD**

SPECIES	SUPPLY	SIZE(cm)	GIRTH(cm)
Acer platanoides 'Emerald Queen'	EHStd	450/625	16/18
Acer platanoides 'Deborah'	EHStd	450/625	16/18
Carpinus betulus 'Fastigiata'	EHStd	450/625	16/18
Tilia cordata 'Green Spire'	EHStd	450/625	16/18

**SECONDARY ROAD**

SPECIES	SUPPLY	SIZE(cm)	GIRTH(cm)
Betula utilis 'Jaquemontii'	EHStd	450/625	16/18
Carpinus betulus 'Frans Fontaine'	EHStd	450/625	16/18
Prunus padus 'Albertii'	EHStd	450/625	16/18
Pyrus calleryana 'Chanticleer'	EHStd	450/625	16/18

**TERTIARY ROAD**

SPECIES	SUPPLY	SIZE(cm)	GIRTH(cm)
Amelanchier lamarckii	EHStd	450/625	16/18
Malus trilobata	EHStd	450/625	16/18
Prunus serrulata 'Sunset Boulevard'	EHStd	450/625	16/18

**MEWS LINK**

SPECIES	SUPPLY	SIZE(cm)	GIRTH(cm)
Acer campestre 'Elsrijk'	EHStd	450/625	16/18
Prunus sargentii 'Rancho'	EHStd	450/625	16/18
Pyrus calleryana 'Chanticleer'	EHStd	450/625	16/18

**TREES - to public open spaces**

SPECIES	SUPPLY	SIZE(cm)	GIRTH(cm)
Acer campestre	EHStd	425/600	14/16
Alnus glutinosa	EHStd	425/600	14/16
Betula pendula	EHStd	425/600	14/16
Fagus sylvatica	EHStd	425/600	14/16
Malus sylvestris	EHStd	425/600	14/16
Prunus avium	EHStd	425/600	14/16
Quercus petraea	EHStd	425/600	14/16
Quercus robur	EHStd	425/600	14/16
Sorbus aria	EHStd	425/600	14/16
Sorbus aucuparia	EHStd	425/600	14/16
Tilia cordata	EHStd	425/600	14/16

**TREES - to southern boundary buffer**

SPECIES	SUPPLY	SIZE(cm)	GIRTH(cm)
Acer campestre	EHStd	425/600	14/16
Betula pendula	EHStd	425/600	14/16
Malus sylvestris	EHStd	425/600	14/16
Prunus avium	EHStd	425/600	14/16
Sorbus aria	EHStd	425/600	14/16
Sorbus aucuparia	EHStd	425/600	14/16

**NATIVE MIX/INFILL HEDGEROW (infill to existing)**

SPECIES	MIX(%)	SUPPLY	SIZE(cm)	CENTRES (m)
Acer campestre	10	T 1+1	60/80	0.30 double staggered row
Cornus sanguinea	10	T 1+1	60/80	0.30 double staggered row
Corylus avellana	15	T 1+1	60/80	0.30 double staggered row
Crataegus monogyna	35	T 1+1	60/80	0.30 double staggered row
Ilex aquifolium	10	T 1+1	60/80	0.30 double staggered row
Prunus spinosa	15	T 1+1	60/80	0.30 double staggered row
Rosa canina	5	T 1+1	60/80	0.30 double staggered row

**NATIVE SHRUB MIX**

SPECIES	MIX(%)	SUPPLY	SIZE(cm)	BREAKS	CENTRES (m)
Acer campestre	10	T 1+1	60/80	3	1.00
Cornus sanguinea	10	T 1+1	60/80	3	1.00
Corylus avellana	10	T 1+1	60/80	3	1.00
Crataegus monogyna	25	T 1+1	60/80	3	1.00
Ilex aquifolium	10	2L	60/80	3	1.00
Malus sylvestris	5	T 1+1	60/80	3	1.00
Prunus spinosa	15	T 1+1	60/80	3	1.00
Rosa canina	5	T 1+1	60/80	3	1.00
Viburnum opulus	10	T 1+1	60/80	3	1.00

**PRIMARY ROAD HEDGEROW**

SPECIES	SUPPLY	SIZE(cm)	CENTRES (m)
Prunus lusitana	10L	80/100	0.50

**RESIDENTIAL EDGE HEDGEROW**

SPECIES	SUPPLY	SIZE(cm)	CENTRES (m)
Carpinus betulus	3L	60/80	4 per metre
Fagus sylvatica	3L	60/80	4 per metre

**MARGINAL PLANTING**

SPECIES	SUPPLY	MP
Angelica sylvestris (Wild Angelica)	plug	10
Berula erecta (Great Water Parsnip)	plug	10
Caltha palustris (Marsh Marigold)	plug	10
Filipendula ulmaria (Meadowweet)	plug	10
Glyceria maxima (Reed sweet grass)	plug	10
Iris pseudacorus (Yellow flag)	plug	10
Juncus effusus (Soft rush)	plug	10
Juncus inflexus (Hard rush)	plug	10
Lycopus europaea (Oppenheim)	plug	10
Lylthrum salicaria (Purple loosestrife)	plug	10
Mentha aquatica (Water mint)	plug	10
Myosotis aquatica (Water forget-me-not)	plug	10
Phalaris arundinacea (Reed canary-grass)	plug	10
Scrophularia auriculata (Water figwort)	plug	10
Vernicia beccabunga (Brooklime)	plug	10

Pond marginal planting to be sourced from certified local provenance plant stock.

**AMENITY GRASS SEED MIX**

A22 low maintenance amenity grass seed mix as supplied by Germinal Seeds or similar approved. Sown at 50g/m2 and implemented as set out below.

**SPECIAL GENERAL PURPOSE MEADOW GRASSLAND (EM3)**

Special General Purpose Meadow Mixture - EM3 as supplied by Emorsgate Seeds or similar approved. Sown at 4g/m2 and implemented as set out below.

**MEADOW MIXTURE FOR WETLANDS (EM8)**

Meadow Mixture for Wetlands - EM8 as supplied by Emorsgate Seeds or similar approved. Sown at 4g/m2 and implemented as set out below.



Rev	Description	Date	Drawn	Chkd
D	Updated to revised layout & redline	24/05/21	AP	AP
C	Updated to revised redline	09/04/21	AP	AP
B	Updated to revised site layout	08/02/21	AP	AP
A	Updated to revised site layout	24/03/21	AP	AP

**COUNTRYSIDE**  
Places People Love

Himley Village, Bicester  
Phase 1 - POS Landscape Masterplan

scale: 1 to 1250 @A1	drawn by: AP
date: 05/02/2021	checked: AP
drawing no: P20-3215_23	sheet no: 1
revision: D	