

	LINK ROAD
Design Speed	30mph
Footway	2.0m
Cycleway	3.0m
Bus Access	Yes
Bus Stops	2no in both directions of travel. Cage markings
Maximum No of Properties served	No restriction
Carriageway Width	6.75m
Access to properties	Some direct access but generally from secondary streets
Carriageway surfacing	Non-porous construction stone mastic asphalt
Footway surfacing	Tarmac
Kerbing	Concrete kerb
Traffic calming	60m intervals
On street parking	Limited to short sections
Parking restriction	At White Post Road junction
Forward visibility	43m
Junction radii	6.0m
Street Lighting	To be agreed

TABLE 1361/HS/1/A

**HIGHWAYS SPECIFICATION
LAND OFF WHITE POST ROAD, BANBURY**