

# Proposed Great Wolf Lodge Chesterton, Bicester

## Flood Risk Assessment

Curtins Ref: 068535-CUR-00-XX-RP-C-00001

Revision: P02




Issue Date: November 2019

Client Name: Great Lakes UK Limited

Site Address: Land to the east of M40 and south of A4095, Chesterton, Bicester,  
Oxfordshire OX26 1TE

Curtins Consulting Limited  
17-19 Whitworth Street West  
Manchester  
M1 5WG  
Tel: 0161 236 2394  
Email: manchester@curtins.com  
www.curtins.com

CIVILS & STRUCTURES • TRANSPORT PLANNING • ENVIRONMENTAL • INFRASTRUCTURE • GEOTECHNICAL • CONSERVATION & HERITAGE • PRINCIPAL DESIGNER  
Birmingham • Bristol • Cambridge • Cardiff • Douglas • Dublin • Edinburgh • Glasgow • Kendal • Leeds • Liverpool • London • Manchester • Nottingham



Rev	Description	Issued by	Checked	Date
P01	Preliminary Issue for Comment	MCS	TL	08/10/19
P02	Issued for Planning	MCS	TL	11/11/19

This report has been prepared for the sole benefit, use, and information for the client. The liability of Curtins Consulting Limited with respect to the information contained in the report will not extend to any third party.

Author	Signature	Date
<b>Michael Smith</b> MEng (Hons) Senior Infrastructure Engineer		11/11/19

Reviewed	Signature	Date
<b>Tom Leake</b> MEng (Hons) CEng MICE Head of Infrastructure South		11/11/19

Curtins has prepared this report on the basis of information provided by Noting Hill Genesis and others including Private Companies and Government authorities, which Curtins Consulting Ltd has not independently verified or checked beyond the agreed scope of work. Curtins does not accept liability in connection to such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.

Curtins Consulting Ltd has prepared this report based on the provided and available information. Investigations are required to confirm scope, assumptions and conclusions. The opinions, conclusions and any recommendations in this report are based on assumptions made by Curtins Consulting Ltd described in this report.

## Table of Contents

Table of Contents .....	ii
Tables .....	iv
1.0 Introduction.....	1
1.1 Overview .....	1
1.2 Scope of Flood Risk Assessment .....	1
2.0 National and Local Policy Considerations .....	2
2.1 National Planning Policy Framework .....	2
2.2 Planning Practice Guidance.....	2
2.3 Local Planning Policy Requirements .....	3
2.3.1 The Cherwell Local Plan 2011-2031 .....	3
2.3.2 Strategic Flood Risk Assessment .....	3
2.3.3 Oxfordshire Flood Risk Management Plan .....	4
3.0 Existing Site Details.....	5
3.1 Location and Description.....	5
3.2 Topography .....	6
3.3 Existing Watercourses .....	6
3.4 Public Drainage.....	7
3.5 Private Drainage.....	8
3.6 Site Geology.....	10
4.0 Sources and Extents of Flooding .....	11
4.1 Natural Drainage .....	11
4.1.1 Fluvial Flooding .....	11
4.1.2 Pluvial Flooding and Overland Flow.....	12
4.1.3 Groundwater Flooding.....	12
4.1.4 Climate Change.....	14
4.2 Artificial Drainage .....	14
4.2.1 Adopted Drainage .....	14

4.2.2	Private Drainage System .....	14
4.2.3	Highway Drainage .....	15
4.2.4	Reservoir Flooding .....	15
4.3	Exceedance Flooding Flow paths .....	16
5.0	Flood Risk Mitigation .....	18
5.1	Natural Drainage .....	18
5.1.1	Fluvial Flooding .....	18
	Pluvial Flooding and Overland Flow .....	18
5.1.2	Groundwater Flooding.....	19
5.1.3	Climate Change.....	20
5.2	Artificial Systems .....	21
5.2.1	Adopted Drainage .....	21
5.2.2	Private Drainage.....	21
5.2.3	Highway Drainage .....	21
5.2.4	Development Drainage .....	21
5.3	Summary .....	22
6.0	Sequential Test.....	24
7.0	Conclusions and Recommendations .....	25
7.1	Overview .....	25
	Appendices .....	26
	Appendix A – Topographical Survey .....	27
	Appendix B – Proposed Site Layout.....	28
	Appendix C – Thames Water Sewer Records.....	29
	Appendix D – UAV Non-Intrusive Groundwater Survey .....	30
	Appendix E – Inferred Groundwater Levels From Pond Levels .....	31
	Appendix F – Proposed Below Ground Drainage Strategy .....	32
	Appendix G – Proposed Land Drainage Strategy .....	33
	Appendix H – Thames Water Foul Discharge Correspondence .....	34

## Figures

Figure 3-1: Aerial View with Site Boundary (red) and Gagle Brook (blue)	5
Figure 3-2: Oxfordshire CC Flood Toolkit Extract	6
Figure 3-3: Extract of Thames Water Sewer Plans	7
Figure 3-4: Existing Site Ditch Network	8
Figure 3-5: Surface Water Discharge Route	9
Figure 3-6: UAV Groundwater Survey	10
Figure 4-1: Environment Agency Flood Zone Map	11
Figure 4-2: Risk of flooding from surface water	12
Figure 4-3: Site Topography and Inferred Groundwater Levels	13
Figure 4-4: Aerial Imagery Showing Evidence of Land Drainage	15
Figure 4-5: Risk of flooding from reservoirs	16
Figure 4-6: Overland Flow Paths	17
Figure 5-1: Historic Mapping (circa 1980's)	19
Figure 5-2: QBAR Calculations	22

## Tables

Table 2-1 - PPG Tables 1 & 2 Summary	2
Table 5-1 - Flood Risk Summary	23

---

## 1.0 Introduction

### 1.1 Overview

Curtins Consulting Limited has been appointed by Great Lakes UK Limited to prepare a site-specific Flood Risk Assessment (FRA) for the proposed development of Great Wolf Lodge, Chesterton, Bicester ('Proposed Development').

Proposals contained or forming part of this report represent the design intent and may be subject to alteration or adjustment in completing the detailed design for this project. Where such adjustments are undertaken as part of the detailed design and are deemed a material derivation from the intent contained in this document, prior approval shall be obtained from the relevant authority in advance of commencing such works.

Where the proposed works, to which this report refers, are undertaken more than twelve months following the issue of this report, Curtins Consulting Ltd shall reserve the right to re-validate the findings and conclusions by undertaking appropriate further investigations at no cost to Curtins Consulting Ltd.

Allowance for the effects of climate change will be made in accordance with government recommendations in place and statistical data available at the time of writing this report. These recommendations may become more onerous and the statistical data may be revised in the future; we will not make any estimate of what changes may result from this. Please be aware that this, and other issues over which the Curtins Consulting has no control, may affect future flood risk at the development and require further work to be undertaken for which we accept no liability.

### 1.2 Scope of Flood Risk Assessment

The assessment is to be undertaken in accordance with the standing advice and requirements of the Environment Agency for Flood Risk Assessments as outlined in the Communities and Local Governments Technical Guidance to the National Planning Policy Framework (NPPF).

The assessment will:

- Investigate all potential risks of current or future flooding to the Site;
- Consider the impact the Proposed Development may have elsewhere with regards to flooding; and
- Consider design proposals to mitigate any potential risk of flooding determined to be present.

The purpose of this report is to assist our client and the Local Planning Authority to make an informed decision on the flood risks associated with the Site's development. Local Planning Authorities have the powers to control developments, in line with recent legislation, and are expected to apply a risk-based approach to development.

## 2.0 National and Local Policy Considerations

### 2.1 National Planning Policy Framework

In recent years, the Government and local authorities have placed increased priority on the need for developers to take full account for the risks of their development at all stages of the planning process. The National Planning Policy Framework (NPPF) and Planning Practice Guidance (PPG) identifies how the issue of flooding is dealt with through the planning process and with the creation of a site-specific Flood Risk Assessment (FRA) for sites over 1ha in area or in Flood Zones 2 & 3.

### 2.2 Planning Practice Guidance

The Government's Planning Practice Guidance (PPG) provides additional information to be read alongside the NPPF. The online guidance sets out the definitions for the flood zones and defines the permitted uses of development that can be proposed in them. The table below provides a summary of this guidance and refers to Table D.2 in the PPG.

**Table 2-1 - PPG Tables 1 & 2 Summary**

Flood Zone	Appropriate Users
Flood Zone 1 - Low Probability This zone comprises land having less than 1 in 1000 annual probability of river or sea flooding (<0.1%)	All uses of land are appropriate in this zone
Flood Zone 2 - Medium Probability This zone comprises land assessed as having between 1 in 100 and 1 in 1000 annual probability of river flooding (1%-0.1%) or between 1 in 200 and 1 in 1000 annual probability of sea flooding (0.5%- 0.1%) in any year	The water-compatible, less vulnerable and more vulnerable uses of land and essential infrastructure in Table D.2 are appropriate in this Zone Subject to the Sequential Test being applied, the highly vulnerable uses in Table D.2 are only appropriate in this zone if the Exception Test is passed
Flood Zone 3a - High Probability This zone comprises land assessed as having a 1 in 100 or greater annual probability of river flooding (>1%) or a 1 in 200 or greater annual probability of flooding from the sea (>0.5%) in any year	The water-compatible and less vulnerable uses of land in Table D.2 of the PPG-TG are appropriate in this zone. The highly vulnerable uses in Table D.2 should not be permitted in this zone. The more vulnerable and essential infrastructure uses in Table D.2 should only be permitted in this zone if the Exception Test is passed. Essential infrastructure permitted in this should be designed and constructed to remain operational and safe for users in time of flood.
Flood Zone 3b - Functional Floodplain This zone comprises land where water has to flow or be stored in times of flood. SFRA's should identify this Flood Zone (land which would flood with an annual probability of 1 in 20 (5%) or greater in any year or is designed to flood in an extreme (0.1%) flood, or at another probability to be agreed between the LPA and the Environment Agency, including water conveyance routes)	Only the water-compatible uses and the essential infrastructure listed in Table D.2 that has to be there should be permitted in this zone. It should be designed and constructed to: Remain operational and safe for users in times of flood; Result in no net loss of floodplain storage; Not impede water flows; and Not increase flood risk elsewhere. Essential infrastructure in this zone should pass the Exception Test.

## 2.3 Local Planning Policy Requirements

### 2.3.1 The Cherwell Local Plan 2011-2031

This FRA has been written in line with the current revision of the Cherwell Local Plan. The plan is aimed to support and guide developments in the area between 2011-2031.

This report has been specifically produced with the following policies in mind;

#### Policy ESD 6: Sustainable Flood Risk Management

This policy aims to reinforce the guidance set out in the NPPF and outlines Cherwell's requirements for new developments in respect to flooding. As with the requirements of the NPPF, ESD 6 outlines the requirements of site-specific flood risk assessment. The policy states the need of the FRA to demonstrate that there will be no increase in surface water discharge or volume emanating from a site for any event up to and including the 1 in 100 year (plus climate change), it also places the requirement for developments not to experience flooding for any events up to and including the 1 in 30 year storm event, ensuring any flood water is held safely on site.

#### Policy ESD 7: Sustainable Drainage Systems (SuDS)

This policy aims to promote the use of SuDS for all new developments in the management of surface water runoff. The policy states that;

*"Where site specific Flood Risk Assessments are required in association with development proposals, they should be used to determine how SuDS can be used on particular sites and to design appropriate systems.*

*In considering SuDS solutions, the need to protect ground water quality must be taken into account, especially where infiltration techniques are proposed. Where possible, SuDS should seek to reduce flood risk, reduce pollution and provide landscape and wildlife benefits. SuDS will require the approval of Oxfordshire County Council as LLFA and SuDS Approval Body, and proposals must include an agreement on the future management, maintenance and replacement of the SuDS features"*

### 2.3.2 Strategic Flood Risk Assessment

Cherwell District Council produced a SFRA in May 2017 which provides an update on a previous version with new legislative policy and summary of flood risk in Cherwell. The document provides guidelines on use of SuDS and guidance for FRAs. The document requires consideration of groundwater emergence as part of the decision-making process on the type of the SuDS techniques. The list of items to be provided with drainage strategy is included below.

Site Drainage Strategy to include:

- SuDS proposals;



- Outfall locations and levels, including confirmation from relevant authorities that the proposed outfall location will be accepted;
- Rates of discharge including confirmation from relevant authorities that the proposed discharge rate will be accepted;
- On-site storage requirements including storage location indicated within the proposed development plan, confirmation that it is to be located outside the existing 1% AEP+CC flood extent, and evidence that sufficient space is available; and
- Maintenance, funding and operation proposals for the SuDS.

### **2.3.3 Oxfordshire Flood Risk Management Plan**

Oxfordshire County Council acts as the Lead Local Flood Authority for the county. A Flood Risk Management Strategy has been produced as part of this role, with an aim to;

- Setting out a long-term programme for flood risk reduction.
- Setting out procedures for identifying relative priorities of measures for flood risk reduction.
- Establish how to find area where a holistic approach to flood risk reduction will achieve multiple benefits.
- Establish how to identify affordable measures for implementation to agreed time frames,
- Facilitate engagement and consultation with community and strategic partners.
- Encourage public awareness and self-help where appropriate.

### 3.0 Existing Site Details

#### 3.1 Location and Description

The Site is currently used as part of an 18-hole golf course associated with Bicester Hotel, Golf and Spa (BHGS). The project proposes to use the north western 9 holes as the Site for the development, turning the existing golf course from an 18 hole to a 9-hole golf course. The Site's main access is currently from the south, via a dedicated entrance of Green Lane. There is a secondary access to the service area from the West off the A4095. The Site planning boundary has a total area of 18.6ha. It is proposed to construct a new part 3, part 4-storey 498 room hotel and waterpark with associated parking for approximately 900 vehicles. The Site will also offer indoor activates, conference facilities, food and beverage hall and public nature trails.

The proposed impermeable area of the development is approximately 7.2ha. This area is made up of the proposed structures and associated hardstanding, areas contributing to the drainage network, car park and access roads.

The Site can be seen in the topographical survey found in **Appendix A**, and the proposed site plan in **Appendix B**.



**Figure 3-1: Aerial View with Indicative Site Boundary (red) and Gagle Brook (blue)**

### 3.2 Topography

The information provided within the topographical survey enclosed in **Appendix A** indicates that the Site generally grades from north-west to south-east along the A4095 road on the north east boundary of the Site; with levels falling from around 87mAOD to 81mAOD. The Site is a typical golf course with various landscaping features such as ponds, lakes and water features across the Site with the majority located towards the north. The water features on the Site are believed to be fed by groundwater, however further site investigations are required to confirm this.

### 3.3 Existing Watercourses

The closest watercourse is Gagle Brook (Ordinary Watercourse) located 500m away, to the north east of the Site. This watercourse flows to the south before turning into an EA main river, approximately 2km south of Bicester. Approximately 4km downstream, Gagle Brook flows into the River Ray.

Oxfordshire County Council has produced a Flood Toolkit which identifies the drains and watercourses within the vicinity of the Site. It indicates drains in the south-east boundary of the of the golf course (outside site boundary) connecting to the network of ditches. Another short ditch network in the east within Bignell Park connects to Gagle Brook. Figure 3-2 below shows the ditch networks.




Figure 3-2: Oxfordshire CC Flood Toolkit Extract

### 3.4 Public Drainage

The Thames Water Asset Location Search indicates that there are no public sewers within the vicinity of the Site. The nearest foul sewer (TW Manhole 7601) is located approximately 500m away to the east of the Site along A4095. It serves the residential area around Alchester Road.

There are no surface water sewers within the vicinity of the Site, there is a surface water network east of the Site in Chesterton. This serves the residential area and discharges to the Gaggle Brook. Refer to **Appendix C** for Thames Water asset records and Figure 3-3 below for an extract.

It should be noted that this plan does not include information regarding sewer connections from individual properties or any sewers not owned by Thames Water.

Information regarding the highway drainage for the A4095 has been requested from Cherwell District Council, however their records only showed the gully locations with no below ground information.




Figure 3-3: Extract of Thames Water Sewer Plans

### 3.5 Private Drainage

Following a visit to the Site and a walk over with the BHGS site maintenance staff, it has been seen that the BHGS buildings are served by a series of below ground foul water drains. These direct flows to the east and south of the hotel building where foul flows are discharged into pump chambers. From here, sewerage is pumped across the southern 9 holes to the Thames Water foul water manhole 7601 beneath the A4095. It is understood from maintenance staff that the macerator pumps used by BHGS are currently operating at full capacity.

Surface water across the Site is collected via a range of above and below ground systems. There is a ditch network that manages land drainage and overland flow from the golf course and green spaces to the north and south of the hotel.

Roof drainage is managed by guttering and rain water pipes, guiding the surface water to a below ground drainage system. The surrounding hardstanding and car parking areas are drained using road and yard gullies.

All surface water collection systems discharge into an existing pond to the south of the hotel, or further downstream into the network of ditches which flow southward, off site.

Figure 3-4 shows the arrangement of this ditch network. The Site boundary is all drained via two ditches that outfall via a 300mm diameter pipe into a pond to the south of BHGS (labelled northern and southern ditch below). The pond has a high-level outfall discharging to the ditch network shown in Figure 3-5. It is understood that the pond is used for irrigation of the Site in summer. From the available information and following the aforementioned site visits, it is assumed that all surface water is currently discharged from the Site via a series of swales and culverts, leading flows southward to Gagle Brook. Figure 3-5



shows the approximate route, with swales shown in green and culverts in purple. This is the

**Figure 3-4: Existing Site Ditch Network With Indicative Site Boundary**

understanding taken from the flow direction of the ditched on the topographical survey, site walk overs and evidence given by the BHGS's maintenance staff.




Figure 3-5: Surface Water Discharge Route With Indicative Site Boundary

### 3.6 Site Geology

The Site is underlain at rockhead by various formations and members of the Great Oolite Group, which are dominated by limestones with subordinate mudstone beds.

The lower part of the Cornbrash Formation is the youngest (uppermost) bedrock unit represented, it comprises limestone with mudstone. Underlying this is the Forest Marble Formation with the White Limestone Formation beneath that.

The Cornbrash Formation is a local unconfined aquifer and is categorised by the Environment Agency (EA) as a 'Secondary A Aquifer' (permeable layers supporting water supplies and stream base flows). The groundwater in the Cornbrash is perched on the low permeability of the Forest Marble beneath, which acts as an aquiclude, separating the Cornbrash from the White Limestone.

An unmanned aerial vehicle (UAV) survey was conducted across the Site to better understand the groundwater levels in the Cornbrash. An extract of the results is shown in The drawing is shown in **Appendix D**.

Figure 3-6. It can be seen that groundwater levels to the east and south of the Site are close to the ground surface. The drawing is shown in **Appendix D**.




Figure 3-6: UAV Groundwater Survey

## 4.0 Sources and Extents of Flooding

Numerous sources of flood risk need to be assessed to be in line with the requirements for planning under NPPF and Environment Agency requirements. This report takes into consideration fluvial flooding (rivers and streams), pluvial flood risk (surface water), tidal flooding (coastal or estuarine), reservoir flooding, groundwater flooding, infrastructure failure flooding and any historical flooding reports.

### 4.1 Natural Drainage

#### 4.1.1 Fluvial Flooding

The Environment Agency's (EA) Flood Map for Planning shows that the Site is located within Flood Zone 1 - Low probability of flooding. This zone comprises of land assessed as having less than a 1 in 1000 annual probability of river or sea flooding. All classifications of vulnerable developments are allowed within this zone. Since the Site area is larger than 1 ha, this FRA will investigate other sources of flood risks for the development.




Figure 4-1: Environment Agency Flood Zone Map

There is no flood risk from the Gagle Brook Watercourse reported in Environment Agency's flood maps or local authority flood maps to the Site.

The risk to Site from fluvial sources is therefore considered as low.



#### 4.1.2 Pluvial Flooding and Overland Flow

Surface water flooding occurs when intense rainfall is unable to soak into the ground or enter drainage systems, because of blockages, or breakages in the sewer pipes or where drainage capacity has been exceeded.

The Environment Agency’s online mapping shows no flood risk from surface water within the Site as shown in Figure 4-2 below. Therefore, flooding risk from surface water is considered low for this Site.




Figure 4-2: Risk of flooding from surface water

#### 4.1.3 Groundwater Flooding

As previously discussed, the Site geology creates a perched groundwater table within the uppermost geology beneath the Site – the Cornbrash Formation. This groundwater is perched by the Forest Marble aquiclude beneath.

The Site is occupied by a number of ponds, largely to the north with some in the south. These ponds are assumed to be fed by groundwater and offer an insight into the groundwater levels. The information contained in Figure 4-3 shows the groundwater levels across the Site, inferred from the pond levels, the full drawing is shown in **Appendix E**.

Cherwell and West Oxfordshire SFRA notes that the Site is underlain by minor aquifer with high vulnerability. The SFRA contains a list of potential development sites and includes locations from Chesterton, where the sites are not considered to be materially affected with regards to groundwater flooding. The Site location area has not been identified with any previous flooding incidents.



**Figure 4-3: Site Topography and Inferred Groundwater Levels**

While groundwater flooding may not result in an immediate flood hazard due to the slow rate at which seepage occurs, it has implications on the viability of infiltration methods as a means for surface water disposal and on the design of sub-structures. Any SuDS design will be carried out considering the high groundwater levels. Certain SuDS methods such as infiltration techniques might be unsuitable for the Site.

Whilst initial indicators highlight that areas of the Site are at risk of high groundwater; further site investigations will be required to monitor the change in groundwater level seasonally.

The Site is considered to be at moderate risk of groundwater flooding.

---

#### **4.1.4 Climate Change**

Climate change will impact on fluvial and pluvial flooding. Flood extents may not significantly increase; however, it can become more frequent.

The effect of climate change on groundwater flooding has a more significant influence on winter flood flows. Wetter winters may increase the frequency of groundwater flooding, but drier summers may counteract this effect by drawing down groundwater levels.

The Environment Agency's new climate change guidance has been considered in this development to ensure that flows during the 100-year event are retained within the Site. The surface water drainage system will be designed considering a return period of 100 years plus 40% climate change event.

### **4.2 Artificial Drainage**

#### **4.2.1 Adopted Drainage**

Sewer flooding occurs when the sewer is overwhelmed by heavy rainfall, becomes blocked or is of inadequate capacity, and will continue until the water drains away.

Asset location search for Thames Water assets has shown that there are no sewers within the vicinity of the Site. Cherwell and West Oxfordshire Level 1 SFRA records no sewer flooding for site location.

Oxfordshire County Council as the Highway Authority is responsible for the drainage of public streets and ensuring that drains, kerbs, road gullies and the pipe network which connects to the public sewers are maintained.

The proposed drainage strategy explains the discharge locations in detail following the discussions with Thames Water and LLFA.

The Site therefore has a very low risk of flooding from adopted sewers.

#### **4.2.2 Private Drainage System**

The Site does not currently have any hardstanding that is positively drained. However, there is a network of land drainage across sections of the Site. This network has been seen to exist during a site walk over and can be seen on aerial mapping available online.



**Figure 4-4: Aerial Imagery Showing Evidence of Land Drainage**

It is anticipated that the extents of this land drainage will affect the flow profile of surface water emanating from the Site, and as a result, increase the peak discharge from that of a greenfield site.

Existing land drains will collect surface water falling on the south eastern areas of the golf course and convey them to the ditch system running across the Site, faster than would occur on an undeveloped site.

#### **4.2.3 Highway Drainage**

Highway drainage information has been requested from Oxfordshire County Council, however their records only contained the location of gullies. As the surrounding highways are not at an elevated risk of surface water flooding, as demonstrated in section 4.1.2. it is assumed that there is a low risk of flooding to the Site by the surrounding highway drains.

#### **4.2.4 Reservoir Flooding**

The EA's online mapping shows no flood risk from surface water within the Site as shown in Figure 4-5. Therefore, flooding risk from reservoirs is considered low.




Figure 4-5: Risk of flooding from reservoirs

### 4.3 Exceedance Flooding Flow paths

As the Site currently has no formal below ground surface water drainage, the only exceedance flows will be overland flows created when rainfall is unable to infiltrate into the ground. Due to the Site topography, this water will flow south east towards the existing ditch network outlined in Section 3.5. This will then be led southward off the Site towards Gagle Brook. These routes are shown in Figure 4-6.




Figure 4-6: Overland Flow Paths

## 5.0 Flood Risk Mitigation

This section responds to the major risks outlined to the undeveloped site in Section 4 and offers mitigating measures that will aim to reduce the risk of flooding to the Site, as well as sites both up and downstream. The proposed Drainage Strategy drawing is contained in **Appendix F** and further discussed in Curtins Below Ground Drainage Strategy document (068535-CUR-00-XX-RP-C-00002).

### 5.1 Natural Drainage

#### 5.1.1 Fluvial Flooding

With reference to the Environment Agency's published flood maps (see Figure 4-1: Environment Agency Flood Zone Map in section 4.1.1) the Site can be shown to be in Flood Zone 1.

The sitewide surface water network is proposed to discharge into a network of existing ditches and drains, which in turn discharge to Gagle Brook. As the Site is in Flood Zone 1, there is a low risk of flooding from rivers and the sea already, it is therefore seen as acceptable to discharge via this route.


The risk to the Site from fluvial flooding therefore remains low and unchanged. As the Site is currently positively drained and unrestricted however, the proposed restriction will decrease fluvial flood risk downstream

#### 5.1.2 Pluvial Flooding and Overland Flow

The proposed development will include SuDS features to optimise the impermeable area and manage levels to direct flows away from buildings. It should be noted that the proposed levels will not increase flood risk to other properties.

Oxfordshire LLFA have produced a 'Local Standards and Guidance for Surface Water Drainage on Major Development in Oxfordshire' which outlines the SuDS features and suitability for different scenarios. This standard will be used to inform the drainage design.

For the purpose of considering flood risk and drainage, the Site is classified as a greenfield site; however, the Site is not completely undeveloped and does benefit from some formalised drainage networks. The existing ditches that cross the Site appear to have been constructed as land drainage in the 1980's. Historical mapping from the period shows no surface features on the site, whereas later mapping shows the ditches. See Figure 5-1. Furthermore, there are no inlets into the ditches along their length, except from shallow, small diameter perforated pipes used to drain the fairways of the golf course. Evidence of these land drains can be seen on aerial mapping (see Figure 4-4).



**Figure 5-1: Historic Mapping (circa 1980's)**

Because of this drainage, the discharge profile from the existing site will not behave in the same way as an undeveloped “greenfield” piece of land. The presence of shallow land drains and the ditches will reduce the run-off’s time of concentration. The Proposed Development is to discharge surface water via the existing ditch network at a rate no greater than QBAR, with excess flows being attenuation in on-site storage features. This is therefore seen to reduce the risk of surface water flooding across the Site as it is anticipated the undeveloped site would discharge at a rate higher than QBAR for comparable rainfall events.

The Site is at a low risk of surface water flooding, the Proposed Development is expected to reduce this further and offer flood reduction benefits for properties downstream of the development.

### **5.1.2 Groundwater Flooding**

Initial non-intrusive site surveys have indicated that areas of the Site are at an elevated risk of groundwater flooding. The south east of the Site is at the greatest risk, with the UAV survey indicating groundwater levels to be as close as 300mm to the surface.

The Site’s groundwater levels are managed using land drainage in this area. The Site maintenance staff have constructed two 300-1000mm deep ditches across the east of the Site (running from north to south). Shallow, small diameter perforated pipework has then been laid across the Site, in all



directions, discharging into the ditches. These ditches flow south and meet in an inspection chamber before being culverted.

The Proposed Development proposes the removal of this existing land drainage system. Surface water to the south of the Site will instead be managed by the proposed below ground surface water system, with a new land drainage system to be installed. The location of this is to be similar to the existing system, albeit installed at a lower level to offer better protection to the highway sub-bases in the proposed car park. This can be seen in **Appendix G**. The proposed levels in the south east section of the Site are also proposed to be raised by up to 500mm, this will offer protection to both the groundwater and the car park construction.

The existing ditches are not connected to any of the ponds in the northern part of the Site and no evidence of flows through them were observed during the site walk over. Whilst further intrusive testing is required, it is understood that these ponds are groundwater fed and therefore will have some hydraulic connection to the existing ditches.

To ensure that these ponds are unaffected by the development, it is proposed to install a swale to the north of the car park, with an invert level equal to that of the existing ditches. This will replicate the existing arrangement and maintain groundwater levels in the area. Further to this, two swales are proposed to run from north to south across the car park, these are installed as diversions to the existing ditched on the Site, and will act as an exceedance flow path, mimicking the existing arrangement. These are shown in **Appendix F**.

The Proposed Development therefore is seen to reduce the groundwater flood risk to the south east of the Site but leave it unchanged to the north. The north of the Site is to remain undeveloped and therefore any groundwater flooding is seen to have a low impact and pose no risk to property or person. The adjacent M40 is served by two filter drains at the edge of each carriageway. The depth or capacity if this is not known, however there is no evidence of groundwater flooding along this section of the M40. The area to the north is also at a lower risk of groundwater flooding than the area to the south of the Site.

It is recommended that a site wide intrusive investigation is carried out alongside long term groundwater monitoring, to ensure that the proposed drainage design does not alter the groundwater levels to the north or increase them to the south.

### 5.1.3 Climate Change

As discussed in Section 4.1.4, all designs will be based on an allowance of 40% increase in rainfall intensity for future climate change.

## 5.2 Artificial Systems

### 5.2.1 Adopted Drainage

The proposed surface water network does not discharge to an adoptable surface water sewer, neither is there any in the vicinity. The risk of flooding from adoptable sewers is therefore seen as negligible.

The proposed foul water system is to be discharged via a gravity network to a private pumping station at the south east corner of the Site. The foul water is then to be pumped via rising main to the nearest Thames Water foul sewer, approximately 500m away from the Site. Initial discussions with Thames Water have concluded that there is a capacity issue with this sewer and that the network will require fortifying. The correspondence with Thames Water can be seen in **Appendix H**. As the Site has not yet achieved planning, Thames Water will not begin the modelling process. This will be initiated following the planning process. Any emergency storage requirements associated with the pumping station will be agreed with building control at a later design stage. It is also proposed to offer back up power and pump supply to the pump stations in the event of failure.

As there are no public sewers on the Site, the risk of flooding from the Thames Water network is negligible. There is a heightened risk downstream in the foul network due to the aforementioned capacity issues, however Thames Water have confirmed they will mitigate this post planning.

### 5.2.2 Private Drainage

The only private drainage on the Site is the previously discussed land drainage and ditch network. As this has been discussed in Section 5.1.2, it will not be discussed further here.

Downstream of the Site, the flood risk to the private systems will be reduced as the maximum discharge rate flowing from the proposed site will be reduced to QBAR.

### 5.2.3 Highway Drainage

The A4095 runs along the eastern boundary of the Site and is positively drained using gullies. Sewer information was requested from Cherwell District Council, however the provided plans only highlighted gully locations. There have been no reported instances of flooding along this road and the surface water flood risk is shown as very low on the Environment Agency's online mapping. As the highway level is higher than the Site, there is no risk of flooding to the highway by the Site.

### 5.2.4 Development Drainage

It will be necessary to provide a suitably designed storm water drainage system to collect, convey and attenuate the additional runoff generated by the development of this Site. The Site is proposed to discharge at QBAR, with a rate of 31.3l/s. The calculations for this are shown in Figure 5-2.




Figure 5-2: QBAR Calculations

The excess surface water is to be attenuated in storage features across the Site. This is further discussed in the Below Ground Drainage Strategy (068353-CUR-00-XX-RP-C-0002).

This strategy should also include measures to improve run-off quality whilst maximising biodiversity and amenity to provide a sustainable drainage system as noted in PPG.

Foul flows from the development should be drained through an entirely separate system designed to adoptable standards to minimise the risk of foul flooding occurring as a result of the development.

The proposed drainage strategy is seen to reduce the flood risk to the Site and to properties downstream.

### 5.3 Summary

The pre and post development flood risks are summarised in Table 5-1. As outlined in this report, the proposed development is not expected to increase any form of flood risk to the Site, or up or downstream of it. The Site's surface water will be managed using flow controls and above and below ground storage features.

**Table 5-1 - Flood Risk Summary**

Potential Source of Flooding	Is there a flood risk to the existing site?	Is the flood risk increased or decreased by the development?	Does the proposed development increase or decrease the flood risk downstream?
Fluvial Flooding	No	No Change	Decreased
Pluvial Flooding	No	Decreased	Decreased
Groundwater Flooding	Yes	Decreased	No Change
Adopted Drainage	No	No Change	No Change
Private Drainage	No	Decreased	Decreased
Highway Drainage	No	No Change	No Change
Reservoir Flooding	No	No Change	No Change
Development Drainage	No	Decreased	N/A

---

## 6.0 Sequential Test

As the development site is shown to be wholly within Flood Zone 1 and outside the influence of any other local flood risk elements, in accordance with Table 3 of the PPG, it is concluded that the development is suitable for this location and the Sequential Test is deemed to have been passed.

## 7.0 Conclusions and Recommendations

### 7.1 Overview

This Flood Risk Assessment has been prepared for the proposed development located on the land to the east of the M40 and west of the A4095, near Chesterton. The FRA has been prepared in accordance with the requirements of the NPPF.

- The Site is located in Flood Zone 1 and is therefore at the lowest risk of fluvial flooding
- The Environment Agency's online mapping shows the Site to be at the lowest risk of surface water flooding.
- There is a very low risk of reservoir flooding to the Site.
- The Site is at an elevated risk of groundwater flooding to the south east. This is managed using a network of ditches and shallow, small diameter perforated land drains. Evidence given by site staff and from historic mapping suggest these drains were installed in the 1980's.
- Other than the above, there is no private drainage on the proposed site.
- The Bicester Hotel, Golf and Spa is served by a separate foul and surface water sewer. The surface water is discharged to the outfall ditch network shown in Figure 3-5, there is no evidence of any restrictions or attenuation on the Site. The foul network is discharged into two pump chambers and pumped via rising main to the Thames Water sewer near Chesterton.
- There are no adopted sewers on the Site, the closest being a Thames Water foul sewer, approximately 500m away.
- The proposed drainage strategy is seen to offer a reduction in flood risk to all sources. It has been designed to ensure no flooding during a 1 in 100 year event +40% allowance for climate change.
- The proposed below ground drainage strategy will restrict discharge rates to QBAR and store excess surface water in above and below ground storage structures.
- The proposed network will utilise storage basins, permeable pavements and swales.
- The groundwater to the south east of the Site is proposed to be managed using a network of land drains installed beneath the proposed car parks sub-base as well as through the diversion of the two drainage ditches through the site. Groundwater levels are to be maintained in the north.

---

## Appendices


### Contents

Appendix A – Topographical Survey .....	27
Appendix B – Proposed Site Layout.....	28
Appendix C – Thames Water Sewer Records.....	29
Appendix D – UAV Non-Intrusive Groundwater Survey .....	30
Appendix E – Inferred Groundwater Levels From Pond Levels .....	31
Appendix F – Proposed Below Ground Drainage Strategy .....	32
Appendix G – Proposed Land Drainage Strategy .....	33
Appendix H – Thames Water Foul Discharge Correspondence .....	34

---

## Appendix A – Topographical Survey





**Topographic Abbreviations**

AV	Air Vent	IL	Invert Level
BB	Bottle Beacon	JB	Junction Box
BD	Back Drop	KD	Kerb Outlet
BK	Block	LB	Letter Box
BL	Basin/Bed Level	LP	Lamp Post
BS	Boulder	MH	Man Hole
BP	Block Pillar	MK	Service Marker
BPF	Block Face	MT	Mercury Telephone Cover
BR	Block Rack	OSM	Ordnance Survey Benchmark
BS	Blue Sign	P	Post
BT	BT Inspection Cover	PB	Post Box
C	Combined (Sewer)	PCP	Pollution Control Point
CAV	Car & Van	PLT	Planar
CA	Camera	PM	Parking Meter
CAB	Cable Junction Box	PFL	Parapet Level
CAV	Cable Inspection Cover	PJ	Pump
CB	Control Box	RL	Road Level
CC	Control Cabinet	RL	Road Level
CD	Cable Duct	RS	Road Sign
CCV	Close Circuit Television	RW	Rising Wall
CG	Cable Grid	RWC	Rain Water Channel
CH	Cable Hole	RWP	Rain Water Pipe
CI	Cable Inspection Point	SD	30mm (Sewer)
CL	Cover Level	SO	Soakaway
CO	Column	SB	Siding Barrier
CP	Chain Pit	SS	Water Stop Cook
D	Depth	SD	Service Duct
DK	Drop Kiosk	SE	Sign Post
OPC	Damp Proof Course	SL	Sign Level
EB	Electricity Control Box	SP	Sign Post
EJ	Electricity Junction Box	ST	Sty Cable
EL	Eave Level	SV	Stop Valve
ELIC	Electricity Inspection Cover	SVP	Soil Vent Pipe
EM	Electric Meter	SW	Stop Wall
EP	Electricity Pylon/Pole	TB	Telephone Call Box
ER	Earth Rod	TSM	Temporary Bench Mark
F	Foul (Sewer)	TC	Traffic Control Inspection Cover
FB	Foul Bed	TH	Thresh
FC	Fuel Cover	TL	Threshold Level
PH	Fire Hydrant	TI	Telephone Inspection Cover
FL	Floor Level	TJ	Telephone Junction Box
FL	Floor Light	TL	Tree
FO	Fibre Optic	TMC	Tarmac
FF	Footpath	TOW	Tree
FRL	Fur Roof Level	TP	Telephone Pole
G	Gully	UTL	Unstable To Lift
GAS	Gas Inspection Cover	VP	Vent Pipe
GB	Gas Junction Box	WL	Water Level
GM	Gas Meter	WM	Water Meter
GP	Gas Post	WD	Wash Out
DV	Gas Vent	WF	Wash Face
H	Head Level	WTR	Water Inspection Cover
IC	Inspection Cover		

**Topographic Legend**

Gate	Vegetative Border
Rising	Pin Kerd
Bottom Of Batter	Overhead Power Line
Top Of Batter	Building Canopy
Building/Wall	Grass Edge
Drp/Vegetative Line	Control With Level
Subsoilstone	Edge of Handstanding
Slope of batter	Stone Hole
Kerb	Tree
Pipes	Bush
Fence/Line	Survey Station
	Photograph Origin

**Utility Abbreviations**

AR	ADDITIONAL RINGS	NR	NON-RECORD
BIC	DEPTH OF COVER	NR	NON-RECORD
D10	DEPTH TO DRIVE	NR	NON-RECORD
D15	DEPTH TO S/L	NR	NON-RECORD
D20	DEPTH TO S/S	NR	NON-RECORD
D25	DEPTH TO S/S	NR	NON-RECORD
D30	DEPTH TO S/S	NR	NON-RECORD
D35	DEPTH TO S/S	NR	NON-RECORD
D40	DEPTH TO S/S	NR	NON-RECORD
D45	DEPTH TO S/S	NR	NON-RECORD
D50	DEPTH TO S/S	NR	NON-RECORD
D55	DEPTH TO S/S	NR	NON-RECORD
D60	DEPTH TO S/S	NR	NON-RECORD
D65	DEPTH TO S/S	NR	NON-RECORD
D70	DEPTH TO S/S	NR	NON-RECORD
D75	DEPTH TO S/S	NR	NON-RECORD
D80	DEPTH TO S/S	NR	NON-RECORD
D85	DEPTH TO S/S	NR	NON-RECORD
D90	DEPTH TO S/S	NR	NON-RECORD
D95	DEPTH TO S/S	NR	NON-RECORD
D100	DEPTH TO S/S	NR	NON-RECORD

**Utility Legend**

FUEL LINE - PETROL	CHamber Extents
FUEL LINE - DIESEL, KERO OR PARAFFIN	Report Photos
ELECTRICITY CABLE	
HIGH VOLTAGE ELECTRICITY CABLE	
WATER SUPPLY PIPE	
TELECOM CABLE	
CABLE TELEVISION	
FARE OPTICS	
CATHODIC PROTECTION	
HEATING PIPES	
SURFACE WATER DRAIN	
FUUL WATER DRAIN	
COMBINED DRAIN	
UNIDENTIFIED (LOCATED USING GPR) - SEE NOTES	
UNIDENTIFIED (LOCATED BY INDUCTION) - SEE NOTES	
UNIDENTIFIED (LOCATED BY RADIO) - SEE NOTES	
TANK GAUGE LINE OR COMM CABLE	
OFF-SITE FILL	
VENT PIPE	
DE PIPE	
REMEDICATION PIPES	
VAPOR RECOVERY	
SURVEY EXTENTS BOUNDARY LINE	
END OF FRACESSOR	

**Notes**

THE ACCURACY OF BOTH THE RADIO DETECTION EQUIPMENT AND THE GROUND PENETRATING RADAR, CAN ONLY BE ASSUMED TO BE +/-15% OF THE LOCATED DEPTH FOR BOTH X AND Y-AXIS INFORMATION. WHILST 1ST HORIZON PROVIDE SUITABLY TRAINED STAFF ON ALL PROJECTS AND OUR INVESTMENT IN THE LATEST DETECTION EQUIPMENT, LOCATED DATA MUST NOT BE ASSUMED EXHAUSTIVE AND DOCUMENT HEIGHT MUST ALWAYS BE ADHERED TO IN ALL AREAS DURING ANY EXCAVATION WORKS.

NO LIABILITY FOR ERRORS, OMISSIONS OR EXCEPTIONS WILL BE ACCEPTED BY 1ST HORIZON SURVEYING & ENGINEERING LTD.

ALL SURVEY WORKS ARE CARRIED OUT IN ACCORDANCE WITH THE RICS SURVEYS OF LAND, BUILDINGS AND UTILITY SURVEYS AT SCALES OF 1:500 AND LARGER, OF WHICH A COPY CAN BE MADE AVAILABLE ON REQUEST.

THIS DRAWING SHOULD ONLY BE USED FOR ITS ORIGINAL PURPOSE. 1ST HORIZON SURVEYING & ENGINEERING LTD ACCEPTS NO RESPONSIBILITY FOR THIS DRAWING IF SUPPLIED TO ANY PARTY OTHER THAN THE ORIGINAL CLIENT.

DO NOT SCALE FROM THIS DRAWING.

ALL LEVELS ARE RELATED OSM15 GRID PROJECTION.

Rev	Details	Name	Date

Client:	<b>Curtins</b> 17-19 Whitworth St West Manchester M1 5WG
Project:	<b>Great Wolf Lodge,</b> Cherston, Bicester, OX26 1TH
Title:	<b>Great Wolf Lodge</b> Topographic Survey Overall Layout
Surveyed:	RD, RL, DF
Drawn:	ABR
Checked:	ABR
Date:	02.08.19
CAD:	ABR, RD
Appr:	JG
Scale:	1:100@A0




No. CS-GW5389-01

---

## Appendix B – Proposed Site Layout




Keyplan



Notes:  
 1. Do not scale  
 2. Contractor to Check all dimensions and report omissions and errors to the Architect  
 3. EPR Architects accepts no liability for use of this drawing by parties other than the party for whom it was prepared or for purposes other than those for which it was prepared.  
 4. This drawing is issued in dwg/print format as an uncontrolled version to enable the recipient to prepare their own documents/drawings/models for which they are solely responsible. This drawing is based on project information current at the time of issue. EPR Architects Limited accepts no liability for any alterations or additions to or discrepancies arising out of any change to such project information that occurs to the information after it is issued by EPR Architects Limited.  
 5. This drawing does not contain shared coordinates and is not issued for coordination purposes.

No.	Revision	Date	Initial	Chk'd
3	P03 - Planning Issue	08.11.19	LOG	AJ
2	P02 - Preliminary Planning Issue	26.10.19	LOG	AJ
1	P01 - Preliminary Planning Issue	25.10.19	LOG	CT

Notes:  
 1. This drawing has been prepared for planning application purposes only.  
 2. EPR Architects accepts no liability for use of this drawing by parties other than the party for whom it was prepared or for purposes other than those for which it was prepared.  
 3. Landscape shown for illustrative purposes only, refer to Landscape Architect's for Landscape proposals for further details.  
 4. Tree locations & existing trees beyond site perimeter - indicative - for illustrative purposes only.



**EPR Architects**  
 30 Millbank, London SW1P 4DU  
 +44(0)20 7327800  
 www.epr.co.uk

Proposed Great Wolf Lodge  
 Chesterton, Bicester, Oxfordshire

Proposed Site Plan


Scale	Status	Revision
1:1250	Planning	3

Project Code: 10875 - EPR - 00 - ZZ - DR - A - TP-0102

C:\Renov\10875\EPR\ZZ\DR\A\0102\TP\0102.dwg, User: G:\Users\G\Documents\G\10875.dwg, 11/08/2019 11:30:12

---

## Appendix C – Thames Water Sewer Records




The width of the displayed area is 500m and the centre of the map is located at OS coordinates 455750,221750  
 The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.

NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available

Manhole Reference	Manhole Cover Level	Manhole Invert Level
9652	77.34	75.7
8651	77.99	76.64
861M	n/a	n/a
861L	n/a	n/a
9651	77.25	75.8
861N	n/a	n/a
7601	78.74	77.54
861K	n/a	n/a
7602	78.11	75.86
8654	77.49	76.06
9601	76.41	74.46
9602	76.44	74.56
8653	77.58	76.29
7603	77.63	75.56
871A	n/a	n/a
871B	n/a	n/a
871D	n/a	n/a
871C	n/a	n/a
871E	n/a	n/a
8701	76.71	75.26
8702	76.46	74.91
8703	76.56	75.09
871F	n/a	n/a
871G	n/a	n/a
8801	76.69	75.32
881B	n/a	n/a
881A	n/a	n/a
9552	76.3	75.23
9551	76.43	75.44
951A	n/a	n/a
9603	75.96	74.14
9553	76.54	75.13
9503	76.52	74.79
8555	77.65	75.69
8503	77.64	75.79
8556	77.63	75.64
9502	76.9	74.96
8554	77.86	75.92
8502	77.88	75.95
9554	76.93	75.26
9501	77.08	75.18
951E	n/a	n/a
8557	77.27	75.35
8504	77.24	75.44
8553	77.75	76.1
8552	77.97	76.35
8501	77.74	76.14
951C	n/a	n/a
951D	n/a	n/a
951B	n/a	n/a
8505	77.53	75.18
8558	77.49	75.57
8551	77.96	76.14
8603	77.93	76.49
8602	78.04	76.61
8601	78.06	76.65
8652	77.94	76.45
8604	77.29	74.92

The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.





The width of the displayed area is 500m and the centre of the map is located at OS coordinates 455750,221250  
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.  
Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.

NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available

Manhole Reference	Manhole Cover Level	Manhole Invert Level
9302	74.68	72.96
941E	n/a	n/a
9404	76.12	74.35
9453	76.1	74.54
9201	74.52	72.94
9251	74.49	73.18
9351	74.54	73.2
9352	74.52	73.09
9303	74.43	72.76
9304	74.5	73.05
941A	n/a	n/a
931A	n/a	n/a
9353	74.41	72.93
9305	74.69	73.52
9301	74.78	73.47
9202	74.28	72.7
941G	n/a	n/a
941F	n/a	n/a
9451	75.35	74.2
0451	75.15	73.59
9452	75.85	73.67
9403	75.85	74.08
9405	76.27	74.55
9402	76.05	74.78
9454	76.33	75
9401	76.13	75.33
9101	n/a	n/a
9102	n/a	n/a
8201	n/a	n/a
8202	75.24	73.81
9254	74.78	73
8203	75.07	73.7
9255	74.78	73.11
8205	75.09	74.1
9204	74.35	72.47
8204	74.78	73.2
8206	74.79	73.63
9252	74.27	72.77
9203	74.28	72.54
811C	n/a	n/a
811B	n/a	n/a
811A	n/a	n/a

The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.





The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified before any works are undertaken. Crown copyright Reserved



















**Scale:** 1:7158  
**Width:** 2000m  
**Printed By:** SAsirvat  
**Print Date:** 15/04/2019  
**Map Centre:** 455522,221600  
**Grid Reference:** SP5521NE

**Comments:**








# ALS Sewer Map Key

## Public Sewer Types (Operated & Maintained by Thames Water)

-  **Foul:** A sewer designed to convey waste water from domestic and industrial sources to a treatment works.
-  **Surface Water:** A sewer designed to convey surface water (e.g. rain water from roofs, yards and car parks) to rivers or watercourses.
-  **Combined:** A sewer designed to convey both waste water and surface water from domestic and industrial sources to a treatment works.
-  **Trunk Surface Water**
-  **Trunk Foul**
-  **Storm Relief**
-  **Trunk Combined**
-  **Vent Pipe**
-  **Bio-solids (Sludge)**
-  **Proposed Thames Surface Water Sewer**
-  **Proposed Thames Water Foul Sewer**
-  **Gallery**
-  **Foul Rising Main**
-  **Surface Water Rising Main**
-  **Combined Rising Main**
-  **Sludge Rising Main**
-  **Proposed Thames Water Rising Main**
-  **Vacuum**





## Sewer Fittings

A feature in a sewer that does not affect the flow in the pipe. Example: a vent is a fitting as the function of a vent is to release excess gas.

-  Air Valve
-  Dam Chase
-  Fitting
-  Meter
-  Vent Column




## Operational Controls

A feature in a sewer that changes or diverts the flow in the sewer. Example: A hydrobrake limits the flow passing downstream.

-  Control Valve
-  Drop Pipe
-  Ancillary
-  Weir





## End Items

End symbols appear at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol, Outfall on a surface water sewer indicates that the pipe discharges into a stream or river.

-  Outfall
-  Undefined End
-  Inlet






## Other Symbols

Symbols used on maps which do not fall under other general categories








-  Public/Private Pumping Station
-  Change of characteristic indicator (C.O.C.I.)
-  Invert Level
-  Summit

### Areas

Lines denoting areas of underground surveys, etc.


-  Agreement
-  Operational Site
-  Chamber
-  Tunnel
-  Conduit Bridge

## Other Sewer Types (Not Operated or Maintained by Thames Water)

-  Foul Sewer
-  Surface Water Sewer
-  Combined Sewer
-  Gully
-  Culverted Watercourse
-  Proposed
-  Abandoned Sewer


### Notes:

- 1) All levels associated with the plans are to Ordnance Datum Newlyn.
- 2) All measurements on the plans are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate direction of flow.
- 4) Most private pipes are not shown on our plans, as in the past, this information has not been recorded.
- 5) 'na' or '0' on a manhole level indicates that data is unavailable.
- 6) The text appearing alongside a sewer line indicates the internal diameter of the pipe in millimetres. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. If you are unsure about any text or symbology present on the plan, please contact a member of Property Insight on 0845 070 9148.




The width of the displayed area is 500m and the centre of the map is located at OS coordinates 455750,221750  
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.



The width of the displayed area is 500m and the centre of the map is located at OS coordinates 455750,221250  
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.



0 45 90 180 270 360  
Meters

The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified before any works are undertaken. Crown copyright Reserved








**Scale:** 1:7158  
**Width:** 2000m  
**Printed By:** SAsirvat  
**Print Date:** 15/04/2019  
**Map Centre:** 455522,221600  
**Grid Reference:** SP5521NE

**Comments:**







# ALS Water Map Key

## Water Pipes (Operated & Maintained by Thames Water)


- 
**Distribution Main:** The most common pipe shown on water maps. With few exceptions, domestic connections are only made to distribution mains.
- 
**Trunk Main:** A main carrying water from a source of supply to a treatment plant or reservoir, or from one treatment plant or reservoir to another. Also a main transferring water in bulk to smaller water mains used for supplying individual customers.
- 
**Supply Main:** A supply main indicates that the water main is used as a supply for a single property or group of properties.
- 
**Fire Main:** Where a pipe is used as a fire supply, the word FIRE will be displayed along the pipe.
- 
**Metered Pipe:** A metered main indicates that the pipe in question supplies water for a single property or group of properties and that quantity of water passing through the pipe is metered even though there may be no meter symbol shown.
- 
**Transmission Tunnel:** A very large diameter water pipe. Most tunnels are buried very deep underground. These pipes are not expected to affect the structural integrity of buildings shown on the map provided.
- 
**Proposed Main:** A main that is still in the planning stages or in the process of being laid. More details of the proposed main and its reference number are generally included near the main.

PIPE DIAMETER	DEPTH BELOW GROUND
Up to 300mm (12")	900mm (3')
300mm - 600mm (12" - 24")	1100mm (3' 8")
600mm and bigger (24" plus)	1200mm (4')

## Valves

-  General Purpose Valve
-  Air Valve
-  Pressure Control Valve
-  Customer Valve

## Hydrants








-  Single Hydrant

## Meters










-  Meter

## End Items

Symbol indicating what happens at the end of a water main.

-  Blank Flange
-  Capped End
-  Emptying Pit
-  Undefined End
-  Manifold
-  Customer Supply
-  Fire Supply



## Operational Sites

-  Booster Station
-  Other
-  Other (Proposed)
-  Pumping Station
-  Service Reservoir
-  Shaft Inspection
-  Treatment Works
-  Unknown
-  Water Tower

## Other Symbols


-  Data Logger

## Other Water Pipes (Not Operated or Maintained by Thames Water)







-  **Other Water Company Main:** Occasionally other water company water pipes may overlap the border of our clean water coverage area. These mains are denoted in purple and in most cases have the owner of the pipe displayed along them.
-  **Private Main:** Indicates that the water main in question is not owned by Thames Water. These mains normally have text associated with them indicating the diameter and owner of the pipe.

---

## Appendix D – UAV Non-Intrusive Groundwater Survey



**LEGEND**

-  Proposed Application site boundary
-  Inferred ground water contours derived from lake levels on 19.03.2019 (mAOD)
-  Lake water level 19.03.2019 (mAOD)
-  BGS borehole - Drawing No. GTWOLF1904-1 and (see Appendix 1)
-  Public right of way
-  Line of cross section

Depth from surface to ground water



**NOTES**

- UAV survey undertaken by GWP Consultants LLP 19th March 2019 to Ordnance Survey grid and datum.
- Survey with spot levels can be provided if requested.
- For cross section see Drawing No. 4.

Version	Revision and compilation notes	Date
A	Draft	18.04.2019

Client  
Curtins

Project  
Great Wolf Lodge Bicester: Desk Study-Geology & Water

Isopachytes of depth from surface to inferred ground water table (March 2019)



Upton House  
Market Street, Charlbury  
Oxfordshire OX7 3PJ  
United Kingdom

tel +44 (0)1468 810374  
fax +44 (0)1468 810093  
e-mail info@gwp.uk.com  
web www.gwp.uk.com

Date 18.04.2019	Drawn RM/EMB	Checked RA	Scale 1:3,000 at A3
Drawing Ref GTWOLF1904	Drawing No 3B	Version A	

Recent excavation apparently being developed for open water swimming.  
NOTE: This feature is outside the extent of survey control and lake water level may not be as accurate as elsewhere on the site



---

## Appendix E – Inferred Groundwater Levels from Pond Levels



**LEGEND**

- Proposed Application site boundary
- 83 Ground surface contours at 1m intervals (mAO)
- 80 Inferred ground water contours derived from lake levels on 19.03.2019 (mAO)
- Lake water level 19.03.2019 (mAO)
- BGS borehole with water strike information for reference (see Appendix 1)
- Public right of way
- Line of cross section



**NOTES**

- UAV survey undertaken by GWP Consultants LLP 19th March 2019 to Ordnance Survey grid and datum.
- Survey with spot levels can be provided if requested.
- For cross section see Drawing No. 4.

Version	Revision and compilation notes	Date
A	Draft	18.04.2019

Client  
Curtins

Project  
Great Wolf Lodge Bicester: Desk Study-Geology & Water

Site topography, lake water levels and inferred groundwater contours in Cornbrash

Upton House  
Market Street, Charlbury  
Oxfordshire OX7 3PJ  
United Kingdom

tel +44 (0)1468 810374  
fax +44 (0)1468 810093  
e-mail info@gwp.uk.com  
web www.gwp.uk.com

Date 18.04.2019	Drawn RM/EMB	Checked RA	Scale 1:3,000 at A3
Drawing Ref GTWOLF1904	Drawing No 3A	Version A	

---

## Appendix F – Proposed Below Ground Drainage Strategy

**GENERAL NOTES:**

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTURAL AND ENGINEERING DRAWINGS AND SPECIFICATIONS. DO NOT SCALE FROM THIS DRAWING. ALL DETAILS AND DIMENSIONS AND LEVELS ARE TO BE CHECKED BY THE CONTRACTOR PRIOR TO COMMENCEMENT OF CONSTRUCTION. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ENGINEER.
- ALL LEVELS IN METERS & DIMENSIONS IN METERS UNLESS NOTED OTHERWISE.
- DESIGN BASED ON TOPOGRAPHICAL & CCTV SURVEY AVAILABLE AT THE TIME OF DESIGN. ALL EXISTING SEWERS, CONNECTIONS, PIPE SIZES AND INVERT LEVELS TO BE CONFIRMED BY CONTRACTOR PRIOR TO COMMENCEMENT OF WORKS TO ENSURE CONNECTIVITY. ANY VARIANCE FROM THE INFORMATION SHOWN SHOULD BE REPORTED TO THE ENGINEER FOR REVIEW.
- ALL PREWORK TO BE COMPLETED IN LINE WITH AVAILABLE CCTV SURVEY.
- WHERE EXISTING DRAINAGE IS BEING USED, ALLOWANCES SHOULD BE MADE TO RELOCATE THIS DRAINAGE IN LINE WITH AVAILABLE CCTV SURVEY INFORMATION.
- WHERE THERE IS NO REQUIREMENT TO KEEP EXISTING DRAINAGE, ALLOWANCES SHOULD BE MADE TO ABANDON THIS IN LINE WITH CURTAINS DRAINAGE SPECIFICATION.
- ALL INTERNAL DRAINAGE POINTS ARE SHOWN INDICATIVELY AND ARE TO BE DESIGNED AND SET OUT BY THE MAIN ENGINEER.
- ANY DRAINAGE RUNS AND THEIR CONNECTIONS DAMAGED THROUGH CONSTRUCTION WORKS SHOULD BE REPLACED TO SUFFICIENT STANDARD. CURTAINS ACCEPT NO RESPONSIBILITY FOR DEFECTS OR INADEQUACIES OF EXISTING DRAINAGE SYSTEMS. ALL LINES OF SITE DRAINAGE DUE TO AN ISSUE WITH THESE NETWORKS ARE OUTSIDE OF OUR REMIT UNLESS SPECIFICALLY INSTRUCTED OTHERWISE.
- THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES.
- EXISTING DITCH DIVERSIONS TO BE 1M WIDE AND 300-500mm IN DEPTH, AS AGREED WITH THE LIA.
- SOIL SURFACE WATER DISCHARGE LIMITED TO QBAR (31.3m) AS AGREED WITH LIA.
- FOUL PUMPING STATION TO BE DESIGNED BY OTHERS AT LATER DESIGN STAGE. PROVISION OF 24-HOUR EMERGENCY STORAGE TO BE AGREED WITH BUILDING CONTROL. AT LATER DESIGN STAGE, SECONDARY POWER SUPPLY AND SECONDARY PUMP TO BE PROVIDED.

**KEY:**

- SURFACE WATER DRAIN
  - SURFACE WATER CHAMBER
  - FOUL WATER DRAIN
  - FOUL WATER CHAMBER
  - EXISTING SURFACE WATER SEWER
  - SURFACE WATER CULVERT
  - BYPASS SEPARATOR
- ORIFICE PLATES:**
- SW12 (OP) - ORIFICE PLATE: Ø100mm; 55; INVERT LEVEL: 81.98m AOD
  - SW16 (OP) - ORIFICE PLATE: Ø100mm; 55; INVERT LEVEL: 81.16m AOD
  - SW22 (OP) - ORIFICE PLATE: Ø100mm; 40; INVERT LEVEL: 80.70m AOD
  - SW31 (OP) - ORIFICE PLATE: Ø100mm; 40; INVERT LEVEL: 81.12m AOD
  - SW32 (OP) - ORIFICE PLATE: Ø100mm; 40; INVERT LEVEL: 80.72m AOD
  - SW34 (OP) - ORIFICE PLATE: Ø100mm; 40; INVERT LEVEL: 79.93m AOD
  - SW36 (OP) - ORIFICE PLATE: Ø100mm; 40; INVERT LEVEL: 79.99m AOD
  - SW38 (OP) - ORIFICE PLATE: Ø100mm; 50; INVERT LEVEL: 80.00m AOD
  - SW41 (OP) - ORIFICE PLATE: Ø100mm; 50; INVERT LEVEL: 79.44m AOD
- HYDROBRAKES:**
- SW42 (HB) - HYDROBRAKE: Q (15) 31.3; Ø100mm; 227; INVERT LEVEL: 78.66m AOD

- BELOW GROUND SURFACE WATER GEO-CELLULAR STORAGE
- BELOW GROUND SURFACE WATER ATTENUATION CONCRETE TANK WITH SUPPORT COLUMNS
- ABOVE GROUND SURFACE WATER STORAGE SLOPE: 1:20V
- PERMEABLE SUB-BASE SUB-BASE TO COLLECT AND ATTENUATE FLOWS, SUMMING TO BE CONFIRMED AT THE TAILED DESIGN PHASE.
- (A) - PERMEABLE SUB-BASE: AREA: 930m<sup>2</sup>; DEPTH: 300mm @ 95% VOID RATIO
- (B) - PERMEABLE SUB-BASE: AREA: 4775m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (C) - PERMEABLE SUB-BASE: AREA: 2000m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (D) - PERMEABLE SUB-BASE: AREA: 1480m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (E) - PERMEABLE SUB-BASE: AREA: 520m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (F) - PERMEABLE SUB-BASE: AREA: 630m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (G) - PERMEABLE SUB-BASE: AREA: 3025m<sup>2</sup>; DEPTH: 300mm @ 95% VOID RATIO
- (H) - PERMEABLE SUB-BASE: AREA: 1700m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (I) - PERMEABLE SUB-BASE: AREA: 165m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (J) - PERMEABLE SUB-BASE: AREA: 690m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- (K) - PERMEABLE SUB-BASE: AREA: 940m<sup>2</sup>; DEPTH: 300mm @ 30% VOID RATIO
- PROPOSED SWALE LOCATIONS AND DEPTHS TO BE CONFIRMED. ANTICIPATED DEPTH 300-500mm.
- PLANNING BOUNDARY
- EXISTING SURFACE WATER SEWER
- EXISTING LAND DRAINS TO BE RETAINED
- EXISTING LAND DRAINS TO BE DIVERTED
- PROPOSED DIVERTED LAND DRAIN

Rev	Description	Date	By	Chk'd
P05	UPDATED FOLLOWING COMMENT	11.11.19	LB	MS
P04	FOUL NETWORK ADDED	18.03.19	LB	MS
P03	UPDATED FOLLOWING COMMENTS	04.09.19	LB	MS
P02	FOR INFORMATION	28.08.19	LB	MS
P01	PRELIMINARY ISSUE	02.08.19	NMH	MS



**PRELIMINARY**


Project: **GREAT WOLF LODGE**

Dwg Title: **PROPOSED DRAINAGE STRATEGY**

Size	Date	Drawn By	Designed By	Checked By
A0	02.08.19	NMH	MS	MS

Scale: 1:500

Project No	Originator	Zone	Level	Type	Discipline	Category	Number	Rev
06535	CUR	00	XX	DR	C		92000	P05




---

## Appendix G – Proposed Land Drainage Strategy

**GENERAL NOTES:**

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND SPECIFICATIONS.
2. DO NOT SCALE FROM THIS DRAWING. ALL DETAILS AND DIMENSIONS AND LEVELS ARE TO BE CHECKED BY THE CONTRACTOR PRIOR TO COMMENCEMENT OF CONSTRUCTION. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ENGINEER.
3. ALL LEVELS ARE IN METERS & DIMENSIONS IN METERS UNLESS NOTED OTHERWISE.
4. DESIGN BASED ON TOPOGRAPHICAL & CCTV SURVEY AVAILABLE AT THE TIME OF DESIGN. ALL EXISTING SEWERS, CONNECTIONS, PIPE SIZES AND INVERT LEVELS TO BE CONFIRMED BY CONTRACTOR PRIOR TO COMMENCEMENT OF WORKS TO ENSURE CONNECTIVITY. ANY VARIANCE FROM THE INFORMATION SHOWN SHOULD BE REPORTED TO THE ENGINEER FOR REVIEW.
5. ALL PREWORK TO BE REPORTED TO THE ENGINEER FOR REVIEW.
6. WHERE EXISTING DRAINAGE IS BEING USED, ALLOWANCES SHOULD BE MADE TO RELOCATE THIS DRAINAGE IN LINE WITH AVAILABLE CCTV SURVEY INFORMATION.
7. WHERE THERE IS NO REQUIREMENT TO KEEP EXISTING DRAINAGE, ALLOWANCES SHOULD BE MADE TO ABANDON THIS IN LINE WITH CURTINS DRAINAGE SPECIFICATION.
8. ALL INTERNAL DRAINAGE POINTS ARE SHOWN INDICATIVELY AND ARE TO BE DESIGNED AND SET OUT BY THE M&E ENGINEER.
9. ANY DRAINAGE RUNS AND THEIR CONNECTIONS DAMAGED THROUGH CONSTRUCTION WORKS SHOULD BE REPLACED TO SUFFICIENT STANDARD. CURTINS ACCEPT NO RESPONSIBILITY FOR DEFECTS OR INADEQUACIES OF EXISTING DRAINAGE SYSTEMS. FAILURE OF SITE DRAINAGE DUE TO AN ISSUE WITH THESE NETWORKS ARE OUTSIDE OF OUR REMIT UNLESS SPECIFICALLY INSTRUCTED OTHERWISE.
11. THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES.
12. LATERAL BRANCHES TO MAIN BELOW GROUND LAND DRAINAGE RUNS NOT SHOWN FOR CLARITY. LAND DRAINAGE TO BE INSTALLED IN A HERRINGBONE PATTERN, WITH DRAIN SPACING TO CONFIRMED FOLLOWING COMPLETION OF DETAILED GEOLOGICAL INVESTIGATIONS.

- - - - - EXISTING SURFACE WATER SEWER
- — — — — EXISTING LAND DRAINS TO BE RETAINED
- — — — — EXISTING LAND DRAINS TO BE DIVERTED
- — — — — PROPOSED DIVERTED LAND DRAIN
- — — — — PROPOSED PERFORATED LAND DRAINAGE
- — — — — — PROPOSED LAND DRAINAGE CHAMBER



4.7m

NOTE  
EXISTING LAND DRAINAGE DITCH TO BE DIVERTED. ADDITIONAL PIPED LAND DRAINAGE TO BE INSTALLED BELOW PAVEMENT AND CONNECTED TO OUTFALL DITCH SYSTEM TO BE RESIGNED AT LATER STAGES. FUNCTION AND CATCHMENTS OF EXISTING LAND DRAINAGE TO FOLLOWING INTRUSIVE SITE INVESTIGATIONS.

NOTE  
BELOW GROUND LAND DRAINAGE NETWORK TO DISCHARGE TO EXISTING DRAINAGE DITCH RUNNING ALONG THE SOUTH OF THE SITE.

NOTE  
LAND DRAINAGE NETWORK TO DISCHARGE TO EXISTING BELOW GROUND NETWORK, PRIOR TO BEING DISCHARGED TO THE EXISTING POND TO THE SOUTH OF THE GOLF RESORT HOTEL.

Vicarage Farm

Stableford House

Pond

P02	UPDATED FOLLOWING COMMENTS	11.11.19	MS	TL
P01	PRELIMINARY ISSUE	17.09.19	MS	TL

Rev	Description	Date	By	Chk



PRELIMINARY

Project: GREAT WOLF LODGE

Dwg Title: PROPOSED LAND DRAINAGE GENERAL ARRANGEMENT

Size	Date	Drawn By	Designed By	Checked By
A0	17.09.19	MCS	MCS	TL

Scale: 1:500  
 Project No: 06535 - CUR - 00 - XX - DR - C - 92003 - P02

---

## Appendix H – Thames Water Foul Discharge Correspondence

**Mr Michael Smith**

Curtins Consulting  
40 Compton Street  
London  
EC1V 0BD



30 September 2019

## Pre-planning enquiry: Capacity Concerns

**Site: Great Wolf Lodge Resort, Chesterton, Bicester OX26 1TH**

Dear Michael,

Thank you for providing information on your development.

*Proposed site: Hotel (500 rooms), Water Park (8540m<sup>2</sup>), Food court, Conference area and Back of house (12500m<sup>2</sup>).*

*Proposed foul water discharge by pump at 50 l/s into manhole SP55217601.*

*Surface water discharging into watercourse.*

### Foul Water

We've assessed your foul water proposals and concluded from our review, that our sewerage network does not have sufficient capacity to accommodate foul water flows from the proposed development.

In order to ensure we make the appropriate upgrades – or 'off-site reinforcement' – to serve your development, we'll need to carry out modelling work, design a solution and build the necessary improvements. Typical timescales for a development of your size are:

**Modelling: 8 months**

**Design: 6 months**

**Construction: 6 months**

**Total: 20 months**

If the time you're likely to take from planning and construction through to first occupancy is longer than this, we'll be able to carry out the necessary upgrades in time for your development. If it's shorter, please contact me on the number below to discuss the timing of our activities.

### What do you need to tell us before we start modelling?

We're responsible for funding any modelling and reinforcement work. We need, though, to spend our customers' money wisely, so we'll only carry out modelling once we're confident that your development will proceed.



In order to have this confidence, we'll need to know that you **own the land and have either outline or full planning permission**. Please email this information to us as soon as you have it.

If you'd like us to start modelling work ahead of this point, we can do this if you agree to underwrite the cost of modelling and design. That means we'll fund the work – but you agree to pay the cost if you don't achieve first occupancy within five years.

If the modelling shows we need to carry out reinforcement work, then before we start construction, we'll need you to supply us with notification that you've confirmed your 'nominated competent person' (NCP) submission to the Health and Safety Executive.

### What do I need to do next?

The discharge of non-domestic effluent is not permitted until a valid trade effluent consent has been issued by Thames Water. If anything, other than domestic sewage is discharged into the public sewers without the above agreement an offence is committed, and the applicant will be liable to the penalties contained in Section 109(1) (WIA 1991). Please contact Trade Effluent prior to seeking a connection approval, to discuss trade effluent consent and conditions of discharge.

**Please note that you must keep us informed of any changes to your design – for example, an increase in the number or density of homes.**

If you have any further questions, please contact me on 020 3577 9224.

Yours sincerely



Hemlata Gurung  
Technical Coordinator  
Developer Services – Sewer Adoptions Team

# Our Locations

## **Birmingham**

2 The Wharf  
Bridge Street  
Birmingham  
B1 2JS  
T. 0121 643 4694  
birmingham@curtins.com

## **Bristol**

Quayside  
40-58 Hotwell Road  
Bristol  
BS8 4UQ  
T. 0117 302 7560  
bristol@curtins.com

## **Cambridge**

50 Cambridge Place  
Cambridge  
CB2 1NS  
T. 01223 631 799  
cambridge@curtins.com

## **Cardiff**

3 Cwrt-y-Parc  
Earlswood Road  
Cardiff  
CF14 5GH  
T. 029 2068 0900  
cardiff@curtins.com

## **Douglas**

Varley House  
29-31 Duke Street  
Douglas  
Isle of Man  
IM1 2AZ  
T. 01624 624 585  
douglas@curtins.com

## **Dublin**

39 Fitzwilliam Square  
Dublin 2  
Ireland  
T. 00353 1 507 9447  
dublin@curtins.com

## **Edinburgh**

1a Belford Road  
Edinburgh  
EH4 3BL  
T. 0131 225 2175  
edinburgh@curtins.com

## **Glasgow**

Queens House  
29 St Vincent Place  
Glasgow  
G1 2DT  
T. 0141 319 8777  
glasgow@curtins.com

## **Kendal**

28 Lowther Street  
Kendal  
Cumbria  
LA9 4DH  
T. 01539 724 823  
kendal@curtins.com

## **Leeds**

Rose Wharf  
Ground Floor  
Leeds  
LS9 8EE  
T. 0113 274 8509  
leeds@curtins.com

## **Liverpool**

51-55 Tithebarn Street  
Liverpool  
L2 2SB  
T. 0151 726 2000  
liverpool@curtins.com

## **London**

40 Compton Street  
London  
EC1V 0BD  
T. 020 7324 2240  
london@curtins.com

## **Manchester**

Merchant Exchange  
17-19 Whitworth Street West  
Manchester  
M1 5WG  
T. 0161 236 2394  
manchester@curtins.com

## **Nottingham**

56 The Ropewalk  
Nottingham  
NG1 5DW  
T. 0115 941 5551  
nottingham@curtins.com