

The Old Post Office - Door and Window Schedule

Date: 26th July 2019

Area Name	Door/Window	Description	Size (mm)	Supplier	Code	Finish	Notes
Kitchen / Dining Area	GD01	Barn door	To match existing	TBC	NA	Painted Timber, colour TBC.	Refurbished existing barn door on rollers to slide over main entrance doors.
	GD02	Double doors to centre with fixed glazed side panels.	To suit existing opening	TBC	TBC	Crittal, colour RAL TBC.	Double glazed
	GD09	Double doors	To suit new opening approx. 1230w x 1940h (check on site).	TBC	TBC	Crittal, colour RAL TBC.	Double glazed
	GD10	Double doors to centre with fixed glazed side panels.	To suit existing opening	TBC	TBC	Crittal, colour RAL TBC.	Double glazed
	GW07	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Double glazed, conservation roof light, recessed installation for tiled roof
	GW08	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Double glazed, conservation roof light, recessed installation for tiled roof
	GW09	Roof window, solar opening	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Double glazed, conservation roof light, recessed installation for tiled roof. Installed with solar operation kit.
	GW10	Roof window, solar opening	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Double glazed, conservation roof light, recessed installation for tiled roof. Installed with solar operation kit.
	GW11	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Double glazed, conservation roof light, recessed installation for tiled roof
Utility Room	GW06	Left hung and right hung casement windows with fixed central window.	To suit new opening approx. 1500w x 850h (check on site).	TBC	TBC	Painted Timber, timber glazing beads, colour TBC.	Single glazed
TV Room/ Snug	GD04	New french doors	To suit existing opening	TBC	TBC	Painted Timber, timber glazing beads, colour TBC.	Single glazed
En-Suite	FW07	Left hung casement window	To suit new opening approx. 700w x 850h (check on site).	TBC	TBC	Painted Timber, timber glazing beads, colour TBC.	Single glazed
	FW08	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Double glazed, conservation roof light, recessed installation for tiled roof
	FW09	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Double glazed, conservation roof light, recessed installation for tiled roof