

The Old Post Office - Door and Window Schedule

Date: 14.11.19

Rev B

Area Name	Door/ Window	Description	Size (mm)	Supplier	Code	Finish	Notes
Kitchen / Dining Area	GD01	Barn door	To match existing	TBC	NA	Painted Timber, colour TBC.	Refurbished existing barn door on rollers to slide over main entrance doors.
	GD02	Double doors to centre with fixed glazed side panels.	To suit existing opening	TBC	TBC	Crittall, colour RAL TBC.	Slimlite' Double glazed
	GD08	Painted Hardwood door with window 900 x 2000	To suit new opening approx. Check on site.	TBC	TBC	Painted Timber. Colour TBC	Slimlite' Double glazed
	GD09	Painted Hardwood door with window 900 x 2000	To suit new opening approx. Check on site.	TBC	TBC	Painted Timber. Colour TBC	Slimlite' Double glazed
	GD10	Double doors to centre with fixed glazed side panels.	To suit existing opening	TBC	TBC	Crittall, colour RAL TBC.	Slimlite' Double glazed
	GW08	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Slimlite' Double glazed, conservation roof light, recessed installation for tiled roof
	GW09	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Slimlite' Double glazed, conservation roof light, recessed installation for tiled roof
	GW10	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Slimlite' Double glazed, conservation roof light, recessed installation for tiled roof
Utility Room	GW06	Left hung and right hung casement windows with fixed central window.	To suit new opening approx. 1500w x 850h (check on site).	TBC	TBC	Painted Timber, timber glazing beads, colour TBC.	Single glazed
TV Room/ Snug	GW07	Left hung and right hung casement windows with fixed central window.	To suit existing opening with lowered cill, approx. 1315w x 1300h (check on site).	TBC	TBC	Painted Timber, timber glazing beads, colour TBC.	Single glazed
En-Suite	FW07	Left hung casement window	To suit new opening approx. 700w x 850h (check on site).	TBC	TBC	Painted Timber, timber glazing beads, colour TBC.	Single glazed
	FW08	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Slimlite' Double glazed, conservation roof light, recessed installation for tiled roof
	FW09	Roof window, manual operation	CK04 (550w x 980h)	Velux	GGL SD5J2	Black external profile and glazing bar in RAL 9005	Slimlite' Double glazed, conservation roof light, recessed installation for tiled roof