

UB11 Vepac Slate Vent



Product features and benefits

- In-line design
- Soil/Vent and mechanical extract adaptor available

Application

- High or low level roof void ventilation
- Mechanical extraction when used with the Vepac Connector and Lower pipe
- Minimum pitch of 25°

Material

- UV Stabilised High Impact Polystyrene

Dimensions

- 380mm x 285mm suitable for 500mm x 250mm and 600mm x 300mm slates (UB11)
- 382mm x 398mm suitable for 600mm x 300mm slates only (Vepac)

Weight

- UB11 0.5kg per unit
- UB11 3.0kg per box
- Vepac 0.62kg per unit
- Vepac 3.72kg per box

Packaging

- 6 per box - UB11
- 8 per box - Vepac

Performance

- Provides 10,750 mm² free vent area



Colours

- Anthracite

Product Code

- UB11— 294620
- Vepac Slate Vent— 100000294660

NB: To convert to a terminal please add the Vepac Connector & Lower Pipe 100140294605

| Spacing | 5mm | 10mm | 25mm |
|-----------|------|-------|-------|
| M Centres | 2.15 | 1.075 | 0.430 |