



- GENERAL NOTES**
1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
  2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
  3. This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
  4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
  5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
  6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
  7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
  8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

**LEGEND**

Soft Landscape

- Existing Tree and Hedges to be Retained**  
Trees to be retained and protected in line with BS5837:2012.
- Existing Trees to be Removed**
- Proposed Trees in POS**  
Extra Heavy Standard / Semi-mature, 18-20 / 20-25cm girth, 4.5-6m high to be planted with a double timber stake secured with a rubber tree tie.
- Proposed Feature Trees**  
Standard Semi-mature, 20-25cm girth, 4.5-6.25m high to be planted with a single timber stake secured with a rubber tree tie.
- Proposed Ornamental Trees in Front Gardens and Back Gardens**  
Heavy Standard, 12-14cm girth, 3.5- 4.25m high to be planted with a single timber stake secured with a rubber tree tie.
- Ornamental Shrub Planting**  
Proposed shrubs and flowering herbaceous plants to be planted as 10L pots at 2-3 per sq.m. planted with feature specimen, 10-12L pots.
- Native Buffer Planting**  
To be native shrub species planted at 60-90cm height, bare root stock at 4 per sq. m.

- Proposed Ornamental Hedge**  
Proposed ornamental hedge to be planted as 100-120cm height, 10L pots, at 3 per lin.m to provide an instant impact.
- Proposed Low Ornamental Hedge**  
Proposed ornamental hedge to be planted as 40-60cm height, 10L pots, at 3 per lin.m to provide an instant impact. To be planted with topiary specimens at key focal points, 15-20L pots
- Proposed Native Hedge**  
Proposed native hedge to be planted as a double staggered row, 100-125cm height, bare root stock at 300mm centre
- Proposed Wildflower Meadow**  
RE1 Traditional Hay Meadow (MGS Grassland) Sown at 5g
- Proposed Grass - Gardens**
- Proposed Grass - POS**

Hard Landscape

- Proposed Closeboarded Fence**  
To architects details
  - Proposed Post & Rail Fence, 1.2m high**  
To architects details
  - Proposed Block Paving**  
To architects details
  - Proposed Permeable Block Paving**  
To architects details
  - Proposed Black Macadam**  
To architects details
  - Proposed Flag Paving**  
To architects details
  - Proposed Compacted Gravel**  
For footpath within POS.
  - Proposed Gravel**
- For hard materials and boundary treatments please refer to architects drawings for details.

**REVISION NOTES**

Rev	By	Description	Date
A	SH	Updated in line with comments	17.12.2019

Client  
**Rectory Homes**

Project  
**Steeple Aston**

Description  
**Landscape Layout**

Status  
**For Approval**

Scale @ A1  
**1:250**

Drawn  
**GBS**

Checked  
**CT**

Date  
**10.12.19**

Job number  
**3461**

Drawing number  
**101**

Revision  
**A**