

# Mercia Antique



**Ibstock**  
At the heart of building



## Product Information

Ibstock Code:	2919
Type:	Wirecut
Facing Description:	Rolled
Dry Brick Weight (kg):	2.3kg
Pack Quantity:	500
Packaging (standard):	Banded (plastic) & Shrinkwrapped
Factory:	Chesterton

## Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T2 R1
Configuration:	Vertically Perforated
Voids (%):	29-34
Compressive Strength (N/mm <sup>2</sup> ):	60
Active Soluble Salts:	S2
Water Absorption (% weight):	7
Durability:	F2~
Gross Dry Density (Sound Insulation) (Kg/m <sup>3</sup> ):	1640
Equivalent Thermal Conductivity "K" value 5% Exposed:	Refer to Ibstock
Initial Rate of Absorption (Suction Rate) (Kg/m <sup>2</sup> /min):	Refer to Ibstock
EAN:	5036335196816