

Buyers are warned that this is a working drawing and the contents of this drawing may be subject to change at any time and alterations and variations can occur during the progress of the build process. As such the layout, form, content and dimensions of the finished construction may differ materially from those shown. Whilst we make every effort to ensure our drawings are up to date there may from time to time be an unavoidable delay in updating these due to changes in regulations and/or re-planning. Purchasers are advised to check with the Sales Adviser whether any alterations have been made to this drawing. The contents of this drawing do not constitute a contract, part of any contract or warranty.

Existing Allotments

3m Wide Track consisting of 300mm Type 1 with dust layer laid on terram

Passing bay in front of parking spaces

Turning Area

Passing bay in front of parking spaces

Passing bays and turning area in reinforced grass (Bodpave 45 or similar)

Visibility Splays:
2.4 x 112.1m Eastbound
2.4 x 106.4m Westbound &
2.4 x 62.1m to Tangent Westbound

Proposed Allotments - refer to Application ref 20/00814/OBL

Existing hedges removed/trimmed back and replaced with new hedge planting behind visibility splays & grass verge in front

WYKHAM LANE

Rev	Description	Date	Drawn	Chk'd
-----	-------------	------	-------	-------



DAVID WILSON HOMES
WHERE QUALITY LIVES

Remus 2 | 2 Cranbrook Way | Solihull Business Park | Solihull | B90 4GT | 0121 713 7310
www.dwh.co.uk

Project

New Allotments

Wykham Lane
Bodicote

Drawing Title

Proposed Improvements to Existing Access Track

Scale

1:500 @ A2

Date

16/01/23

Drawn By

DG

Drawing Ref

7942-ALL-01

Revision

-