


THE FINEST TIMBER WINDOWS & DOORS

Order confirmation : 1908073

(Please Note: Images viewed from outside. Arrow denotes hinge position)

Item	Quantity	Description	Per Item	Total
18	4 No.	GARDEN STUDIO Product: Conservation Casement Size: 800 mm x 1125 mm Weight: 36 kg Frame Timber: Laminated Larch / Engineered Hardwood Sash Timber: Laminated Larch Finish: 3 Coat Dual Colour Fr Out: BS4800 16 C 33 DUCK EGG BLUE Sa Out: BS4800 16 C 33 DUCK EGG BLUE Fr Ins: RAL 9003 Signal White Sa Ins: RAL 9003 Signal White Frame Width: Head 68 Cill 68 Left 68 Right 68 Sash Width: SNo Top Bottom Left Right 1 64 69 64 64 Frame Profile: Ovolo Sash Profile: Ovolo Sash Bar: 22mm Ovolo Applied Glazing Bars Sash: Conservation Casement Openings: Top Swing (RH Handle) Hardware: Lock - Standard Espag Hinges - T/Swing Ferritic - Standard Handle - Bulb Type Locking - Antique Brass T/vent - 4600 White + White Grille -- FSC Material Used -- Attachments: 40 x 32mm Head Drip 34 x 85mm Cill Extender + Window Board Groove Glass Specification: 1.1 4mm Clear Toughened / 16mm Argon / 4mm Clear Toughened Soft Coat Low-E PLUS Black WarmEdge Spacer (Std)		



GLAZED WITH BLACK GLAZING TAPE



FM624029 EM5624030

Registered Number 00698976. VAT Registered Number 927 5580 94
 Part of Performance Timber Products Group Ltd.

Mumford & Wood Ltd, Tower Business Park,
 Kelvedon Road, Tiptree, Essex. CO5 0LX

T: +44(0)1621 818155 F: +44(0)1621 818175


www.mumfordwood.com

THE FINEST TIMBER WINDOWS & DOORS

Order confirmation : 1908073

(Please Note: Images viewed from outside. Arrow denotes hinge position)

Item	Quantity	Description	Per Item	Total
22	1 No.	<p>GARDEN STUDIO</p> <p>Product: Conservation Casement Size: 900 mm x 875 mm Weight: 33 kg Frame Timber: Laminated Larch / Engineered Hardwood Sash Timber: Laminated Larch Finish: 3 Coat Dual Colour Fr Out: BS4800 16 C 33 DUCK EGG BLUE Sa Out: BS4800 16 C 33 DUCK EGG BLUE Fr Ins: RAL 9003 Signal White Sa Ins: RAL 9003 Signal White Frame Width: Head 68 Cill 68 Left 68 Right 68 Sash Width: SNo Top Bottom Left Right 1 64 69 64 64</p> <p>Frame Profile: Ovolo Sash Profile: Ovolo Sash Bar: 22mm Ovolo Applied Glazing Bars Sash: Conservation Casement Openings: Top Swing (RH Handle) Hardware: Lock - Standard Espag Hinges - T/Swing Ferritic - Standard Handle - Bulb Type Locking - Antique Brass T/vent - 4600 White + White Grille -- FSC Material Used -- Top Swing Size is suitable for Fire Escape.</p> <p>Attachments: 40 x 32mm Head Drip 34 x 85mm Cill Extender + Window Board Groove</p> <p>Glass Specification: 1.1 4mm Clear Toughened / 16mm Argon / 4mm Clear Toughened Soft Coat Low-E PLUS Black WarmEdge Spacer (Std)</p>		



GLAZED WITH BLACK GLAZING TAPE



FM624029 EMS624030

Registered Number 00698976. VAT Registered Number 927 5580 94
 Part of Performance Timber Products Group Ltd.

Mumford & Wood Ltd, Tower Business Park,
 Kelvedon Road, Tiptree, Essex. CO5 0LX

T: +44(0)1621 818155 F: +44(0)1621 818175

www.mumfordwood.com