



Hedge Specification

Mix of indigenous Bare Rooted 40/60cm Seedlings planted at 30cm spacings;

- Crataegus monogyna 50%
- Rosa canina 10%
- Acer campestre 15%
- Viburnum opulus 10%
- Carpinus betulus 15%

All planting shall be carried out in accordance with BS 4428:1989 Code of Practice for general landscape operations.

Please note all grass has been planted and established for 7 years.

Charlie Luxton Design
 Beanacre Cottage, Ropeway, Hook Norton, Oxon, OX15 5QB
 info@charlieluxton.com
 01608 730086

Do not scale off this drawing. This drawing is to be read with all other contract documents. Any discrepancies are to be reported to the Architect. At construction status, this drawing remains design intent only. All information to be checked by contractor for site accuracy and fit. Drawings are subject to statutory approvals and site surveys.

P1	200813	Planning issue
P2	200824	Condition Discharge

project
 Heath Barn
 Sibford Gower
 Banbury
 OX15 5HQ

drwg no	213_03_320	rev	P2
title Proposed Landscape Plan			
scale 1:1250 @ A4			