

Hydrock The Poplars, Land South of Clifton Road, Deddington Drainage and Flood Risk Assessment

For Blue Cedar Homes

 Date:
 26 November 2020

 Doc ref:
 10690-HYD-XX-XX-RP-D-5001

TECHNICAL DESIGN NOTE



Project name	The Poplars, Land South of Clifton Road, Deddington
Design note title	Drainage and Flood Risk Assessment
Document reference	10690-HYD-XX-XX-RP-D-5001
Author	Rob Belcher BEng GMICE
Checked by	Richard Hughes
Revision	P03 - Following client comment
Date	26 November 2020

CONTENTS

1.	Introduction	3
2.	Site Information	4
2.1	Location and Setting	.4
2.2	Topography	.4
2.3	Proposed Development	.4
3.	Drainage Strategy	5
3.1	Existing Drainage	.5
3.2	Proposed	.5
4.	Conclusion	7



1. INTRODUCTION

This Technical Note has been prepared by Hydrock on behalf of Blue Cedar Homes in support of a Planning Application to be submitted to Cherwell District Council for a proposed development at the The Poplars, Land South of Clifton Road, Deddington.

The following drainage report identifies the existing situation, development proposals and how surface and foul water is proposed to be dealt with as part of the development. As the development is less than 1 ha and within Flood Zone 1, a site specific flood risk assessment is not considered to be necessary.

TECHNICAL DESIGN NOTE



Project name	The Poplars, Land South of Clifton Road, Deddington
Design note title	Drainage and Flood Risk Assessment
Document reference	10690-HYD-XX-XX-RP-D-5001
Author	Rob Belcher BEng GMICE
Checked by	Richard Hughes
Revision	P03 - Following client comment
Date	26 November 2020

CONTENTS

1.	Introduction	3
2.	Site Information	4
2.1	Location and Setting	.4
2.2	Topography	.4
2.3	Proposed Development	.4
3.	Drainage Strategy	5
3.1	Existing Drainage	.5
3.2	Proposed	.5
4.	Conclusion	7



2. SITE INFORMATION

2.1 Location and Setting

The existing 0.46ha site is located at The Poplars, Land South of Clifton Road, Deddington. OX15 0TH at a National Grid Reference of SP 47123 31742.

The site is currently comprised of entirely greenfield land. Directly north lies Clifton Road, to the east and south lies a continuation of greenfield with a few dwellings further east. A site with a recent consent for up to 15 dwellings is also located to the east of the site. Directly west of the development is a small pocket of approximately 7 residential dwellings.

A site location plan is included in Appendix A.

2.2 Topography

The site falls in a constant southerly direction from Clifton Road from a level of approximately 124.5mAOD to 123.5mAOD along the southern border.

A Topographical Survey of the site is included in Appendix A.

2.3 Proposed Development

The proposal includes the erection of 7 residential dwellings with associated areas of hardstanding and landscaping. The highway between plots 1 and 6 within the site is proposed to remain private, however is to be designed to adoptable standards. Drainage within this highway will also be constructed to an adoptable standard.

The proposed layout plans are included in Appendix B.



3. DRAINAGE STRATEGY

3.1 Existing

3.1.1 Surface water

Due to the undeveloped nature of the existing site, the lack of information recorded on the topographic survey and Thames Water records (Appendix A) identifying no assets within the development boundary it is assumed that the site is not currently served by a formal drainage network. It is therefore assumed that rainwater infiltrates the ground until the saturation point is met at which point surface water flows overland following the natural topography.

Following a desktop study, highway ditches are shown to be present along both sides of Clifton Road. Consultation with Cherwell District Council have identified that a culvert crosses Clifton Street to the west of the development site (Appendix B).

3.1.2 Foul water

Due to the undeveloped nature of the development it is assumed that no foul network is currently present on site. Thames Water records have been obtained (Appendix A) and indicate a public foul water sewer within Clifton Road located north of the development. The closest manhole to the development access is MH0702 and is shown to have an invert level of 122.18mAOD.

3.2 Proposed

3.2.1 Surface Water

The options for managing surface water have been reviewed in accordance with the following hierarchy, as discussed in Building Regulations Part H and Paragraph 080 of NPPG:

- 1. Infiltration to the ground using a soakaway or other suitable Sustainable Drainage System (SuDS).
- 2. If this is not feasible, discharge to a watercourse at a restricted rate, unless it does not affect flood risk e.g. if to the sea or an estuary.
- 3. Discharge at a restricted rate to a surface water sewer or drain.
- 4. Discharge at a restricted rate to a combined sewer system –only considered if the above have all been investigated and it has been proved that none of these options are suitable. The approval for this can only be given by the Water Authority.

Infiltration testing has been completed on site (Appendix A) and found that infiltration would provide a suitable method of surface water discharge. Hence, it is proposed that the impermeable areas on site drain towards soakaway features.

Results from the onsite testing (Appendix B) concluded an infiltration rate of 1.94x10-4m/s in the location of the proposed development and therefore this value has been used in order to calculate infiltration feature sizes.

The total roof impermeable area is proposed to drain via a new private network towards the permeable paved private drive adjacent to plot 4. The private permeable paving will drain its own area with the remaining additional impermeable areas draining towards an underground geocellular crate located within the private drive. Calculations have shown that the geocellular crate will need to be 5m x 10m x



1m in order to cater for all storms up to and including the 1 in 100yr event + 40% Climate change realised over this time.

The initial section of highway (between plots 1 and 7) is to remain private but constructed to adoptable standards and will drain its own area via permeable paving.

As mentioned before, further investigation is required of the existing ditch network near Clifton Road as if there is a ditch present on the southern edge, a new culvert will be required to allow access to the development site.

The proposed drainage strategy drawing and calculations are included in Appendix B.

3.2.2 Foul Water Strategy

In line with the Design and Construction Guidance, residential flows per dwelling equate to 4000 l/day. This therefore equates to a peak flow of 0.32 l/s.

It is proposed that foul flows connect into the existing Thames Water network located within Clifton Road to the north of the development. Confirmation that this is viable point of connection will need to be verified with Thames Water prior to any works occurring.

Due to a level difference between the existing invert level of the Thames Water foul sewer and the development site, a private package pumping station is proposed to be used to pump flows produced from plots 1, 2, 3, 4 & 5 via private rising main towards a gravity fed system in the highway adjacent to plot 6. The private pumping station would be located south of plot 4. Drainage within the highway adjacent to plot 6 will remain private but be designed and constructed to adoptable standards.



4. CONCLUSION

Although not specifically required due to the size of the development, the entirety of the site is confirmed to be within Flood Zone 1.

On site geotechnical and infiltration assessments has been carried out and identifies that the site is suitable for infiltration-based drainage. Therefore, it is proposed that surface water runoff is discharged either via permeable paving, lined soakaways and underground geocellular crates. Foul flows are proposed to either be drained under gravity or via a pumped solution towards the existing Thames Water foul network located in Clifton Road to the north of the development.

This report therefore demonstrates that the proposed development:

- Is suitable in the location proposed.
- Will not increase flood risk elsewhere as a result of the proposed development through the loss of floodplain storage or impedance of flood flows.
- Will put in place measures to ensure surface and foul water is appropriately managed.

As such, the proposal is concluded to meet the flood risk requirements of the NPPF.



Appendix A – Existing Site

Title
Site Location Plan
Topographical Survey (1)
Topographical Survey (2)
Thames Water Records
Infiltration Test Results

CLIFTON ROAD, DEDDINGTON, OXFORDSHIRE – SITE LOCATION DETAILS



 OS X (Eastings)
 447138

 OS Y (Northings)
 231722

 Nearest Post Code
 OX15 0TH

 Nat Grid
 SP471317 / SP4713831722





Asset location search



Hydrock Consultants Over Court Barns Over Lane BRISTOL BS32 4DF

Search address supplied

Clifton Road, Deddington

Your reference

10690 Clifton Road

Our reference

ALS/ALS Standard/2020_4273933

Search date

9 October 2020

Knowledge of features below the surface is essential for every development

The benefits of this knowledge not only include ensuring due diligence and avoiding risk, but also being able to ascertain the feasibility of any development.

Did you know that Thames Water Property Searches can also provide a variety of utility searches including a more comprehensive view of utility providers' assets (across up to 35-45 different providers), as well as more focused searches relating to specific major utility companies such as National Grid (gas and electric).

Contact us to find out more.



Thames Water Utilities Ltd Property Searches, PO Box 3189, Slough SL1 4WW DX 151280 Slough 13



searches@thameswater.co.uk www.thameswater-propertysearches.co.uk



0845 070 9148





Search address supplied: Clifton Road, Deddington,

Dear Sir / Madam

An Asset Location Search is recommended when undertaking a site development. It is essential to obtain information on the size and location of clean water and sewerage assets to safeguard against expensive damage and allow cost-effective service design.

The following records were searched in compiling this report: - the map of public sewers & the map of waterworks. Thames Water Utilities Ltd (TWUL) holds all of these.

This searchprovides maps showing the position, size of Thames Water assets close to the proposed development and also manhole cover and invert levels, where available.

Please note that none of the charges made for this report relate to the provision of Ordnance Survey mapping information. The replies contained in this letter are given following inspection of the public service records available to this company. No responsibility can be accepted for any error or omission in the replies.

You should be aware that the information contained on these plans is current only on the day that the plans are issued. The plans should only be used for the duration of the work that is being carried out at the present time. Under no circumstances should this data be copied or transmitted to parties other than those for whom the current work is being carried out.

Thames Water do update these service plans on a regular basis and failure to observe the above conditions could lead to damage arising to new or diverted services at a later date.

Contact Us

If you have any further queries regarding this enquiry please feel free to contact a member of the team on 0845 070 9148, or use the address below:

Thames Water Utilities Ltd Property Searches PO Box 3189 Slough SL1 4WW

Email: <u>searches@thameswater.co.uk</u> Web: <u>www.thameswater-propertysearches.co.uk</u>

Asset location search



Waste Water Services

Please provide a copy extract from the public sewer map.

Enclosed is a map showing the approximate lines of our sewers. Our plans do not show sewer connections from individual properties or any sewers not owned by Thames Water unless specifically annotated otherwise. Records such as "private" pipework are in some cases available from the Building Control Department of the relevant Local Authority.

Where the Local Authority does not hold such plans it might be advisable to consult the property deeds for the site or contact neighbouring landowners.

This report relates only to sewerage apparatus of Thames Water Utilities Ltd, it does not disclose details of cables and or communications equipment that may be running through or around such apparatus.

The sewer level information contained in this response represents all of the level data available in our existing records. Should you require any further Information, please refer to the relevant section within the 'Further Contacts' page found later in this document.

For your guidance:

- The Company is not generally responsible for rivers, watercourses, ponds, culverts or highway drains. If any of these are shown on the copy extract they are shown for information only.
- Any private sewers or lateral drains which are indicated on the extract of the public sewer map as being subject to an agreement under Section 104 of the Water Industry Act 1991 are not an 'as constructed' record. It is recommended these details be checked with the developer.

Clean Water Services

Please provide a copy extract from the public water main map.

Enclosed is a map showing the approximate positions of our water mains and associated apparatus. Please note that records are not kept of the positions of individual domestic supplies.

For your information, there will be a pressure of at least 10m head at the outside stop valve. If you would like to know the static pressure, please contact our Customer Centre on 0800 316 9800. The Customer Centre can also arrange for a full flow and pressure test to be carried out for a fee.

<u>Thames Water Utilities Ltd</u>, Property Searches, PO Box 3189, Slough SL1 4WW, DX 151280 Slough 13 T 0845 070 9148 E <u>searches@thameswater.co.uk</u> I <u>www.thameswater-propertysearches.co.uk</u>





For your guidance:

- Assets other than vested water mains may be shown on the plan, for information only.
- If an extract of the public water main record is enclosed, this will show known public water mains in the vicinity of the property. It should be possible to estimate the likely length and route of any private water supply pipe connecting the property to the public water network.

Payment for this Search

A charge will be added to your suppliers account.





Further contacts:

Waste Water queries

Should you require verification of the invert levels of public sewers, by site measurement, you will need to approach the relevant Thames Water Area Network Office for permission to lift the appropriate covers. This permission will usually involve you completing a TWOSA form. For further information please contact our Customer Centre on Tel: 0845 920 0800. Alternatively, a survey can be arranged, for a fee, through our Customer Centre on the above number.

If you have any questions regarding sewer connections, budget estimates, diversions, building over issues or any other questions regarding operational issues please direct them to our service desk. Which can be contacted by writing to:

Developer Services (Waste Water) Thames Water Clearwater Court Vastern Road Reading RG1 8DB

Tel: 0800 009 3921 Email: developer.services@thameswater.co.uk

Clean Water queries

Should you require any advice concerning clean water operational issues or clean water connections, please contact:

Developer Services (Clean Water) Thames Water Clearwater Court Vastern Road Reading RG1 8DB

Tel: 0800 009 3921 Email: developer.services@thameswater.co.uk



Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved

Thames Water Utilities Ltd, Property Searches, PO Box 3189, Slough SL1 4W, DX 151280 Slough 13 T 0845 070 9148 E searches@thameswater.co.uk I www.thameswater-propertysearches.co.uk NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available

Manhole Reference	Manhole Cover Level	Manhole Invert Level						
081D	n/a	n/a						
071A	n/a	n/a						
081A	n/a	n/a						
081B	n/a	n/a						
0702	124.85	122.16						
181C	n/a	n/a						
181B	n/a	n/a						
181A	n/a	n/a						
2701	n/a	n/a						
8501	121.52	117.9						
9601	122.88	119.08						
9602	123.01	120.21						
0701	124.57	121.08						
081C	n/a	n/a						
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.								





The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified before any works are undertaken. Crown copyright Reserved

Scale:	1:7158	Comments
Width:	2000m	
Printed By:	G1KANAGA	
Print Date:	12/10/2020	
Map Centre:	447109,231743	
Grid Reference:	SP4731NW	

ALS Sewer Map Key



Sewer Fittings

A feature in a sewer that does not affect the flow in the pipe. Example: a vent is a fitting as the function of a vent is to release excess gas.

- Air Valve Dam Chase Fitting
- ≥ Meter

Π

0 Vent Column

Operational Controls

A feature in a sewer that changes or diverts the flow in the sewer. Example: A hydrobrake limits the flow passing downstream.

X Control Valve Ф Drop Pipe Ξ Ancillary Weir

End Items

End symbols appear at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol, Outfall on a surface water sewer indicates that the pipe discharges into a stream or river.

- いし Outfall
- Undefined End Inlet

Other Symbols

Symbols used on maps which do not fall under other general categories

- ****/ Public/Private Pumping Station
- * Change of characteristic indicator (C.O.C.I.)
- Ø Invert Level
- < Summit

Areas

Lines denoting areas of underground surveys, etc.

Agreement **Operational Site** :::::: Chamber Tunnel Conduit Bridge

Other Sewer Types (Not Operated or Maintained by Thames Water)



Notes:

hames

Water

- 1) All levels associated with the plans are to Ordnance Datum Newlyn.
- 2) All measurements on the plans are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate direction of flow.
- 4) Most private pipes are not shown on our plans, as in the past, this information has not been recorded.
- 5) 'na' or '0' on a manhole level indicates that data is unavailable.
- 6) The text appearing alongside a sewer line indicates the internal diameter of the pipe in milimetres. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. If you are unsure about any text or symbology present on the plan, please contact a member of Property Insight on 0845 070 9148.

Thames Water Utilities Ltd, Property Searches, PO Box 3189, Slough SL1 4W, DX 151280 Slough 13 T 0845 070 9148 E searches@thameswater.co.uk I www.thameswater-propertysearches.co.uk



Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.





The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified before any works are undertaken. Crown copyright Reserved

Scale:	1:7158	Comments:
Width:	2000m	
Printed By:	G1KANAGA	
Print Date:	12/10/2020	
Map Centre:	447109,231743	
Grid Reference:	SP4731NW	

ALS Water Map Key

Water Pipes (Operated & Maintained by Thames Water)

- Distribution Main: The most common pipe shown on water maps.
 With few exceptions, domestic connections are only made to distribution mains.
- Trunk Main: A main carrying water from a source of supply to a treatment plant or reservoir, or from one treatment plant or reservoir to another. Also a main transferring water in bulk to smaller water mains used for supplying individual customers.
- **Supply Main:** A supply main indicates that the water main is used as a supply for a single property or group of properties.
- STREE
 Fire Main: Where a pipe is used as a fire supply, the word FIRE will be displayed along the pipe.
- **Metered Pipe:** A metered main indicates that the pipe in question supplies water for a single property or group of properties and that quantity of water passing through the pipe is metered even though there may be no meter symbol shown.
- Transmission Tunnel: A very large diameter water pipe. Most tunnels are buried very deep underground. These pipes are not expected to affect the structural integrity of buildings shown on the map provided.
- **Proposed Main:** A main that is still in the planning stages or in the process of being laid. More details of the proposed main and its reference number are generally included near the main.

PIPE DIAMETER	DEPTH BELOW GROUND			
Up to 300mm (12")	900mm (3')			
300mm - 600mm (12" - 24")	1100mm (3' 8")			
600mm and bigger (24" plus)	1200mm (4')			

Thames Water Utilities Ltd, Property Searches, PO Box 3189, Slough SL1 4W, DX 151280 Slough 13 T 0845 070 9148 E searches@thameswater.co.uk I www.thameswater-propertysearches.co.uk



Operational Sites



Other Symbols

Data Logger

Other Water Pipes (Not Operated or Maintained by Thames Water)

Other Water Company Main: Occasionally other water company water pipes may overlap the border of our clean water coverage area. These mains are denoted in purple and in most cases have the owner of the pipe displayed along them.

Private Main: Indiates that the water main in question is not owned by Thames Water. These mains normally have text associated with them indicating the diameter and owner of the pipe.

Terms and Conditions

All sales are made in accordance with Thames Water Utilities Limited (TWUL) standard terms and conditions unless previously agreed in writing.

- 1. All goods remain in the property of Thames Water Utilities Ltd until full payment is received.
- 2. Provision of service will be in accordance with all legal requirements and published TWUL policies.
- 3. All invoices are strictly due for payment 14 days from due date of the invoice. Any other terms must be accepted/agreed in writing prior to provision of goods or service, or will be held to be invalid.
- 4. Thames Water does not accept post-dated cheques-any cheques received will be processed for payment on date of receipt.
- 5. In case of dispute TWUL's terms and conditions shall apply.
- 6. Penalty interest may be invoked by TWUL in the event of unjustifiable payment delay. Interest charges will be in line with UK Statute Law 'The Late Payment of Commercial Debts (Interest) Act 1998'.
- 7. Interest will be charged in line with current Court Interest Charges, if legal action is taken.
- 8. A charge may be made at the discretion of the company for increased administration costs.

A copy of Thames Water's standard terms and conditions are available from the Commercial Billing Team (cashoperations@thameswater.co.uk).

We publish several Codes of Practice including a guaranteed standards scheme. You can obtain copies of these leaflets by calling us on 0800 316 9800

If you are unhappy with our service you can speak to your original goods or customer service provider. If you are not satisfied with the response, your complaint will be reviewed by the Customer Services Director. You can write to her at: Thames Water Utilities Ltd. PO Box 492, Swindon, SN38 8TU.

If the Goods or Services covered by this invoice falls under the regulation of the 1991 Water Industry Act, and you remain dissatisfied you can refer your complaint to Consumer Council for Water on 0121 345 1000 or write to them at Consumer Council for Water, 1st Floor, Victoria Square House, Victoria Square, Birmingham, B2 4AJ.

Credit Card	BACS Payment	Telephone Banking	Cheque
Call 0845 070 9148 quoting your invoice number starting CBA or ADS / OSS	Account number 90478703 Sort code 60-00-01 A remittance advice must be sent to: Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW. or email ps.billing@thameswater. co.uk	By calling your bank and quoting: Account number 90478703 Sort code 60-00-01 and your invoice number	Made payable to ' Thames Water Utilities Ltd' Write your Thames Water account number on the back. Send to: Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW or by DX to 151280 Slough 13

Ways to pay your bill

Thames Water Utilities Ltd Registered in England & Wales No. 2366661 Registered Office Clearwater Court, Vastern Rd, Reading, Berks, RG1 8DB.



Telephone: +44 (0)117 947 1006

20th December 2018 314228 L01 (00) The Old School Stillhouse Lane Bedminster Bristol BS3 4EB UK

www.rsk.co.uk

Blue Cedar Homes Limited 220 Park Avenue Aztec West Almondsbury Bristol BS32 4SY

FACTUAL INFILTRATION TESTING REPORT, LAND SOUTH OF CASTLE STREET, DEDDINGTON

For the Attention of Jon Symons,

This letter presents the results of infiltration testing undertaken for the Land South of Castle Street, Deddington. RSK's service constraints are presented within **Appendix A**.

1. SITE DESCRIPTION AND SETTING

The site is situated on the eastern edge of Deddington, Oxfordshire and set within a mixed agricultural and residential setting. The site is accessed via a shared entrance from Castle Street in the north west corner. The site comprises a single large grassed field, with a large mature trees and shrubs along the northern and southern boundaries, occasional mature trees also lie along the eastern boundary. **Figure 1** shows the site location.

The residential village of Deddington is located to the west of the site, including a primary school offsite to the north-west. Agricultural fields are located south beyond the ruin of Deddington Castle, residential housing is to the east and north.

The northern two thirds of the site is generally level, with the southern third sloping gently downwards towards the south.

Based on a review of the British Geological Society (BGS) records for the site, the site is believed to be underlain by bedrock deposits of the Marlstone Rock Formation.

2. PROPOSED DEVELOPMENT

It is understood that the site is proposed to be developed for residential end use. A proposed layout plan has not been provided to RSK.

3. SITE INVESTIGATION METHODOLOGY

RSK carried out intrusive investigation work on 4th December 2018, to determine existing ground conditions and conduct trial pit soakaways. The works were undertaken to provide an indication of the likely infiltration rates at the site.





3.1 Methodology

A non-targeted investigation was undertaken for the site to provide general information for soakaway placement. A total of 3 No. trial pits were undertaken following the Client's requested methodology and given the area of the site.

The 3 No. trial pits were excavated (TP1 - TP3) using mechanical excavation techniques. The locations and depths of the soakaway test pits were chosen by RSK, in order to provide a general spread across the site.

3.2 Investigation Locations

The investigation and the soil descriptions were carried out in general accordance with BS5930: 2015 - Code of Practice for Ground Investigations. A photographic log of the investigation works is presented as **Appendix B** and the exploratory hole logs and other site work records are presented in **Appendix C**.

The locations of the intrusive investigations are shown in Figure 2.

3.3 Soil Sampling

No laboratory testing was required by the client, as such, no soil samples were taken during the investigation.

4. SITE GEOLOGY

A summary of ground conditions encountered during the intrusive works is outlined in the following sections. Generally, the site was underlain by Topsoil over bedrock deposits of the Marlstone Rock Formation. No Made Ground was encountered during the investigation.

The exploratory logs are summarised in **Table 1** and reported in detail in **Appendix C**. Exploratory hole locations are shown on the site plan in **Figure 2**.

Stratum Exploratory holes encountered		Depth to top of stratum m bgl	Proven thickness (m)	
Topsoil		Ground level	0.30	
Marlstone Rock Formation	TP1 - TP3	0.30	>0.75 - >1.30	

Table 1: Geology at the site based on published data.

4.1.1 Topsoil

The Topsoil generally comprised a cohesive soil comprising a brown slightly sandy slightly gravelly silty CLAY. Gravel is subangular to subrounded, fine to coarse of limestone and quartzite. The base of the Topsoil was encountered at 0.30 m bgl in all locations.

4.1.2 Marlstone Rock Formation

This stratum was encountered from beneath the Topsoil in all locations and comprised a orangish brown slightly sandy slightly gravelly silty CLAY to depths of between 0.90 - 1.40 m bgl. The gravel is subangular to subrounded, fine to coarse of ironstone, limestone and quartzite. This layer was further underlain by a strong brownish grey LIMESTONE recovered as gravels and cobbles.



4.1.3 Groundwater

No groundwater was encountered during the intrusive investigation

4.1.4 Visual/olfactory evidence of soil contamination

No visual or olfactory evidence of soil contamination was encountered during the intrusive investigation.

5. INFILTRATION TESTING

Trial pit soakaway tests were carried out at each location, the results of which are summarised in **Table 2**. The test certificates are presented within **Appendix D**.

Table 2: Trial pit infiltration rates

Trial Pit	Test base depth (m bgl)			Length of test (minutes)			Infiltration rate (m/s)		
	1	2	3	1	2	3	1	2	3
TP1	1.05	1.05	-	26	32	-	7.89x10 ⁻⁵	6.46x10⁻⁵	-
TP2	1.58	1.57	-	16	16	-	1.19x10 ⁻⁴	1.26x10 ⁻⁴	-
TP3	1.46	1.46	1.42	9	11	12	2.36x10 ⁻⁴	2.11x10 ⁻⁴	1.91x10 ^{-₄}
11.5	1.40	1.40	1.42		11	12	2.00/10	2.11/10	1.312

Notes: m bgl - metres below ground level

N/A - Infiltration rate could not be calculated as the required intercepts were not met.

* Infiltration was calculated via extrapolation, therefore, should be used as indicative only.

BOLD - Infiltration rate should be adopted in the area of this trial pit.

6. CONCLUSION

6.1 Soakaway design

Finished heights and final layout of the development is not known however, in general terms groundwater levels would need to be at least 1m below any infiltration feature. Infiltration rates less than 1.0×10^{-6} are considered not to be sufficient to offer an infiltration based solution, Infiltration rates may be sufficient however further drainage design works would be required to determine if this offers a suitable solution.

Yours sincerely
For RSK Environment Limited

Andy Denton

Sophie Penney

Geo-environmental Consultant

Principal Consultant



Enc.

Figure 1 - Site location plan Figure 2 - Exploratory hole location plan

Appendix A - RSK service constraints

Appendix B - Photographic log

Appendix C - Exploratory logs

Appendix D - Infiltration testing certificates



Figures





	IF	GENI	ר										
			Site Bo	undary									
-			Trial Pi	t Locatior	ו								
=													
-													
1													
1	1	l	I			1	I						
	Rev.	Date		Amendm	ent	Drawn	Chkd.	Appd.					
1													
4													
		1: H	8 Frogmore emel Hem	e Road	Tel: +44 (0) ⁻ Fax: +44 (0) ⁻	1442 43750 1442 43755	0 50						
1		H H U	ertfordshir P3 9RT nited King	e E \ dom	Email: info@rsk Neb: www.rsk	.co.uk .co.uk							
1	Client		0										
1	E	BLUE	CEI	DAR H	OMES	S LIM	ITE	D					
+													
1	Projec	ct Title											
1	~						~ T /	~~					
	C	AST	_E S	IKEE	I, DEE	BIN) ا د						
	Drawi	ng Title											
0		E	XPL	ORAT	ORY H	HOLE	=						
1			LO	CATIC	ON PLA	٩N							
	Drawr	n Date		Checked [Date	Approved	Date						
	ASC Scale	21.1	2.18	AD 2 Orig Size	1.12.18	KF	21.1	2.18					
1	1:1	000		A3		m							
L.	Project 314	^{st No.} 4228 -	R02 ((00)	Drawing File 314228 (F	R02-00)	Fig 2	.dwg					
	Drawi		2				I	Rev. P1					
			_	0	. 1000								
			10	Scale 1) 20	30 4	0 ⁵⁰ 1	m						
		-											



Appendix A – Service constraints

- 1. This report and the site investigation carried out in connection with the report (together the "Services") were compiled and carried out by RSK Environment Limited (RSK) for Blue Cedar Homes Limited (the "client") in accordance with the terms of a contract between RSK and the "client", dated 23 April 2018. The Services were performed by RSK with the skill and care ordinarily exercised by a reasonable environmental consultant at the time the Services were performed. Further, and in particular, the Services were performed by RSK taking into account the limits of the scope of works required by the client, the time scale involved and the resources, including financial and manpower resources, agreed between RSK and the client.
- 2. Other than that expressly contained in paragraph 1 above, RSK provides no other representation or warranty whether express or implied, in relation to the Services.
- 3. Unless otherwise agreed in writing the Services were performed by RSK exclusively for the purposes of the client. RSK is not aware of any interest of or reliance by any party other than the client in or on the Services. Unless expressly provided in writing, RSK does not authorise, consent or condone any party other than the client relying upon the Services. Should this report or any part of this report, or otherwise details of the Services or any part of the Services be made known to any such party, and such party relies thereon that party does so wholly at its own and sole risk and RSK disclaims any liability to such parties. Any such party would be well advised to seek independent advice from a competent environmental consultant and/or lawyer.
- 4. It is RSK's understanding that this report is to be used for the purpose described in the introduction to the report. That purpose was a significant factor in determining the scope and level of the Services. Should the purpose for which the report is used, or the proposed use of the site change, this report may no longer be valid and any further use of or reliance upon the report in those circumstances by the client without RSK 's review and advice shall be at the client's sole and own risk. Should RSK be requested to review the report after the date of this report, RSK shall be entitled to additional payment at the then existing rates or such other terms as agreed between RSK and the client.
- 5. The passage of time may result in changes in site conditions, regulatory or other legal provisions, technology or economic conditions which could render the report inaccurate or unreliable. The information and conclusions contained in this report should not be relied upon in the future without the written advice of RSK. In the absence of such written advice of RSK, reliance on the report in the future shall be at the client's own and sole risk. Should RSK be requested to review the report in the future, RSK shall be entitled to additional payment at the then existing rate or such other terms as may be agreed between RSK and the client.
- 6. The observations and conclusions described in this report are based solely upon the Services which were provided pursuant to the agreement between the client and RSK. RSK has not performed any observations, investigations, studies or testing not specifically set out or required by the contract between the client and RSK. RSK is not liable for the existence of any condition, the discovery of which would require performance of services not otherwise contained in the Services. For the avoidance of doubt, unless otherwise expressly referred to in the introduction to this report, RSK did not seek to evaluate the presence on or off the site of asbestos, electromagnetic fields, lead paint, heavy metals, radon gas or other radioactive or hazardous materials.
- 7. The Services are based upon RSK's observations of existing physical conditions at the Site gained from a walk-over survey of the site together with RSK's interpretation of information including documentation, obtained from third parties and from the client on the history and usage of the site. The Services are also based on information and/or analysis provided by independent testing and information services or laboratories upon which RSK was reasonably entitled to rely. The Services clearly are limited by the accuracy of the information, including documentation, reviewed by RSK and the observations possible at the time of the walk-over survey. Further RSK was not authorised and did not attempt to independently verify the accuracy or completeness of information, documentation or materials received from the client or third parties, including laboratories and information services, during the performance of the Services. RSK is not liable for any inaccurate information or conclusions, the discovery of which inaccuracies required the doing of any act including the gathering of any information which was not reasonably available to RSK and including the doing of any independent investigation of the information provided to RSK save as otherwise provided in the terms of the contract between the client and RSK.
- 8. The intrusive environmental site investigation aspects of the Services is a limited sampling of the site at pre-determined borehole and soil vapour locations based on the operational configuration of the site. The conclusions given in this report are based on information gathered at the specific test locations and can only be extrapolated to an undefined limited area around those locations. The extent of the limited area depends on the soil and groundwater conditions, together with the position of any current structures and underground facilities and natural and other activities on site. In addition chemical analysis was carried out for a limited number of parameters [as stipulated in the contract between the client and RSK] [based on an understanding of the available operational and historical information,] and it should not be inferred that other chemical species are not present.
- 9. Any site drawing(s) provided in this report is (are) not meant to be an accurate base plan, but is (are) used to present the general relative locations of features on, and surrounding, the site. Features (boreholes, trial pits etc) annotated on site plans are not drawn to scale but are centred over the approximate location. Such features should not be used for setting out and should be considered indicative only.



Appendix B – Photographic log

Photo no. 1	Date: 04/12/18	
Description View showin depth of TP limestone gr base.	ng the full 1 with ravel at the	





Photo no. 3	Date: 04/12/18	
Description View showir extent of TP limestone gr base.	n: ng the full 22 with ravel at the	

Photo no.	Date:	
4	04/12/18	
Description	:	Commentation of the Commen
View showir arisings fron	ng the n TP2.	



Photo no. 5	Date: 04/12/18		
Description View showir extent of TP limestone gr base.	ng the full P3 with ravel at the		



Appendix C – Exploratory logs



TRIAL PIT LOG

	Contract:								Client:					Trial Pi	it:	
	Ca	stl	e Stre	et, D	eddi	ngto	n			Blue	Cedar H	Homes Lto	d			TP1
	Contract Ref:				Start:	04.1	2.18	Groun	d Level:		Co-ordinat	tes:		Sheet:		
С	astle Stre	et,	Dedo	lingto	PE nd:	04.1	2.18								1	of 1
	Sampl	es a No	ind In-si	tu Tests	sults	Nater	Backfill				Description	of Strata			Depth (Thick	Material Graphic
	Deptil		турс		Suno	-		Turf	overlvina bra	wn slic	ahtly sandy s	slightly gravell	v siltv CLAY.	Gravel	ness)	
	-							is sul	bangular to s	subroun	nded fine to	coarse of lime	stone and qua	artzite.	(0.30) 0.30	x. x. x. x. x. x. x. x. x. x. x. x. x. x
	-							Oran	gish brown	slightly	sandy sligh	htly gravelly si	ilty CLAY. Gr	avel is	-	× <u>×</u>
	-							quart	quartzite.						- - (0.60)	x- <u></u> x - <u></u> x
															0.90	
	_							Stror cobb	ng brownish les.	grey	LIMESTO	NE recovered	d as gravel	s and	- 1.05	
	-							Trial	pit terminate	d at 1.0	05m depth.				-	
	-														-	
	-														-	
	-														-	
R5	-														-	
35 C	-														-	
3 - 09:	-														-	
07. 2/12/1	_														_	
J - V8 JK. [1]	-														-	
N.GP sk.co.u	-														-	
INGTO www.rs	-														-	
Veb: v	-														-	
009 V																
STRI 947 1	-														_	
ASTLE 0117	-														-	
28 C/ Fax:	-														-	
3142 1006	-														-	
- A4P 17 947	_														-	
LOG - el: 011	-														-	
L PIT EB. T	-														-	
g TRIA BS3 4	_														_	
7 Log ristol,	-														-	
v8_0 ster, B	_														-	
rjVersion: , Bedmin	-														-	
07_001 F use Lane	Plan (Not to Scale)									Ģ	General	Remark	S			
n: v8 Stillhc		← 222 ─ ►														
Versio chool,				-	7											
-B Lib Old S	÷															
07.G 1, The	'	▼ └─────														
tY_V8 ent Ltt																
IBRAR								All di	mensions in	metres	•	Scale:		1:25		
SKEn	Method Used:	ethod Plan				t d:		Hand	toole		Logged By:	222	Checke Bv:	d		
υř		ed: Hand dug Us						1 10110	10015		,	111	-,.			



TRIAL PIT LOG

	Contract:							Client:					Trial Pit	t:		
	Ca	astl	e Stre	eet, D	eddi	ngto	n			Blue	Cedar H	omes Ltd				TP2
	Contract Ref	:			Start:	04.1	2.18	Groun	d Level:		Co-ordinate	es:		Sheet:		
С	astle Stre	et,	Dedo	dingto	PE nd:	04.1	2.18								1	of 1
	Samp	les a	nd In-si	tu Tests	6	ater	kfill				Description	of Strata			Depth (Thick	Material
	Depth	No	Туре	Res	sults	Ň	Bac				Description	JI SII'dla			ness)	Legend
	-							Turf	overlying bro	own slig	ghtly sandy sl	ightly gravelly silt	y CLAY. (Gravel	-	× - ×
	-							is su		Subroui		barse of infleston	e anu qua	rizite.	(0.30)	
	-							Orar	ngish brown	slightly	gravelly slig	htly sandy silty C	CLAY. Gra	vel is	0.30	
	-							suba	angular to su tzite.	Ibround	led fine to co	arse of ironstone	, limeston	e and	-	<u>6</u> xx
	-							.							-	<u> </u>
															- _(1.00)	<u> </u>
	-														-	
	-													-	_	
															-	××
	-							0.5							1.30	
	-							cobb	ng brownish bles and boul	lders.	LIMESTONE	recovered as	clayey gr	aveis,	(0.30)	
	-													-	1.60	
- 0	-							Trial	pit terminate	ed at 1.	60m depth.				-	
C.H	-														-	
- 09:3	-														-	
2/18 -	-													-	-	
12/	-														-	
co.uk.	-														-	
w.rsk.	-														-	
. ww														-	-	
9 We	-														_	
1005	-														-	
1/ 34															_	
I.O.:XE	-														-	
on On	-														-	
4/ 10	-													-	-	
117 9	-													-	-	
l el: 0	-														-	
4EB.															-	
, BS3	-													-	-	
Bristo	-														-	
Ister, I	-														-	
eamir	-														-	
ane, B	LI															
use L	Plan (Not to	Scal	e)							C	General	Remarks				
Stillho			0.00			1. ⊢	lard d	igging	from 1.00m o	depth.						
chool,			_ ()		- 											
DId Sc	222															
I he	Ť,															
nt Ltd,																
onme.								h IIA	imensions in	metres	3	Scale [.]		1:25		
Envir	Method				Plan	t		, ui U			Logged		Checked	3		
, NSK	Used:	Ha	and du	g	Use	d:		Hand	d tools		By:	???	By:			AGS



TRIAL PIT LOG

	Contract:								Client:					Trial Pi	it:	
	C	e Stre	et, D)eddi	ngto	n			Blue	Cedar H	omes Ltd				TP3	
	Contract Re	f:			Start:	04.1	2.18	Groun	d Level:		Co-ordinate	es:		Sheet:		
С	astle Str	eet.	Dedo	dingt	OE nd:	04.1	2.18								1	of 1
	Samp	oles a	ind In-si	tu Test	s	iter	kfil				Description	of Strate			Depth	Material
	Depth	No	Туре	Re	sults	Na	Bac			I	Description	or Strata			ness)	Legend
	-							Turf is su	overlying bro bangular to s	wn slig ubroun	htly gravelly ded fine to c	slightly sandy si coarse of limesto	ilty CLAY.	Gravel artzite.	(0.30)	×.
	Ľ														0.30	
	-							Orar	ngish brown s Ingular to sub tzite	slightly prounde	gravelly slig ed fine to co	htly sandy silty barse of ironston	CLAY. Gra e, limestor	avel is ne and	-	
	-							quai							-	<u> </u>
	-								at 0.70m beco from 0.80m h	oming v ard dig	very gravelly ging.				(1.10)	
	-														-	× × · · ×
	-														1.40	
	-							Stroi cobb	ng brownish bles and bould	grey l ders.		E recovered as	clayey gi	ravels,	1.60	
CR5	-							Ina	pit terminate	dal I.o	om depth.				-	
8 - 09:35	-														-	
- v8_07. 12/12/1	-														-	
N.GPJ . sk.co.uk.															-	
DDINGT(b: www.r	-														-	
EET, DE 1009 We	-														-	
ПLE STF 117 947	-														-	
228 CAS 6 Fax: 0	-														-	
4P 314 947 100	-														-	
. LOG - A el: 0117	-														-	
RIAL PIT 33 4EB. 7	-														-	
7 Log T Bristol, BS	-														-	
ion: v8_0 ninster, E	-														-	
1 PrjVers ane, Bedr	[
/8_07_00	Plan (Not to Scale)									G	Seneral	Remarks				
Version: v chool, Sti																
7.GLB Lib The Old S	222															
RY_V8_0 nent Ltd,																
LIBRA Environr	Method				Plan	t		All d	mensions in	metres	logged	Scale:	Checke	1:25		
GINT RSK E	Used:	Jsed: Hand dug Us						Hand	l tools		By:	???	By:	J		AGS



Appendix D – Infiltration test certificates



STRUCTURAL SOILS LTD

INSITU TESTING REPORT



1774

Report No.	748564R.01(00)				
Date	06-December-2018	Contract Castle St	reet, Deddington		
Client Address	RSK Environment Ltd Spring Lodge 172 Chester Road Helsby Cheshire WA6 0AR				
For the Atter	ntion of Romani S	Salama			
Order receive Testing Start Testing Com	ed ed pleted	03-December-2018 04-December-2018 04-December-2018	Client Reference Client Order No. Instruction Type	None None Written	
Tests markec Laboratory.	l 'Not UKAS Accredited' in	this report are not included	in the UKAS Accredita	tion Schedule for our	
UKAS Accre	edited Tests				
Not UKAS A	Accredited Tests				
3no. Soakaw	ay tests carried out at location	ons specified by client.			
The results re	epresent the ground conditio	ns at the specified location	s and depths at the time	of testing.	
Please Note: F Test were und Opinions and	Remaining samples will be retai ertaken on samples 'as received interpretations expressed in this	ned for a period of one month " unless otherwise stated. s report are outside the scope of	from today and will then b	be disposed of. oratory.	
Structu	ural Soils Ltd 1a Princess Stree	t Bedminster Bristol BS3 4AC	6 Tel.0117 9471000. e-mai	l dimitris.xirouchakis@soils.c	









Appendix B – Proposed Site

Reference	Title
4192-3-110	Proposed Layout
10690-HYD-XX-XX-CA-D-1000	Geocellular Tank Soakaway
10690-HYD-XX-XX-CA-D-1001	Permeable paving
10690-HYD-XX-XX-DR-D-2200	Drainage Strategy Plan



Hydrock Consultants Ltd	Page O	
•	10690 Clifton Rd, Deddington	
	Infiltration Tank	Sec. 1
	1 in 100yr + 40% CC	Mirco
Date 20/10/2020 16:50	Designed by RobBelcher	Desinado
File 10690-HYD-XX-XX-CA-D-1000.SRCX	Checked by	Diginarie
Innovyze	Source Control 2018.1.1	

Half Drain Time : 138 minutes.

	Stor	m	Max	Max	Max	Max	Status
	Even	t	Level	Depth	Infiltration	Volume	
			(m)	(m)	(1/s)	(m³)	
15	min	Summer	98.035	0.535	2.5	25.4	ОК
30	min	Summer	98.171	0.671	2.7	31.9	ΟK
60	min	Summer	98.271	0.771	2.8	36.6	ΟK
120	min	Summer	98.297	0.797	2.8	37.9	ΟK
180	min	Summer	98.277	0.777	2.8	36.9	ΟK
240	min	Summer	98.248	0.748	2.8	35.5	ΟK
360	min	Summer	98.190	0.690	2.7	32.8	ΟK
480	min	Summer	98.137	0.637	2.6	30.3	ΟK
600	min	Summer	98.088	0.588	2.6	27.9	ΟK
720	min	Summer	98.041	0.541	2.5	25.7	ОК
960	min	Summer	97.955	0.455	2.4	21.6	ΟK
1440	min	Summer	97.815	0.315	2.3	15.0	ΟK
2160	min	Summer	97.668	0.168	2.1	8.0	ΟK
2880	min	Summer	97.583	0.083	2.0	3.9	ΟK
4320	min	Summer	97.542	0.042	1.7	2.0	ΟK
5760	min	Summer	97.534	0.034	1.3	1.6	ΟK
7200	min	Summer	97.528	0.028	1.1	1.3	ОК
8640	min	Summer	97.524	0.024	1.0	1.1	ОК
10080	min	Summer	97.521	0.021	0.8	1.0	ОК
15	min	Winter	98.103	0.603	2.6	28.6	ОК
30	min	Winter	98.261	0.761	2.8	36.1	ОК
60	min	Winter	98.382	0.882	2.9	41.9	ОК
120	min	Winter	98.427	0.927	3.0	44.0	ОК
180	min	Winter	98.400	0.900	2.9	42.8	ОК

Storm			Rain	Flooded	Time-Peak
Event			(mm/hr)	Volume	(mins)
				(m³)	
15	min	Summer	139.350	0.0	18
30	min	Summer	91.106	0.0	32
60	min	Summer	56.713	0.0	62
120	min	Summer	34.106	0.0	108
180	min	Summer	24.997	0.0	140
240	min	Summer	19.934	0.0	172
360	min	Summer	14.444	0.0	240
480	min	Summer	11.493	0.0	310
600	min	Summer	9.620	0.0	378
720	min	Summer	8.314	0.0	442
960	min	Summer	6.600	0.0	576
1440	min	Summer	4.760	0.0	822
2160	min	Summer	3.427	0.0	1172
2880	min	Summer	2.712	0.0	1500
4320	min	Summer	1.948	0.0	2200
5760	min	Summer	1.538	0.0	2936
7200	min	Summer	1.281	0.0	3632
8640	min	Summer	1.102	0.0	4336
10080	min	Summer	0.970	0.0	5000
15	min	Winter	139.350	0.0	18
30	min	Winter	91.106	0.0	32
60	min	Winter	56.713	0.0	60
120	min	Winter	34.106	0.0	116
180	min	Winter	24.997	0.0	146

Hydrock Consultants Ltd		Page 1
	10690 Clifton Rd, Deddington	
	Infiltration Tank	The second
	1 in 100yr + 40% CC	Mirco
Date 20/10/2020 16:50	Designed by RobBelcher	Desinado
File 10690-HYD-XX-XX-CA-D-1000.SRCX	Checked by	Diamage
Innovyze	Source Control 2018.1.1	

	Storm Event		Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
240	min W	Vinter	98.365	0.865	2.9	41.1	ОК
360	min W	Vinter	98.284	0.784	2.8	37.2	ΟK
480	min W	Vinter	98.206	0.706	2.7	33.6	ОК
600	min W	Vinter	98.133	0.633	2.6	30.0	ΟK
720	min W	Vinter	98.063	0.563	2.6	26.8	ΟK
960	min W	Vinter	97.940	0.440	2.4	20.9	ΟK
1440	min W	Vinter	97.745	0.245	2.2	11.6	ΟK
2160	min W	Vinter	97.569	0.069	2.0	3.3	ΟK
2880	min W	Vinter	97.543	0.043	1.7	2.0	ΟK
4320	min W	Vinter	97.531	0.031	1.2	1.5	ΟK
5760	min W	Vinter	97.524	0.024	1.0	1.1	ΟK
7200	min W	Vinter	97.520	0.020	0.8	1.0	ΟK
8640	min W	Vinter	97.518	0.018	0.7	0.8	ΟK
10080	min W	Vinter	97.515	0.015	0.6	0.7	O K

	Stor Even	m t	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
240	min	Winter	19.934	0.0	184
360	min	Winter	14.444	0.0	260
480	min	Winter	11.493	0.0	334
600	min	Winter	9.620	0.0	406
720	min	Winter	8.314	0.0	476
960	min	Winter	6.600	0.0	608
1440	min	Winter	4.760	0.0	854
2160	min	Winter	3.427	0.0	1168
2880	min	Winter	2.712	0.0	1464
4320	min	Winter	1.948	0.0	2184
5760	min	Winter	1.538	0.0	2904
7200	min	Winter	1.281	0.0	3632
8640	min	Winter	1.102	0.0	4328
10080	min	Winter	0.970	0.0	5136

Hydrock Consultants Ltd		Page 2
•	10690 Clifton Rd, Deddington	
	Infiltration Tank	Section 1
	1 in 100yr + 40% CC	Mirco
Date 20/10/2020 16:50	Designed by RobBelcher	
File 10690-HYD-XX-XX-CA-D-1000.SRCX	Checked by	Diamaye
Innovyze	Source Control 2018.1.1	
	<u>Rainfall Details</u>	
Painfall Model	ESP Winter Storms Ves	
Return Period (years)	100 Cv (Summer) 0.750	
Region	England and Wales Cv (Winter) 0.840	
M5-60 (mm)	20.000 Shortest Storm (mins) 15	
Summer Storms	Yes Climate Change % +40	
	<u>Time Area Diagram</u>	
	Total Area (ha) 0.105	
	Time (mins) Area	
	From: To: (ha)	
	0 4 0.105	

icro ainag
icro ainag
icro ainag
ainag
allidy
Area (m
80

Hydrock Consultants Ltd					
•	10690 Clifton Road, Deddington				
	Highway Permeable Paving	The second			
	1 in 100yr + 40% CC	Mirco			
Date 20/10/2020 17:03	Designed by RB	Desinado			
File 10690-HYD-XX-XX-CA-	Checked by RJH	Diginada			
Innovyze	Source Control 2018.1.1				

Half Drain Time : 6 minutes.

	Storm Event		Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
		~		0 1 7 0	0.6 5		
15	min	Summer	99.8/3	0.1/3	26.5	9.0	Flood Risk
30	mın	Summer	99.883	0.183	27.9	9.6	Flood Risk
60	mın	Summer	99.859	0.159	24.3	8.1	Flood Risk
120	min	Summer	99.819	0.119	18.2	5.7	Flood Risk
180	min	Summer	99.795	0.095	14.6	4.3	Flood Risk
240	min	Summer	99.780	0.080	12.2	3.3	Flood Risk
360	min	Summer	99.761	0.061	9.3	2.2	Flood Risk
480	min	Summer	99.751	0.051	7.8	1.5	Flood Risk
600	min	Summer	99.746	0.046	6.5	1.3	Flood Risk
720	min	Summer	99.743	0.043	5.7	1.1	Flood Risk
960	min	Summer	99.738	0.038	4.5	0.9	Flood Risk
1440	min	Summer	99.733	0.033	3.3	0.6	Flood Risk
2160	min	Summer	99.728	0.028	2.4	0.5	Flood Risk
2880	min	Summer	99.725	0.025	1.9	0.4	Flood Risk
4320	min	Summer	99.721	0.021	1.3	0.3	Flood Risk
5760	min	Summer	99.719	0.019	1.1	0.2	Flood Risk
7200	min	Summer	99.717	0.017	0.9	0.2	Flood Risk
8640	min	Summer	99.716	0.016	0.8	0.1	Flood Risk
10080	min	Summer	99.715	0.015	0.7	0.1	Flood Risk
15	min	Winter	99.888	0.188	28.7	9.9	Flood Risk
30	min	Winter	99.885	0.185	28.3	9.8	Flood Risk
60	min	Winter	99.848	0.148	22.6	7.5	Flood Risk
120	min	Winter	99.801	0.101	15.5	4.6	Flood Risk
180	min	Winter	99.777	0.077	11.8	3.2	Flood Risk

Storm			Rain	Flooded	Time-Peak
	Even	t	(mm/hr)	Volume	(mins)
				(m³)	
15	min	Summer	139.350	0.0	12
30	min	Summer	91.106	0.0	20
60	min	Summer	56.713	0.0	36
120	min	Summer	34.106	0.0	66
180	min	Summer	24.997	0.0	96
240	min	Summer	19.934	0.0	126
360	min	Summer	14.444	0.0	186
480	min	Summer	11.493	0.0	246
600	min	Summer	9.620	0.0	306
720	min	Summer	8.314	0.0	366
960	min	Summer	6.600	0.0	490
1440	min	Summer	4.760	0.0	720
2160	min	Summer	3.427	0.0	1076
2880	min	Summer	2.712	0.0	1460
4320	min	Summer	1.948	0.0	2164
5760	min	Summer	1.538	0.0	2840
7200	min	Summer	1.281	0.0	3664
8640	min	Summer	1.102	0.0	4272
10080	min	Summer	0.970	0.0	5136
15	min	Winter	139.350	0.0	13
30	min	Winter	91.106	0.0	21
60	min	Winter	56.713	0.0	36
120	min	Winter	34.106	0.0	68
180	min	Winter	24.997	0.0	98

Hydrock Consultants Ltd				
	10690 Clifton Road, Deddington			
	Highway Permeable Paving	The second		
	1 in 100yr + 40% CC	Mirco		
Date 20/10/2020 17:03	Designed by RB	Desinado		
File 10690-HYD-XX-XX-CA-	Checked by RJH	Diamage		
Innovyze	Source Control 2018.1.1			

	Stor Even	m t	Max Level (m)	Max Depth (m)	Max Infiltration (1/s)	Max Volume (m³)	Status
240	min	Winter	99.763	0.063	9.6	2.3	Flood Risk
360	min	Winter	99.748	0.048	7.1	1.4	Flood Risk
480	min	Winter	99.743	0.043	5.7	1.1	Flood Risk
600	min	Winter	99.739	0.039	4.7	0.9	Flood Risk
720	min	Winter	99.737	0.037	4.1	0.8	Flood Risk
960	min	Winter	99.733	0.033	3.3	0.6	Flood Risk
1440	min	Winter	99.728	0.028	2.4	0.5	Flood Risk
2160	min	Winter	99.724	0.024	1.7	0.3	Flood Risk
2880	min	Winter	99.721	0.021	1.3	0.3	Flood Risk
4320	min	Winter	99.718	0.018	1.0	0.2	Flood Risk
5760	min	Winter	99.716	0.016	0.8	0.1	Flood Risk
7200	min	Winter	99.714	0.014	0.6	0.1	Flood Risk
8640	min	Winter	99.713	0.013	0.5	0.1	Flood Risk
10080	min	Winter	99.712	0.012	0.5	0.1	Flood Risk

Storm Event		Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)	
240	min	Winter	19.934	0.0	128
360	min	Winter	14.444	0.0	184
480	min	Winter	11.493	0.0	246
600	min	Winter	9.620	0.0	308
720	min	Winter	8.314	0.0	366
960	min	Winter	6.600	0.0	480
1440	min	Winter	4.760	0.0	712
2160	min	Winter	3.427	0.0	1084
2880	min	Winter	2.712	0.0	1496
4320	min	Winter	1.948	0.0	2200
5760	min	Winter	1.538	0.0	2976
7200	min	Winter	1.281	0.0	3624
8640	min	Winter	1.102	0.0	4344
10080	min	Winter	0.970	0.0	5144

Hydrock Consultants Ltd		Page 2		
•	10690 Clifton Road, Deddington			
	Highway Permeable Paving	The second		
	1 in 100yr + 40% CC	Micco		
Date 20/10/2020 17:03	Designed by RB	Desinado		
File 10690-HYD-XX-XX-CA-	Checked by RJH	Diamage		
Innovyze	Source Control 2018.1.1			
Rainfall Details				
Return Period (years) Region Eng M5-60 (mm) Ratio R Summer Storms	100 Cv (Summer) 0.750 land and Wales Cv (Winter) 0.840 20.000 Shortest Storm (mins) 15 0.410 Longest Storm (mins) 10080 Yes Climate Change % +40			
<u> </u>	ime Area Diagram			
То	tal Area (ha) 0.084			
E	Time (mins) Area From: To: (ha)			
	0 4 0.084			

Hydrock Consultants Ltd			Page 3		
	10690	Clifton	Road, Deddington		
	Highwa	y Perme	able Paving		Sec. Sec.
	1 in 1	00yr +	40% CC		Micco
Date 20/10/2020 17:03	Design	ed by R	В		
File 10690-HYD-XX-XX-CA-	Checke	d by RJ	Н		Diamage
Innovyze	Source	Contro	1 2018.1.1		
Storage is C	<u>Model</u>	<u>Details</u> ver Leve	l (m) 100.000		
Porou	<u>s Car P</u>	<u>ark Str</u>	<u>ucture</u>		
Infiltration Coefficient Bas	se (m/hr)	0.68760	Width (m)	80.0	
Membrane Percolation	n (mm/hr)	1000	Length (m)	10.0	
Max Percolati	on (l/s)	222.2	Slope (1:X)	50.0	
Safet	y Factor	5.0	Depression Storage (mm)	5	
Invert I	Porosity	99 700	Evaporation (mm/day) Membrane Depth (m)	3 250	
				200	



	KEY EXISTING	
	DEVELOPMENT BOUNDARY	
	PROPSED	
	SURFACE INSPECTION CHAMBER (450 DIA)	
	5m OFFSET FROM SOAKAWAY	
	PRIVATE FOUL SEWER	
124.77 124 men 124.85		
	PRIVATE FOUL PUMPING STATION	
124.86		
	GENERAL DRAINAGE NOTES:	
• 123.95 • 124.07	 ALL DRAINAGE INDICATED ON THIS PLAN IS DESIGNED IN ACCO WITH THE HYDROCK REPORT (REF: 10690-HYD-XX-XX-RP-D-500 	DRDANCE 1).
$- \chi_{0} \rightarrow \chi \rightarrow $	2. USE OF THIS DRAWING DOES NOT ABSOLVE THE CLIENT FROM RESPONSIBILITIES UNDER THE HEALTH AND SAFETY: THE CON DESIGN AND MANAGEMENT RECULATIONS 2015 THE DRINCIPAL	HIS STRUCTION
124.39	DESIGN AND MANAGEMENT REGULATIONS 2015. THE PRINCIPA DESIGNER IS REQUIRED TO CONTACT HYDROCK CONSULTANT PERMITTING THIS DRAWING TO BE USED IN CONNECTION WITH	L S PRIOR TO I ANY
	CONSTRUCTION WORKS.	
	REGULATIONS, BS EN-752 DRAIN AND SEWER SYSTEMS OUTSIL BUILDINGS AND OTHER RELEVANT BRITISH STANDARDS AND O PRACTICES.	DE ODES OF
grass	 ALL SEWERS TO BE LAID SOFFIT TO SOFFIT UNLESS OTHERWING IT IS THE CONTRACTORS RESPONSIBILITY TO LOCATE EXISTIN 	SE SHOWN. G
9.000	SERVICES ON SITE ACCURATELY.	
	FROM UNDERGROUND SERVICES" WHEN EXCAVATING AROUND SERVICES.	D EXISTING
	7. THE CONTRACTOR IS TO VERIFY THE LINE, LEVEL AND DIAMET EXISTING SEWERS BEFORE COMMENCING DRAINAGE WORKS.	ER OF
	8. ALL LEVELS ARE TO OS DATUM.	
+ 124.14 + 124.	9. COMPLIANCE WITH HEALTH & SAFETY MATTERS ON ANY TRENCH/MANHOLE IS OBLIGATORY AND A PERMIT TO ENTER A	CONFINED
	SPACE IS REQUIRED.	
· · · · · · · · · · · · · · · · · · ·		
1.1.124.0		
+ 123.95		
+ 123.97		
	REVISIONS	
	P03 26/11/20 UPDATED FOLLOWING REVISED LAYOUT RHE	B RJH RJH
	P02 13/11/20 UPDATED FOLLOWING REVISED LAYOUT RH P01 30/10/20 INITIAL ISSUE RH	RJH RJH RJH RJH
	Rev Date Description By	Ckd App
. 199.70	OVER COURT BARNS OVER LANE	
+ 123.7U	ALMONDSBURY BRISTOL	
arass	BS32 4DF t: +44 (0) 1454 619533 e: bristol@hvdrock.com	
	BLUE CEDAK HUIVIES	
+ 123.42	PROJECT	
	CLIFTON ROAD, DEDDINGTON	
	TITLE	
	SURFACE & FOUL WATER	
	DRAINAGE STRATEGY	
7 ₂₉		
[~] .0		
² + 122.97		
	HYDROCK PROJECT NO. SCALE @ A1	
	HYDROCK PROJECT NO. SCALE @ A1 C-10690 1:200	CTATIC
	HYDROCK PROJECT NO. C-10690 STATUS DESCRIPTION INFORMATION	status S2
	HYDROCK PROJECT NO. SCALE @ A1 C-10690 1:200 STATUS DESCRIPTION INFORMATION DRAWING NO. (PROJECT CODE-ORGINATOR-ZONE-LEVEL-TYPE-ROLE-NUMBER)	status S2 revision

Rob Belcher

From:	Tony Brummell <tony.brummell@cherwell-dc.gov.uk></tony.brummell@cherwell-dc.gov.uk>
Sent:	26 October 2020 06:38
То:	Rob Belcher
Subject:	Re: Clifton Road, Deddington - Culvert
Attachments:	SVC-SQL-UNI-01_CANONQXL05614_4776_001.pdf

Rob

Having researched this further I am aware of a large culvert crossing Clifton Road to west of your site but have no knowledge of any culvert within your site. But that's not to say there are none.

I have copied a couple of old maps. These don't suggest there is a watercourse, culverted or otherwise.

My advice would be to investigate further when you have cleared the site and are ready to start development. As well as Building Control Manager I am the Council's Flood Risk Manager. If you come across anything let me know and I can advise further.

Tony Brummell MSc CEng FICE FCIWEM MCIHT MCMI

Building Control Manager

Cherwell and South Northamptonshire Building Control Service

Cherwell District Council and South Northamptonshire Council

Direct Dial: 01295 221909

tony.brummell@cherwellandsouthnorthants.gov.uk

www.cherwell.gov.uk www.southnorthants.gov.uk

Find us on Facebook www.facebook.com/cherwelldistrictcouncil or www.facebook.com/southnorthantscouncil

Follow us on Twitter @Cherwellcouncil or @SNorthantsC

From: Rob Belcher <RobBelcher@hydrock.com>
Sent: 22 October 2020 10:30
To: Tony Brummell <Tony.Brummell@Cherwell-DC.gov.uk>
Subject: Clifton Road, Deddington - Culvert

Morning Tony,

Thanks for your time on the phone this morning.

Please see attached site layout and location plan. As mentioned on the phone, we are hoping to identify whether or not the culvert which runs underneath Earls Lane crosses south within the north-western most corner of our development site.

Any info you have which may be useful would be really helpful. Please don't hesitate to call or email.

Many thanks,

Rob Belcher BEng (Hons) GMICE

Assistant Engineer - Infrastructure

Following government advice, I am currently working from home. If we need to speak, drop me an email and I'll get back to you. For wider information on working with Hydrock during COVID-19 visit <u>hydrock.com/coronavirus</u>.

Hydrock

Over Court Barns, Over Lane, Almondsbury, Bristol BS32 4DF Tel: (01454) 619533 Internal Ext. 2207 hydrock.com



Six consecutive years in the 'Sunday Times 100 Best Companies to Work For' listing, and winner of the NCE100 'Health and Wellbeing Leader of the Year' award, 2019.



Hydrock Consultants Limited, company number 3118932 registered in England and Wales at Over Court Barns, Over Lane, Almondsbury, Bristol, BS32 4DF. Before printing this e-mail, please think about the environment. Disclaimer: The information in this e-mail is confidential and may be read, copied or used only by the intended recipients. If you are not the intended recipient you are hereby notified that any perusal, use, distribution, copying or disclosure is strictly prohibited. If you have received this e-mail in error please advise us immediately by return e-mail to bristol@hydrock.com and delete the e-mail document without making a copy. Whilst every effort has been made to ensure this email is virus free, no responsibility is accepted for loss or damage arising from viruses or changes made to this message after it was sent.

This e-mail (including any attachments) may be confidential and may contain legally privileged information. You should not disclose its contents to any other person. If you are not the intended recipient, please notify the sender immediately.

Whilst the Council has taken every reasonable precaution to minimise the risk of computer software viruses, it cannot accept liability for any damage which you may sustain as a result of such viruses. You should carry out your own virus checks before opening the e-mail(and/or any attachments).

Unless expressly stated otherwise, the contents of this e-mail represent only the views of the sender and does not impose any legal obligation upon the Council or commit the Council to any course of action.