


Woods Hardwick		Page 1
15-17 Goldington Road Bedford Bedfordshire MK40 3NH		
Date 08/04/2021 15:46 File SW PH9 Proposed	Designed by a.tew Checked by	
XP Solutions		Network 2014.1.1

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD






FEH Rainfall Model

Return Period (years)	2
Site Location GB 450500 225250 SP 50500 25250	
C (1km)	-0.023
D1 (1km)	0.328
D2 (1km)	0.309
D3 (1km)	0.264
E (1km)	0.292
F (1km)	2.461
Maximum Rainfall (mm/hr)	0
Maximum Time of Concentration (mins)	30
Foul Sewage (l/s/ha)	0.000
Volumetric Runoff Coeff.	0.750
Add Flow / Climate Change (%)	0
Minimum Backdrop Height (m)	0.000
Maximum Backdrop Height (m)	0.000
Min Design Depth for Optimisation (m)	1.200
Min Vel for Auto Design only (m/s)	1.00
Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Network Design Table for Storm

- Indicates pipe length does not match coordinates

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
1.000	9.050	0.650	13.9	0.026	5.00	0.0	0.600	\	-1	
1.001	9.000	0.500	18.0	0.016	0.00	0.0	0.600	\	-1	
1.002	7.527	0.250	30.1	0.024	0.00	0.0	0.600	\	-1	
1.003	12.654	0.287	44.1	0.000	0.00	0.0	0.600	o	150	
1.004	45.169	0.115	392.8	0.053	0.00	0.0	0.600	o	450	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	0.00	5.01	123.850	0.026	0.0	0.0	0.0	14.05	50669.7	0.0
1.001	0.00	5.02	123.200	0.042	0.0	0.0	0.0	12.36	44557.7	0.0
1.002	0.00	5.04	122.700	0.066	0.0	0.0	0.0	9.55	34441.1	0.0
1.003	0.00	5.17	122.450	0.066	0.0	0.0	0.0	1.52	26.9	0.0
1.004	0.00	5.91	121.863	0.119	0.0	0.0	0.0	1.02	162.2	0.0

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
2.000	24.880	0.130	191.4	0.076	5.00	0.0	0.600	o	375	
2.001	6.893	0.027	255.3	0.000	0.00	0.0	0.600	o	375	
1.005	28.960	0.050	579.2	0.008	0.00	0.0	0.600	o	600	
3.000	25.800	0.112	230.4	0.028	5.00	0.0	0.600	oo	41	
1.006	10.020	0.017	589.4	0.049	0.00	0.0	0.600	o	600	
1.007	21.048	0.156	134.9	0.000	0.00	0.0	0.600	o	150	
1.008	16.030	0.300	53.4	0.000	0.00	0.0	0.600	o	150	
1.009	71.700	0.910	78.8	0.000	0.00	0.0	0.600	o	225	
4.000	42.980	0.233	184.5	0.500	5.00	0.0	0.600	o	225	
5.000	8.290	0.537	15.4	0.050	5.00	0.0	0.600	o	150	
4.001	7.220	0.030	240.7	0.000	0.00	0.0	0.600	o	300	
4.002	41.565	0.354	117.4	0.020	0.00	0.0	0.600	o	300	
6.000	17.914	0.241	74.3	0.020	5.00	0.0	0.600	o	100	
6.001	47.052	0.866	54.3	0.022	0.00	0.0	0.600	o	150	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
2.000	0.00	5.32	121.980	0.076	0.0	0.0	0.0	1.31	144.3	0.0
2.001	0.00	5.42	121.850	0.076	0.0	0.0	0.0	1.13	124.7	0.0
1.005	0.00	6.39	121.598	0.203	0.0	0.0	0.0	1.00	284.1	0.0
3.000	0.00	5.42	121.660	0.028	0.0	0.0	0.0	1.03	145.2	0.0
1.006	0.00	6.56	121.548	0.280	0.0	0.0	0.0	1.00	281.6	0.0
1.007	0.00	6.97	121.531	0.280	0.0	0.0	0.0	0.86	15.3	0.0
1.008	0.00	7.16	121.375	0.280	0.0	0.0	0.0	1.38	24.4	0.0
1.009	0.00	7.97	121.000	0.280	0.0	0.0	0.0	1.47	58.6	0.0
4.000	0.00	5.75	121.507	0.500	0.0	0.0	0.0	0.96	38.1	0.0
5.000	0.00	5.05	121.961	0.050	0.0	0.0	0.0	2.58	45.5	0.0
4.001	0.00	5.87	121.274	0.550	0.0	0.0	0.0	1.01	71.3	0.0
4.002	0.00	6.34	121.244	0.570	0.0	0.0	0.0	1.45	102.5	0.0
6.000	0.00	5.33	123.132	0.020	0.0	0.0	0.0	0.89	7.0	0.0
6.001	0.00	5.91	122.891	0.042	0.0	0.0	0.0	1.37	24.2	0.0

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by


XP Solutions Network 2014.1.1

Network Design Table for Storm














PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
6.002	64.199	0.985	65.2	0.000	0.00	0.0	0.600	o	150	
4.003	63.899	0.200	319.5	0.000	0.00	0.0	0.600	o	300	
7.000	128.657	0.762	168.8	0.250	5.00	0.0	0.600	o	300	
7.001	14.690	0.130	113.0	0.020	0.00	0.0	0.600	o	300	
4.004	17.440	0.150	116.3	0.000	0.00	0.0	0.600	oo	42	
4.005	36.660	0.120	305.5	0.000	0.00	0.0	0.600	o	525	
4.006	64.888	0.210	309.0	0.000	0.00	0.0	0.600	o	525	
4.007	49.402	0.160	308.8	0.000	0.00	0.0	0.600	o	525	
8.000	1.000	0.100	10.0	0.000	5.00	0.0	0.600	o	100	
9.000	30.130	0.690	43.7	0.221	5.00	0.0	0.600	o	300	
9.001	14.283	0.250	57.1	0.048	0.00	0.0	0.600	o	375	
9.002	39.587	1.390	28.5	0.055	0.00	0.0	0.600	o	375	
10.000	58.183	0.265	219.6	0.339	5.00	0.0	0.600	o	450	
9.003	43.381	0.280	154.9	0.137	0.00	0.0	0.600	o	525	
9.004	10.311	0.170	60.7	0.000	0.00	0.0	0.600	o	525	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
6.002	0.00	6.77	122.025	0.042	0.0	0.0	0.0	1.25	22.0	0.0
4.003	0.00	7.98	120.890	0.612	0.0	0.0	0.0	0.87	61.8	0.0
7.000	0.00	6.78	121.882	0.250	0.0	0.0	0.0	1.21	85.3	0.0
7.001	0.00	6.94	121.120	0.270	0.0	0.0	0.0	1.48	104.5	0.0
4.004	0.00	8.16	120.690	0.882	0.0	0.0	0.0	1.68	371.3	0.0
4.005	0.00	8.64	120.540	0.882	0.0	0.0	0.0	1.28	276.3	0.0
4.006	0.00	9.49	120.420	0.882	0.0	0.0	0.0	1.27	274.7	0.0
4.007	0.00	10.14	120.210	0.882	0.0	0.0	0.0	1.27	274.8	0.0
8.000	0.00	5.01	120.605	0.000	0.0	0.0	0.0	2.46	19.3	0.0
9.000	0.00	5.21	123.520	0.221	0.0	0.0	0.0	2.39	168.6	0.0
9.001	0.00	5.31	122.755	0.269	0.0	0.0	0.0	2.40	265.2	0.0
9.002	0.00	5.50	122.505	0.324	0.0	0.0	0.0	3.41	376.2	0.0
10.000	0.00	5.71	121.305	0.339	0.0	0.0	0.0	1.37	217.6	0.0
9.003	0.00	6.11	120.965	0.800	0.0	0.0	0.0	1.80	389.0	0.0
9.004	0.00	6.17	120.685	0.800	0.0	0.0	0.0	2.88	623.4	0.0

Woods Hardwick		Page 4
15-17 Goldington Road Bedford Bedfordshire MK40 3NH		
Date 08/04/2021 15:46 File SW PH9 Proposed		
XP Solutions		Network 2014.1.1

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
8.001	61.528	0.170	361.9	0.151	0.00	0.0	0.600	o	750	
11.000	49.643	0.380	130.6	0.098	5.00	0.0	0.600	o	300	
11.001	29.531	0.150	196.9	0.171	0.00	0.0	0.600	o	450	
11.002	56.417	0.325	173.6	0.314	0.00	0.0	0.600	o	525	
11.003	8.196	0.240	34.2	0.107	0.00	0.0	0.600	o	600	
12.000	24.053	0.555	43.3	0.000	5.00	0.0	0.600	o	750	
8.002	2.406	0.060	40.1	0.000	0.00	0.0	0.600	o	300	
4.008	36.168	0.120	301.4	0.000	0.00	0.0	0.600	o	525	
13.000	24.393	0.110	221.8	0.020	5.00	0.0	0.600	o	450	
13.001	40.256	0.150	268.4	0.067	0.00	0.0	0.600	o	600	
14.000	13.311	0.925	14.4	0.060	5.00	0.0	0.600	o	225	
13.002	8.528	0.145	58.8	0.000	0.00	0.0	0.600	o	150	
4.009	28.200	0.140	201.4	0.000	0.00	0.0	0.600	o	525	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
8.001	0.00	6.87	120.505	0.951	0.0	0.0	0.0	1.47	647.3	0.0
11.000	0.00	5.60	121.730	0.098	0.0	0.0	0.0	1.37	97.1	0.0
11.001	0.00	5.94	121.200	0.269	0.0	0.0	0.0	1.45	229.9	0.0
11.002	0.00	6.50	120.975	0.583	0.0	0.0	0.0	1.70	367.4	0.0
11.003	0.00	6.53	120.575	0.690	0.0	0.0	0.0	4.18	1180.9	0.0
12.000	0.00	5.09	120.890	0.000	0.0	0.0	0.0	4.26	1881.1	0.0
8.002	0.00	6.89	120.335	1.641	0.0	0.0	0.0	2.49	176.0	0.0
4.008	0.00	10.61	120.050	2.523	0.0	0.0	0.0	1.28	278.2	0.0
13.000	0.00	5.30	120.860	0.020	0.0	0.0	0.0	1.36	216.5	0.0
13.001	0.00	5.75	120.600	0.087	0.0	0.0	0.0	1.48	418.9	0.0
14.000	0.00	5.06	121.375	0.060	0.0	0.0	0.0	3.47	137.9	0.0
13.002	0.00	5.86	120.450	0.147	0.0	0.0	0.0	1.31	23.2	0.0
4.009	0.00	10.90	119.930	2.670	0.0	0.0	0.0	1.57	340.9	0.0

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by


XP Solutions Network 2014.1.1

Network Design Table for Storm


















PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
1.010	50.410	0.120	420.1	0.000	0.00	0.0	0.600	o	525	
1.011	10.500	0.030	350.0	0.000	0.00	0.0	0.600	o	525	
1.012	37.570	0.090	417.4	0.000	0.00	0.0	0.600	o	525	
1.013	9.819	0.032	305.0	0.000	0.00	0.0	0.600	o	525	
1.014	13.878	0.038	365.2	0.000	0.00	0.0	0.600	o	525	
1.015	42.621	0.510	83.6	0.000	0.00	0.0	0.600	o	525	
15.000	53.163	0.360	147.7	0.213	5.00	0.0	0.600	o	375	
16.000	15.820	0.210	75.3	0.064	5.00	0.0	0.600	o	150	
16.001	38.537	0.810	47.6	0.061	0.00	0.0	0.600	o	300	
15.001	7.739	0.290	26.7	0.009	0.00	0.0	0.600	o	375	
17.000	30.705	0.190	161.6	0.133	5.00	0.0	0.600	o	300	
15.002	40.050	0.200	200.3	0.105	0.00	0.0	0.600	o	450	
15.003	12.752	0.070	182.2	0.052	0.00	0.0	0.600	o	525	
18.000	54.226	0.860	63.1	0.152	5.00	0.0	0.600	o	300	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.010	0.00	11.68	119.790	2.950	0.0	0.0	0.0	1.09	235.2	0.0
1.011	0.00	11.82	119.670	2.950	0.0	0.0	0.0	1.19	257.9	0.0
1.012	0.00	12.40	119.640	2.950	0.0	0.0	0.0	1.09	236.0	0.0
1.013	0.00	12.53	119.550	2.950	0.0	0.0	0.0	1.28	276.5	0.0
1.014	0.00	12.72	119.518	2.950	0.0	0.0	0.0	1.17	252.4	0.0
1.015	0.00	13.01	119.480	2.950	0.0	0.0	0.0	2.45	530.7	0.0
15.000	0.00	5.60	123.005	0.213	0.0	0.0	0.0	1.49	164.4	0.0
16.000	0.00	5.23	123.890	0.064	0.0	0.0	0.0	1.16	20.5	0.0
16.001	0.00	5.51	123.530	0.125	0.0	0.0	0.0	2.29	161.5	0.0
15.001	0.00	5.63	122.645	0.347	0.0	0.0	0.0	3.52	388.7	0.0
17.000	0.00	5.41	122.620	0.133	0.0	0.0	0.0	1.23	87.2	0.0
15.002	0.00	6.10	122.280	0.585	0.0	0.0	0.0	1.43	227.9	0.0
15.003	0.00	6.23	122.005	0.637	0.0	0.0	0.0	1.66	358.6	0.0
18.000	0.00	5.46	123.020	0.152	0.0	0.0	0.0	1.98	140.2	0.0

Woods Hardwick		Page 6
15-17 Goldington Road Bedford Bedfordshire MK40 3NH		
Date 08/04/2021 15:46 File SW PH9 Proposed		
XP Solutions		Network 2014.1.1

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
15.004	19.449	0.300	64.8	0.069	0.00	0.0	0.600	o	525	
15.005	11.031	0.060	183.9	0.012	0.00	0.0	0.600	o	600	
15.006	60.371	0.300	201.2	0.087	0.00	0.0	0.600	o	750	
19.000	19.311	0.130	148.5	0.045	5.00	0.0	0.600	o	150	
19.001	7.717	0.060	128.6	0.000	0.00	0.0	0.600	o	225	
19.002	36.223	0.250	144.9	0.040	0.00	0.0	0.600	o	300	
19.003	14.362	0.100	143.6	0.035	0.00	0.0	0.600	o	375	
19.004	26.956	0.130	207.4	0.031	0.00	0.0	0.600	o	750	
19.005	50.007	0.340	147.1	0.045	0.00	0.0	0.600	o	750	
15.007	21.961	0.320	68.6	0.190	0.00	0.0	0.600	o	750	
20.000	24.657	0.170	145.0	0.059	5.00	0.0	0.600	o	300	
20.001	11.150	0.050	223.0	0.000	0.00	0.0	0.600	o	375	
20.002	57.319	0.250	229.3	0.100	0.00	0.0	0.600	o	375	
20.003	57.682	0.250	230.7	0.209	0.00	0.0	0.600	o	525	
15.008	53.514	0.270	198.2	0.060	0.00	0.0	0.600	o	750	
21.000	26.369	1.060	24.9	0.100	5.00	0.0	0.600	o	225	
21.001	26.368	1.360	19.4	0.032	0.00	0.0	0.600	o	225	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
15.004	0.00	6.34	121.935	0.858	0.0	0.0	0.0	2.79	602.9	0.0
15.005	0.00	6.44	121.560	0.870	0.0	0.0	0.0	1.79	506.9	0.0
15.006	0.00	6.96	121.350	0.957	0.0	0.0	0.0	1.97	869.9	0.0
19.000	0.00	5.39	122.660	0.045	0.0	0.0	0.0	0.82	14.5	0.0
19.001	0.00	5.50	122.455	0.045	0.0	0.0	0.0	1.15	45.8	0.0
19.002	0.00	5.97	122.320	0.085	0.0	0.0	0.0	1.30	92.2	0.0
19.003	0.00	6.12	121.995	0.120	0.0	0.0	0.0	1.51	166.8	0.0
19.004	0.00	6.36	121.520	0.151	0.0	0.0	0.0	1.94	856.9	0.0
19.005	0.00	6.72	121.390	0.196	0.0	0.0	0.0	2.31	1018.5	0.0
15.007	0.00	7.06	121.050	1.343	0.0	0.0	0.0	3.38	1493.7	0.0
20.000	0.00	5.32	121.900	0.059	0.0	0.0	0.0	1.30	92.1	0.0
20.001	0.00	5.47	121.655	0.059	0.0	0.0	0.0	1.21	133.6	0.0
20.002	0.00	6.27	121.605	0.159	0.0	0.0	0.0	1.19	131.7	0.0
20.003	0.00	6.92	121.205	0.368	0.0	0.0	0.0	1.47	318.3	0.0
15.008	0.00	7.51	120.730	1.771	0.0	0.0	0.0	1.98	876.6	0.0
21.000	0.00	5.17	123.405	0.100	0.0	0.0	0.0	2.63	104.7	0.0
21.001	0.00	5.31	122.345	0.132	0.0	0.0	0.0	2.99	118.7	0.0

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
15.009	47.191	0.440	107.3	0.110	0.00	0.0	0.600	o	750	
15.010	41.163	0.210	196.0	0.238	0.00	0.0	0.600	o	900	
22.000	39.777	0.370	107.5	0.211	5.00	0.0	0.600	o	300	
22.001	55.655	2.340	23.8	0.079	0.00	0.0	0.600	o	375	
15.011	26.994	0.153	176.4	0.045	0.00	0.0	0.600	o	900	
15.012	26.010	0.147	176.9	0.040	0.00	0.0	0.600	o	900	
23.000	22.710	0.560	40.6	0.235	5.00	0.0	0.600	o	300	
23.001	10.044	0.070	143.5	0.000	0.00	0.0	0.600	o	300	
23.002	67.567	0.770	87.7	0.109	0.00	0.0	0.600	o	375	
23.003	55.711	0.190	293.2	0.119	0.00	0.0	0.600	o	375	
23.004	55.725	1.555	35.8	0.050	0.00	0.0	0.600	o	375	
15.013	19.547	0.040	488.7	0.145	0.00	0.0	0.600	o	1050	
15.014	25.868	0.050	517.4	0.027	0.00	0.0	0.600	o	1050	
24.000	21.406	0.680	31.5	0.164	5.00	0.0	0.600	o	225	
24.001	36.607	0.250	146.4	0.019	0.00	0.0	0.600	o	300	
24.002	21.558	0.400	53.9	0.056	0.00	0.0	0.600	o	300	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
15.009	0.00	7.80	120.460	2.013	0.0	0.0	0.0	2.70	1193.7	0.0
15.010	0.00	8.11	119.870	2.251	0.0	0.0	0.0	2.23	1421.5	0.0
22.000	0.00	5.44	122.970	0.211	0.0	0.0	0.0	1.52	107.2	0.0
22.001	0.00	5.69	122.525	0.290	0.0	0.0	0.0	3.73	411.8	0.0
15.011	0.00	8.30	119.660	2.586	0.0	0.0	0.0	2.36	1498.8	0.0
15.012	0.00	8.49	119.507	2.626	0.0	0.0	0.0	2.35	1496.6	0.0
23.000	0.00	5.15	123.105	0.235	0.0	0.0	0.0	2.48	175.0	0.0
23.001	0.00	5.28	122.545	0.235	0.0	0.0	0.0	1.31	92.6	0.0
23.002	0.00	5.86	122.400	0.344	0.0	0.0	0.0	1.94	213.7	0.0
23.003	0.00	6.74	121.630	0.463	0.0	0.0	0.0	1.05	116.3	0.0
23.004	0.00	7.05	121.440	0.513	0.0	0.0	0.0	3.04	335.2	0.0
15.013	0.00	8.70	119.210	3.284	0.0	0.0	0.0	1.55	1344.0	0.0
15.014	0.00	8.98	119.170	3.311	0.0	0.0	0.0	1.51	1305.9	0.0
24.000	0.00	5.15	123.125	0.164	0.0	0.0	0.0	2.34	93.0	0.0
24.001	0.00	5.62	122.370	0.183	0.0	0.0	0.0	1.30	91.7	0.0
24.002	0.00	5.79	122.120	0.239	0.0	0.0	0.0	2.15	151.7	0.0

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
24.003	29.650	1.850	16.0	0.076	0.00	0.0	0.600	o	300	
15.015	31.230#	0.090	347.0	0.100	0.00	0.0	0.600	o	1050	
15.016	3.227	0.020	161.4	0.000	0.00	0.0	0.600	o	225	
1.016	12.868	0.040	321.7	0.000	0.00	0.0	0.600	o	525	
1.017	4.635	0.020	231.8	0.000	0.00	0.0	0.600	o	525	
1.018	7.557	0.040	188.9	0.000	0.00	0.0	0.600	o	525	
1.019	3.323	0.030	110.8	0.000	0.00	0.0	0.600	o	525	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
24.003	0.00	5.92	121.720	0.315	0.0	0.0	0.0	3.95	279.0	0.0
15.015	0.00	9.26	119.120	3.726	0.0	0.0	0.0	1.84	1596.9	0.0
15.016	0.00	9.32	118.990	3.726	0.0	0.0	0.0	1.03	40.8	0.0
1.016	0.00	13.19	118.970	6.676	0.0	0.0	0.0	1.24	269.1	0.0
1.017	0.00	13.24	118.930	6.676	0.0	0.0	0.0	1.47	317.6	0.0
1.018	0.00	13.32	118.710	6.676	0.0	0.0	0.0	1.63	352.0	0.0
1.019	0.00	13.34	118.670	6.676	0.0	0.0	0.0	2.13	460.6	0.0

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.019	HW01	119.770	118.640	0.000	0	0

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.840	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	1.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	4
Number of Online Controls	6	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

15-17 Goldington Road
Bedford
Bedfordshire MK40 3NH




Date 08/04/2021 15:46
File SW PH9 Proposed

Designed by a.tew
Checked by

XP Solutions Network 2014.1.1

Synthetic Rainfall Details

Rainfall Model	FEH
Return Period (years)	100
Site Location	GB 450500 225250 SP 50500 25250
C (1km)	-0.023
D1 (1km)	0.328
D2 (1km)	0.309
D3 (1km)	0.264
E (1km)	0.292
F (1km)	2.461
Summer Storms	No
Winter Storms	Yes
Cv (Summer)	0.750
Cv (Winter)	0.840
Storm Duration (mins)	15

Woods Hardwick		Page 10
15-17 Goldington Road Bedford Bedfordshire MK40 3NH		
Date 08/04/2021 15:46 File SW PH9 Proposed	Designed by a.tew Checked by	
XP Solutions		Network 2014.1.1

Online Controls for Storm

Orifice Manhole: Swale, DS/PN: 1.001, Volume (m³): 32.6

Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 123.200

Orifice Manhole: Swale, DS/PN: 1.002, Volume (m³): 32.5

Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 122.700

Hydro-Brake® Manhole: B1- 9, DS/PN: 1.007, Volume (m³): 5.6

Design Head (m) 1.200 Hydro-Brake® Type Md5 SW Only Invert Level (m) 121.531
Design Flow (l/s) 15.0 Diameter (mm) 150

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	5.0	1.200	14.8	3.000	23.5	7.000	35.8
0.200	9.8	1.400	16.0	3.500	25.3	7.500	37.1
0.300	10.9	1.600	17.1	4.000	27.1	8.000	38.3
0.400	10.8	1.800	18.2	4.500	28.7	8.500	39.5
0.500	10.8	2.000	19.2	5.000	30.3	9.000	40.6
0.600	11.1	2.200	20.1	5.500	31.8	9.500	41.7
0.800	12.3	2.400	21.0	6.000	33.2		
1.000	13.6	2.600	21.8	6.500	34.5		

Complex Manhole: 243a (HB), DS/PN: 8.002, Volume (m³): 49.5

Hydro-Brake Optimum®

Unit Reference MD-SHE-0045-1400-2400-1400
Design Head (m) 2.400
Design Flow (l/s) 1.4
Flush-Flo™ Calculated
Objective Minimise upstream storage
Diameter (mm) 45
Invert Level (m) 120.335
Minimum Outlet Pipe Diameter (mm) 75
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	2.400	1.4	Kick-Flo®	0.404	0.6
Flush-Flo™	0.200	0.8	Mean Flow over Head Range	-	1.0

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Hydro-Brake Optimum®

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	0.7	1.200	1.0	3.000	1.5	7.000	2.3
0.200	0.8	1.400	1.1	3.500	1.7	7.500	2.4
0.300	0.7	1.600	1.2	4.000	1.8	8.000	2.4
0.400	0.6	1.800	1.2	4.500	1.9	8.500	2.5
0.500	0.7	2.000	1.3	5.000	2.0	9.000	2.6
0.600	0.8	2.200	1.3	5.500	2.0	9.500	2.6
0.800	0.9	2.400	1.4	6.000	2.1		
1.000	0.9	2.600	1.4	6.500	2.2		

Hydro-Brake Optimum®

Unit Reference MD-SHE-0070-2100-0900-2100
 Design Head (m) 0.900
 Design Flow (l/s) 2.1
 Flush-Flo™ Calculated
 Objective Minimise upstream storage
 Diameter (mm) 70
 Invert Level (m) 121.835
 Minimum Outlet Pipe Diameter (mm) 100
 Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.900	2.1	Kick-Flo®	0.563	1.7
Flush-Flo™	0.271	2.1	Mean Flow over Head Range	-	1.8

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	1.8	1.200	2.4	3.000	3.6	7.000	5.4
0.200	2.1	1.400	2.6	3.500	3.9	7.500	5.6
0.300	2.1	1.600	2.7	4.000	4.2	8.000	5.8
0.400	2.0	1.800	2.9	4.500	4.4	8.500	5.9
0.500	1.9	2.000	3.0	5.000	4.6	9.000	6.1
0.600	1.7	2.200	3.2	5.500	4.8	9.500	6.3
0.800	2.0	2.400	3.3	6.000	5.0		
1.000	2.2	2.600	3.4	6.500	5.2		

Hydro-Brake Optimum® Manhole: 234 (HB), DS/PN: 13.002, Volume (m³): 18.0

Unit Reference MD-SHE-0074-3000-1600-3000
 Design Head (m) 1.600
 Design Flow (l/s) 3.0
 Flush-Flo™ Calculated
 Objective Minimise upstream storage

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Hydro-Brake Optimum® Manhole: 234 (HB), DS/PN: 13.002, Volume (m³): 18.0

Diameter (mm) 74
 Invert Level (m) 120.450
 Minimum Outlet Pipe Diameter (mm) 100
 Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.600	3.0	Kick-Flo®	0.661	2.0
Flush-Flo™	0.323	2.5	Mean Flow over Head Range	-	2.4

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	2.0	1.200	2.6	3.000	4.0	7.000	6.0
0.200	2.4	1.400	2.8	3.500	4.3	7.500	6.2
0.300	2.5	1.600	3.0	4.000	4.6	8.000	6.4
0.400	2.5	1.800	3.2	4.500	4.9	8.500	6.5
0.500	2.4	2.000	3.3	5.000	5.1	9.000	6.7
0.600	2.2	2.200	3.5	5.500	5.3	9.500	6.9
0.800	2.2	2.400	3.6	6.000	5.6		
1.000	2.4	2.600	3.8	6.500	5.8		

Complex Manhole: 256 (HB), DS/PN: 15.016, Volume (m³): 38.0

Hydro-Brake Optimum®

Unit Reference MD-SCL-0042-1300-2400-1300
 Design Head (m) 2.400
 Design Flow (l/s) 1.3
 Flush-Flo™ Calculated
 Objective Minimise blockage risk
 Diameter (mm) 42
 Invert Level (m) 118.990
 Minimum Outlet Pipe Diameter (mm) 75
 Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	2.400	1.3	Kick-Flo®	0.372	0.6
Flush-Flo™	0.170	0.7	Mean Flow over Head Range	-	0.9

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Hydro-Brake Optimum®

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	0.7	1.200	1.0	3.000	1.4	7.000	2.1
0.200	0.7	1.400	1.0	3.500	1.5	7.500	2.2
0.300	0.7	1.600	1.1	4.000	1.6	8.000	2.2
0.400	0.6	1.800	1.1	4.500	1.7	8.500	2.3
0.500	0.7	2.000	1.2	5.000	1.8	9.000	2.4
0.600	0.7	2.200	1.2	5.500	1.9	9.500	2.4
0.800	0.8	2.400	1.3	6.000	2.0		
1.000	0.9	2.600	1.3	6.500	2.0		

Hydro-Brake Optimum®


Unit Reference MD-SHE-0107-4900-0820-4900
 Design Head (m) 0.820
 Design Flow (l/s) 4.9
 Flush-Flo™ Calculated
 Objective Minimise upstream storage
 Diameter (mm) 107
 Invert Level (m) 120.560
 Minimum Outlet Pipe Diameter (mm) 150
 Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.820	4.9	Kick-Flo®	0.545	4.1
Flush-Flo™	0.245	4.9	Mean Flow over Head Range	-	4.2

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.7	1.200	5.8	3.000	9.0	7.000	13.5
0.200	4.9	1.400	6.3	3.500	9.7	7.500	13.9
0.300	4.9	1.600	6.7	4.000	10.3	8.000	14.3
0.400	4.7	1.800	7.1	4.500	10.9	8.500	14.7
0.500	4.4	2.000	7.4	5.000	11.5	9.000	15.2
0.600	4.2	2.200	7.8	5.500	12.0	9.500	15.6
0.800	4.8	2.400	8.1	6.000	12.5		
1.000	5.4	2.600	8.4	6.500	13.0		

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions

Network 2014.1.1

Storage Structures for Storm

Complex Manhole: SW MH, DS/PN: 2.001

Tank or Pond

Invert Level (m) 121.840

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	69.0	0.401	0.0	0.403	7.0	0.704	0.0
0.400	69.0	0.402	0.0	0.703	7.0		

Porous Car Park

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.7
Membrane Percolation (mm/hr)	1000	Length (m)	60.0
Max Percolation (l/s)	145.0	Slope (1:X)	80.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	5
Invert Level (m)	122.630	Cap Volume Depth (m)	0.000

Complex Manhole: Pond, DS/PN: 12.000

Tank or Pond

Invert Level (m) 120.890

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	337.7	2.200	1044.5

Trench Soakaway

Infiltration Coefficient Base (m/hr)	0.12564	Trench Width (m)	10.0
Infiltration Coefficient Side (m/hr)	0.00000	Trench Length (m)	22.0
Safety Factor	1.0	Slope (1:X)	0.0
Porosity	0.30	Cap Volume Depth (m)	0.000
Invert Level (m)	120.890	Cap Infiltration Depth (m)	0.000

Tank or Pond Manhole: 232, DS/PN: 13.000

Invert Level (m) 120.860

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	60.0	0.500	60.0	0.501	0.0

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH

Designed by a.tew
 Checked by



Date 08/04/2021 15:46
 File SW PH9 Proposed

XP Solutions Network 2014.1.1

Complex Manhole: 256 (HB), DS/PN: 15.016

Trench Soakaway

Infiltration Coefficient Base (m/hr) 0.02707	Trench Width (m) 6.8
Infiltration Coefficient Side (m/hr) 0.00000	Trench Length (m) 62.8
Safety Factor 1.0	Slope (1:X) 0.0
Porosity 0.30	Cap Volume Depth (m) 0.000
Invert Level (m) 118.990	Cap Infiltration Depth (m) 0.000

Tank or Pond

Invert Level (m) 119.020

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	445.0	2.800	1965.9	2.801	0.0

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions

Network 2014.1.1

Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 1.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 4
 Number of Online Controls 6 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH
 Site Location GB 450500 225250 SP 50500 25250
 C (1km) -0.023
 D1 (1km) 0.328
 D2 (1km) 0.309
 D3 (1km) 0.264
 E (1km) 0.292
 F (1km) 2.461
 Cv (Summer) 0.750
 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status ON
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 30
 Climate Change (%) 0

PN	Storm	Return Period	Climate Change	First X Surcharge	First Y Flood	First Z Overflow	O/F Act.	Lvl Exc.
1.000	15 Winter	30	0%					
1.001	15 Winter	30	0%					
1.002	60 Winter	30	0%					
1.003	60 Winter	30	0%					
1.004	30 Winter	30	0%					
2.000	15 Winter	30	0%					
2.001	30 Winter	30	0%					
1.005	30 Winter	30	0%					
3.000	30 Winter	30	0%	30/15 Summer				
1.006	30 Winter	30	0%					
1.007	30 Winter	30	0%	30/15 Summer				
1.008	360 Summer	30	0%					
1.009	360 Summer	30	0%					
4.000	15 Winter	30	0%	30/15 Summer	30/15 Summer			5

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH




Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	Storm	Return Climate Period	Change	First X Surcharge	First Y Flood	First Z Overflow Act.	O/F	Lvl Exc.
5.000	15 Winter	30	0%	30/15 Summer				
4.001	15 Winter	30	0%	30/15 Summer				
4.002	15 Winter	30	0%	30/15 Summer				
6.000	15 Winter	30	0%	30/15 Summer				
6.001	15 Winter	30	0%					
6.002	15 Winter	30	0%					
4.003	15 Winter	30	0%	30/15 Summer				
7.000	15 Winter	30	0%	30/15 Summer				
7.001	15 Winter	30	0%					
4.004	15 Winter	30	0%					
4.005	15 Winter	30	0%					
4.006	15 Winter	30	0%					
4.007	15 Winter	30	0%					
8.000	60 Winter	30	0%					
9.000	15 Winter	30	0%					
9.001	15 Winter	30	0%					
9.002	15 Winter	30	0%					
10.000	15 Winter	30	0%	30/15 Summer				
9.003	15 Winter	30	0%	30/15 Summer				
9.004	15 Summer	30	0%	30/15 Summer				
8.001	15 Summer	30	0%	30/15 Summer				
11.000	15 Summer	30	0%	30/15 Summer				
11.001	15 Winter	30	0%	30/15 Summer				
11.002	15 Winter	30	0%	30/15 Summer				
11.003	15 Summer	30	0%	30/15 Summer				
12.000	480 Winter	30	0%	30/240 Winter				
8.002	480 Winter	30	0%	30/15 Summer				
4.008	15 Winter	30	0%					
13.000	120 Winter	30	0%					
13.001	120 Winter	30	0%					
14.000	15 Winter	30	0%					
13.002	15 Winter	30	0%	30/15 Summer				
4.009	15 Winter	30	0%					
1.010	15 Winter	30	0%					
1.011	15 Winter	30	0%					
1.012	15 Winter	30	0%					
1.013	15 Winter	30	0%					
1.014	15 Winter	30	0%					
1.015	15 Winter	30	0%					
15.000	15 Winter	30	0%					
16.000	15 Winter	30	0%	30/15 Summer				
16.001	15 Winter	30	0%					
15.001	15 Winter	30	0%					
17.000	15 Winter	30	0%					
15.002	15 Winter	30	0%	30/15 Summer				
15.003	15 Winter	30	0%					
18.000	15 Winter	30	0%					
15.004	15 Winter	30	0%					
15.005	15 Winter	30	0%					
15.006	15 Winter	30	0%					

Woods Hardwick		Page 18
15-17 Goldington Road Bedford Bedfordshire MK40 3NH		
Date 08/04/2021 15:46 File SW PH9 Proposed	Designed by a.tew Checked by	
XP Solutions		Network 2014.1.1

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	Storm	Return Period	Climate Change	First X Surcharge	First Y Flood	First Z Overflow	O/F Act.	Lvl Exc.
19.000	15 Winter	30	0%	30/15 Summer				
19.001	15 Winter	30	0%					
19.002	15 Winter	30	0%					
19.003	15 Winter	30	0%					
19.004	15 Winter	30	0%					
19.005	15 Winter	30	0%					
15.007	15 Winter	30	0%					
20.000	15 Winter	30	0%					
20.001	15 Winter	30	0%					
20.002	15 Winter	30	0%					
20.003	15 Winter	30	0%					
15.008	15 Winter	30	0%					
21.000	15 Winter	30	0%					
21.001	15 Winter	30	0%					
15.009	15 Winter	30	0%					
15.010	1440 Winter	30	0%					
22.000	15 Winter	30	0%					
22.001	15 Winter	30	0%					
15.011	1440 Winter	30	0%	30/480 Winter				
15.012	1440 Winter	30	0%	30/240 Winter				
23.000	15 Winter	30	0%					
23.001	15 Winter	30	0%	30/15 Summer				
23.002	15 Winter	30	0%					
23.003	15 Winter	30	0%	30/15 Summer				
23.004	15 Winter	30	0%					
15.013	1440 Winter	30	0%	30/15 Winter				
15.014	1440 Winter	30	0%	30/120 Winter				
24.000	15 Winter	30	0%					
24.001	15 Winter	30	0%					
24.002	15 Winter	30	0%					
24.003	15 Winter	30	0%					
15.015	1440 Winter	30	0%	30/120 Winter				
15.016	1440 Winter	30	0%	30/15 Summer				
1.016	30 Winter	30	0%					
1.017	30 Winter	30	0%					
1.018	30 Winter	30	0%					
1.019	15 Winter	30	0%					

PN	US/MH Name	Water	Flooded			Pipe	Status	
		Level (m)	Surch'ed Depth (m)	Volume (m³)	Flow / Cap.	O'flow (l/s)		Flow (l/s)
1.000	Swale	123.854	-0.996	0.000	0.00	0.0	10.4	OK
1.001	Swale	123.817	-0.383	0.000	0.00	0.0	3.9	OK
1.002	Swale	123.269	-0.431	0.000	0.00	0.0	3.8	OK
1.003	Swale	122.490	-0.110	0.000	0.16	0.0	3.8	OK
1.004	B1- 5	122.060	-0.253	0.000	0.12	0.0	18.1	OK
2.000	SW MH	122.106	-0.249	0.000	0.24	0.0	29.9	OK
2.001	SW MH	122.058	-0.167	0.000	0.08	0.0	7.0	OK
1.005	B1- 6	122.057	-0.141	0.000	0.07	0.0	16.7	OK

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Water		Flooded		Pipe		Status
		Level (m)	Surch'd Depth (m)	Volume (m³)	Flow / Cap.	O'flow (l/s)	Flow (l/s)	
3.000	B1- 13	122.051	0.091	0.000	0.05	0.0	6.4	SURCHARGED
1.006	B1- 8	122.050	-0.098	0.000	0.11	0.0	16.8	OK
1.007	B1- 9	122.047	0.366	0.000	0.76	0.0	10.9	SURCHARGED
1.008	Ex MH	121.448	-0.077	0.000	0.48	0.0	10.9	OK
1.009	Ex MH	121.066	-0.159	0.000	0.19	0.0	10.9	OK
4.000	Ex MH 1113	123.206	1.474	29.366	2.39	0.0	86.9	FLOOD
5.000	Ex MH 1109	122.323	0.212	0.000	0.46	0.0	18.1	FLOOD RISK
4.001	Ex MH 1111	122.216	0.642	0.000	1.83	0.0	95.2	SURCHARGED
4.002	Ex MH 1110	122.079	0.535	0.000	1.04	0.0	98.9	SURCHARGED
6.000	Ex MH 1097	123.294	0.062	0.000	1.12	0.0	7.6	SURCHARGED
6.001	Ex MH 1115	122.985	-0.056	0.000	0.68	0.0	16.1	OK
6.002	Ex MH 1071	122.172	-0.003	0.000	0.69	0.0	14.9	OK
4.003	Ex MH 121.709	121.709	0.519	0.000	1.87	0.0	110.3	SURCHARGED
7.000	Ex MH 1112	122.427	0.245	0.000	1.06	0.0	87.9	SURCHARGED
7.001	Ex PI 121.357	121.357	-0.063	0.000	0.97	0.0	84.7	OK
4.004	Ex MH 120.960	120.960	-0.105	0.000	0.64	0.0	192.8	OK
4.005	Ex MH 120.901	120.901	-0.164	0.000	0.81	0.0	191.8	OK
4.006	100 (D) 120.765	120.765	-0.180	0.000	0.75	0.0	187.6	OK
4.007	101 (D) 120.553	120.553	-0.182	0.000	0.75	0.0	184.3	OK
8.000	Dummy 120.705	120.705	0.000	0.000	0.04	0.0	0.4	SURCHARGED*
9.000	237 123.685	123.685	-0.135	0.000	0.58	0.0	88.5	OK
9.001	238 122.956	122.956	-0.174	0.000	0.55	0.0	108.0	OK
9.002	239 122.668	122.668	-0.212	0.000	0.38	0.0	130.6	OK
10.000	240 122.375	122.375	0.620	0.000	0.63	0.0	125.7	SURCHARGED
9.003	241 122.240	122.240	0.750	0.000	0.88	0.0	301.5	SURCHARGED
9.004	242 122.058	122.058	0.848	0.000	0.90	0.0	283.9	SURCHARGED
8.001	243 121.876	121.876	0.621	0.000	0.55	0.0	309.3	SURCHARGED
11.000	229 122.346	122.346	0.316	0.000	0.38	0.0	34.7	SURCHARGED
11.001	230 122.241	122.241	0.591	0.000	0.50	0.0	98.2	SURCHARGED
11.002	231 122.083	122.083	0.583	0.000	0.60	0.0	199.6	SURCHARGED
11.003	235 121.970	121.970	0.795	0.000	0.42	0.0	206.7	SURCHARGED
12.000	Pond 121.737	121.737	0.097	0.000	0.00	0.0	3.1	SURCHARGED
8.002	243a (HB) 121.769	121.769	1.134	0.000	0.02	0.0	1.1	SURCHARGED
4.008	102 (D) 120.411	120.411	-0.164	0.000	0.77	0.0	183.4	OK
13.000	232 121.105	121.105	-0.205	0.000	0.01	0.0	1.6	OK
13.001	233 121.105	121.105	-0.095	0.000	0.01	0.0	5.1	OK
14.000	234a 121.444	121.444	-0.156	0.000	0.20	0.0	24.0	OK
13.002	234 (HB) 121.115	121.115	0.515	0.000	0.12	0.0	2.5	SURCHARGED
4.009	103 (D) 120.354	120.354	-0.101	0.000	0.63	0.0	179.3	OK
1.010	Ex MH 120.286	120.286	-0.029	0.000	0.85	0.0	178.2	OK
1.011	Ex MH 120.195	120.195	0.000	0.000	1.02	0.0	163.7	OK
1.012	Ex MH 120.037	120.037	-0.128	0.000	0.79	0.0	161.2	OK
1.013	Ex MH 119.957	119.957	-0.118	0.000	0.89	0.0	160.0	OK
1.014	104 (D) 119.929	119.929	-0.114	0.000	0.97	0.0	160.0	OK
1.015	105 (D) 119.692	119.692	-0.313	0.000	0.34	0.0	160.0	OK
15.000	200 123.207	123.207	-0.173	0.000	0.55	0.0	83.3	OK
16.000	201 124.200	124.200	0.160	0.000	1.32	0.0	25.1	SURCHARGED
16.001	202 123.651	123.651	-0.179	0.000	0.33	0.0	49.3	OK
15.001	203 122.871	122.871	-0.149	0.000	0.64	0.0	134.6	OK

15-17 Goldington Road
 Bedford
 Bedfordshire MK40 3NH



Date 08/04/2021 15:46
 File SW PH9 Proposed

Designed by a.tew
 Checked by

XP Solutions Network 2014.1.1

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Water		Flooded		Pipe		Status
		Level (m)	Surch'd Depth (m)	Volume (m³)	Flow / Cap.	O'flow (l/s)	Flow (l/s)	
17.000	204	122.835	-0.085	0.000	0.65	0.0	51.4	OK
15.002	205	122.756	0.026	0.000	1.08	0.0	219.1	SURCHARGED
15.003	206	122.414	-0.116	0.000	0.96	0.0	237.7	OK
18.000	207	123.163	-0.157	0.000	0.45	0.0	59.5	OK
15.004	208	122.280	-0.180	0.000	0.75	0.0	313.2	OK
15.005	209	122.031	-0.129	0.000	0.97	0.0	318.8	OK
15.006	210	121.708	-0.392	0.000	0.45	0.0	341.9	OK
19.000	211	122.895	0.085	0.000	1.29	0.0	17.6	SURCHARGED
19.001	212	122.568	-0.112	0.000	0.51	0.0	17.5	OK
19.002	213	122.452	-0.168	0.000	0.38	0.0	32.7	OK
19.003	214	122.156	-0.214	0.000	0.37	0.0	46.2	OK
19.004	215	121.678	-0.592	0.000	0.10	0.0	58.5	OK
19.005	216	121.550	-0.590	0.000	0.09	0.0	75.1	OK
15.007	217	121.440	-0.360	0.000	0.53	0.0	468.4	OK
20.000	218	122.010	-0.190	0.000	0.28	0.0	23.3	OK
20.001	219	121.815	-0.215	0.000	0.24	0.0	23.8	OK
20.002	220	121.801	-0.179	0.000	0.51	0.0	62.7	OK
20.003	221	121.476	-0.254	0.000	0.50	0.0	144.2	OK
15.008	222	121.249	-0.231	0.000	0.81	0.0	606.7	OK
21.000	223	123.506	-0.124	0.000	0.41	0.0	40.0	OK
21.001	223a	122.457	-0.113	0.000	0.49	0.0	53.3	OK
15.009	224	120.915	-0.295	0.000	0.67	0.0	673.2	OK
15.010	225	120.725	-0.045	0.000	0.04	0.0	37.9	OK
22.000	226	123.184	-0.086	0.000	0.83	0.0	82.6	OK
22.001	227	122.667	-0.233	0.000	0.30	0.0	114.3	OK
15.011	228	120.719	0.159	0.000	0.05	0.0	43.6	SURCHARGED
15.012	228a	120.718	0.311	0.000	0.05	0.0	44.3	SURCHARGED
23.000	244	123.275	-0.130	0.000	0.61	0.0	94.0	OK
23.001	245	122.908	0.063	0.000	1.41	0.0	93.2	SURCHARGED
23.002	246	122.634	-0.141	0.000	0.68	0.0	136.2	OK
23.003	247	122.298	0.293	0.000	1.56	0.0	168.8	SURCHARGED
23.004	248	121.646	-0.169	0.000	0.58	0.0	180.3	OK
15.013	249	120.717	0.457	0.000	0.07	0.0	55.4	SURCHARGED
15.014	250	120.717	0.497	0.000	0.06	0.0	55.8	SURCHARGED
24.000	251	123.276	-0.074	0.000	0.77	0.0	65.6	OK
24.001	252	122.589	-0.081	0.000	0.85	0.0	72.2	OK
24.002	253	122.311	-0.109	0.000	0.71	0.0	94.4	OK
24.003	254	121.872	-0.148	0.000	0.49	0.0	124.0	OK
15.015	255	120.717	0.547	0.000	0.06	0.0	62.8	SURCHARGED
15.016	256 (HB)	120.717	1.502	0.000	0.18	0.0	4.8	SURCHARGED
1.016	106 (D)	119.381	-0.114	0.000	0.87	0.0	160.6	OK
1.017	107 (D)	119.346	-0.109	0.000	0.99	0.0	160.6	OK
1.018	108 (PI)	119.051	-0.184	0.000	0.75	0.0	160.6	OK
1.019	109	119.018	-0.177	0.000	0.77	0.0	160.6	OK