



UNIT 1

PLANTING SCHEDULE				
Code	Species	Pot size (Ltr)	Plant density per m2	Total No.
TREES				
ACE	Acer campestre 'Elegant'	Air pot 10-12cm girth	-	2
BP	Betula pendula	Air pot 10-12cm girth	-	6
FS	Fagus sylvatica	Air pot 10-12cm girth	-	1
ME	Malus 'Evereste'	Air pot 10-12cm girth	-	2
PAP	Prunus avium 'Plena'	Air pot 10-12cm girth	-	1
SAS	Sorbus aucuparia 'Sheerwater Seedling'	Air pot 10-12cm girth	-	6
NATIVE SHRUB MIX				
CS	Cornus sanguinea 35%	Transplant 1+1 60-90 cm	2	40
EE	Euonymus europaeus 30%	Transplant 1+1 60-90 cm	2	40
PDI	Prunus domestica subsp. Italica 10%	1 yr old maiden 1-2m tall	1 tree per 4 m2	5
VO	Viburnum opulus 25%	Transplant 1+1 60-90 cm	2	40
NATIVE SHRUBS				
CSW	Calluna vulg. 'Springwood White'	2L	5	183
LAH	Lavandula ang. 'Hidcote'	2L	4	120
RO	Rosmarinus officinalis	3L	2	65
BULBS (IN THE GREEN) MIX				
EH	Eranthis hyemalis 50%	Bulb	15	135
GN	Galanthus nivalis 50%	Bulb in the green	15	135

UNIT 3

PLANTING SCHEDULE				
Code	Species	Pot size (Ltr)	Plant density per m2	Total No.
TREES				
ACE	Acer campestre 'Elegant'	Air pot 10-12cm girth	-	1
CJ	Cercidiphyllum japonicum	Air pot 10-12cm girth	-	5
FS	Fagus sylvatica	Air pot 10-12cm girth	-	1
LS	Liquidamber sylvatica	Air pot 10-12cm girth	-	5
PAP	Prunus avium 'Plena'	Air pot 10-12cm girth	-	2
NATIVE SHRUBS				
CAS	Cornus alba 'Sibirica'	3L	1	43
CSW	Calluna vulg. 'Springwood White'	2L	5	180
HA	Hypericum androsaemum	2L	2	17
LAH	Lavandula ang. 'Hidcote'	2L	4	150
RO	Rosmarinus officinalis	3L	2	86

All plants to be pot grown unless otherwise stated.

SCHEDULE OF DRY MEADOW MIX SPECIES (EMORSGATE SEED MIX EL1)

Herbs (represent 20% of the total weight)	% of total herbs	Grasses (represent 80% of the total weight)	% of total grasses
Galium verum Lady's bedstraw	3	Agrostis capillaris Common bent	8
Leontodon hispidus Rough hawkbit	0.5	Cynosurus cristatus Crested dog's tail	40
Leucanthemum vulgare Oxeye daisy	1	Festuca rubra Red fescue	28
Lotus corniculatus Bird's-foot trefoil	3	Phleum bertolonii Small cat's tail	4
Primula veris Cowslip	1.5		
Prunella vulgaris Selfheal	5		
Ranunculus acris Meadow buttercup	3		
Rumex acetosa Common sorrel	2		
Trifolium pratense Red clover	1		

SCHEDULE OF DAMP MEADOW MIX SPECIES (EMORSGATE SEED MIX EM8)

Herbs (represent 20% of the total weight)	% of total herbs	Grasses (represent 80% of the total weight)	% of total grasses
Achillea millefolium Yarrow	0.5	Agrostis capillaris Common bent	10
Achillea ptarmica Sneezewort	0.2	Alopecurus pratensis Meadow foxtail	4
Betonica officinalis Betony	1	Anthoxanthum odoratum Sweet vernal grass	1
Centaurea nigra Common knapweed	2.5	Briza media Quaking grass	1
Filipendula ulmaria Meadowsweet	2	Cynosurus cristatus Crested dog's tail	32
Galium verum Lady's bedstraw	1	Deschampsia cespitosa Tufted hairgrass	1
Geum rivale Water avens	0.5	Festuca rubra Red fescue	24
Leucanthemum vulgare Oxeye daisy	0.6	Hordeum secalinum Meadow barley	1
Lotus pedunculatus Greater birds' foot trefoil	0.8	Festuca pratensis Meadow fescue	6
Plantago lanceolata Ribwort plantain	1		
Primula veris Cowslip	0.2		
Prunella vulgaris Selfheal	1.5		
Ranunculus acris Meadow buttercup	2.5		
Rhinanthus minor Yellow rattle	1.5		
Rumex acetosa Common sorrel	1.5		
Sanguisorba officinalis Great burnet	1		
Silene flos-cuculi Ragged robin	0.2		
Vicia cracca Tufted vetch	1.5		

No dimensions are to be scaled from this drawing. All stated measurements are to be verified on site. Any discrepancies to be brought to the attention of Open Spaces.

- Proposed Tree
- Proposed Native Shrub Planting
- Proposed Emorsgate Flowering Lawn Mix EL1 (Dry Meadow Grassland)
- Proposed Emorsgate Meadow Mix EM8 (Damp Meadow Grassland)
- Proposed Native Shrub Mix
- Proposed Bulb Planting
- Extent of current application (Plot 1&3)
- Plot boundary line

Note: This drawing is to be read in conjunction with the Soft Landscape Specification document.

Rev	Date	Description	Rev by

Client
Oxford Technology Park
Land East of Evenlode Crescent and South of Langford Lane, Kidlington

Drawing Title
Soft Landscape Plan
Unit 1 and Unit 3

Date: 03/03/2021 Drawn: SS

Scale: 1:200 on A1 Checked: KM

Dwg No: OS 1346-16.4 Rev: -

Open Spaces
Landscape Architects
LANDSCAPE ARCHITECTURE - TREES - ECOLOGY
2 Monument Offices, Hall Farm, Maldon Road
Woodham Mortimer, Essex CM9 6SN
Tel: 01277 356511 os@open-spaces.co.uk
www.open-spaces.co.uk

