



| PLANTING SCHEDULE    |                                  |                       |                      |           |
|----------------------|----------------------------------|-----------------------|----------------------|-----------|
| Code                 | Species                          | Pot size (Ltr)        | Plant density per m2 | Total No. |
| <b>TREES</b>         |                                  |                       |                      |           |
| ACE                  | Acer campestre 'Elegant'         | Air pot 10-12cm girth | -                    | 1         |
| CJ                   | Cercidiphyllum japonicum         | Air pot 10-12cm girth | -                    | 5         |
| FS                   | Fagus sylvatica                  | Air pot 10-12cm girth | -                    | 1         |
| LS                   | Liquidamber sylvatica            | Air pot 10-12cm girth | -                    | 5         |
| PAP                  | Prunus avium 'Plena'             | Air pot 10-12cm girth | -                    | 2         |
| <b>NATIVE SHRUBS</b> |                                  |                       |                      |           |
| CAS                  | Cornus alba 'Sibirica'           | 3L                    | 1                    | 43        |
| CSW                  | Calluna vulg. 'Springwood White' | 2L                    | 5                    | 180       |
| HA                   | Hypericum androsaemum            | 2L                    | 2                    | 17        |
| LAH                  | Lavandula ang. 'Hidcote'         | 2L                    | 4                    | 150       |
| RO                   | Rosmarinus officinalis           | 3L                    | 2                    | 86        |

All plants to be pot grown unless otherwise stated.

**SCHEDULE OF DRY MEADOW MIX SPECIES (EMORSGATE SEED MIX EL1)**

| Herbs (represent 20% of the total weight)     |     | % of total herbs | Grasses (represent 80% of the total weight)   |    | % of total grasses |
|---|-----|------------------|---|----|--------------------|
| <i>Galium verum</i> Lady's bedstraw           | 3   |                  | <i>Agrostis capillaris</i> Common bent        | 8  |                    |
| <i>Leontodon hispidus</i> Rough hawkbit       | 0.5 |                  | <i>Cynosurus cristatus</i> Crested dog's tail | 40 |                    |
| <i>Leucanthemum vulgare</i> Oxeye daisy       | 1   |                  | <i>Festuca rubra</i> Red fescue               | 28 |                    |
| <i>Lotus corniculatus</i> Bird's-foot trefoil | 3   |                  | <i>Phleum bertolonii</i> Small cat's tail     | 4  |                    |
| <i>Primula veris</i> Cowslip                  | 1.5 |                  |   |    |                    |
| <i>Prunella vulgaris</i> Selfheal             | 5   |                  |   |    |                    |
| <i>Ranunculus acris</i> Meadow buttercup      | 3   |                  |   |    |                    |
| <i>Rumex acetosa</i> Common sorrel            | 2   |                  |   |    |                    |
| <i>Trifolium pratense</i> Red clover          | 1   |                  |   |    |                    |

No dimensions are to be scaled from this drawing. All stated measurements are to be verified on site. Any discrepancies to be brought to the attention of Open Spaces.

|  |  |
|--|--|
|  | Proposed Tree  |
|  | Proposed Emorsgate Flowering Lawn Mix EL1 (Dry Meadow Grassland) |
|  | Proposed Native Shrub Planting                                   |
|  | Extent of current application (Plot 1&3)                         |
|  | Plot boundary line   |

Note: This drawing is to be read in conjunction with the Soft Landscape Specification document.

| Rev | Date | Description | Rev by |
|-----|------|-------------|--------|
|     |      |             |        |
|     |      |             |        |
|     |      |             |        |

Client

Project  
Oxford Technology Park  
Land East of Evenlode Crescent and South of Langford Lane, Kidlington

|                               |              |             |
|-------------------------------|--------------|-------------|
| Drawing Title                 |              |             |
| Soft Landscape Plan<br>Unit 3 |              |             |
| Date:                         | 03/03/2021   | Drawn: SS   |
| Scale:                        | 1:200 on A1  | Checked: KM |
| Dwg No:                       | OS 1346-16.3 | Rev: -      |

**Open Spaces**  
Landscape Architects  
LANDSCAPE ARCHITECTURE – TREES – ECOLOGY  
2 Monument Offices, Hall Farm, Maldon Road  
Woodham Mortimer, Essex CM9 6SN  
Tel: 01277 356511 os@open-spaces.co.uk  
www.open-spaces.co.uk