



*Note: Where building over or near to ( within 3m) existing public drains an agreement with Thames Water will need to be obtained*



**FOUNDATIONS:**  
Foundations in C20 mix concrete, in trench fill type footings, minimum width 450mm ( 600mm shown). Minimum foundation depth 1.000m (or to the approval of the local authority building inspector and dependant upon ground conditions). Notwithstanding the representation on the drawings, foundations to comply with Building Regulations in all respects.



*Note: All structural work to be carried out in accordance with all current Health and Safety regulations. Contractor to ensure adequate temporary propping is in place before attempting to carry out work on any structural element.*

Rev.	Date	Revisions
<div><p><b><i>Steve Karpa</i></b></p><p><b>Architectural Detailing</b></p><p>15 Taylor Close, Bicester, Oxon, OX26 3HS Tel/Fax: 01869 322671    Mobile: 07905261592 stevekarpa@hotmail.com</p></div>		
Client: <b>YASAMIN KAZEMI</b>		
Job Title: PROPOSED EXTENSION AT: 1 HORNE CLOSE, CAVERSFIELD, OXON.		
Drawing Title:  <b>SECTION</b>		
Scale: 1:50, 1:20 @ A3	Date: February 2021	Drawn: SJK
Drawing Number:		<b>SK.21-877-08</b>