

External Materials Key
To Be Read In Accordance with Client Materials Schedule

- Recessed brick panel 
- Brickwork - Buff Brick 
- Brickwork - Buff Brick Feature 'Burglar Bond' 
- Brickwork - Grey contrasting Brick 
- Back painted Structural glass panel 
- Roof tiles Marley 'Rivendale' Blue Black or similar approved
- Rainwater goods - Black
- IG door sets - Grey
- Upvc Windows - Grey



FRONT ELEVATION [NORTH]



SIDE ELEVATION [EAST]

<ul style="list-style-type: none"> - Statutory approvals to be received prior to commencement of works. - Building control submission to be deposited prior to any works. - Check / trace positions of existing services / drainage prior to new works. - Ensure no Easements / rights of way exist on site prior to construction. - Do NOT scale from this drawing. Check dimensions on site against site survey prior to any new works. Report and resolve any discrepancies prior to any new building works. - Relevant Party Wall notices to be served and agreed before new works. - CDM Co-ordinator to be appointed with Health & Safety file in place prior to any new works. 			A1 SHEET
Revision:	Date:	Description:	By:
P1	13.02.21	Preliminary Issue	MJR

1:50
0 1m 2m 3m 4m

Client:



Trower Davies
Architectural Consultants

Site Address:
UPPER HEYFORD, PHASE 9A
BICESTER

Drawing Title:
APARTMENT BLOCK SPF6 - 500-508
ELEVATIONS

Scale: 1:50 @ A1	Date drawn: FEB 21	Drawn by: MJR
Project Number: 727	Drawing Number: SPF6-P04	Revision: P1

Status:
P L A N N I N G