

BRITANNIA

JOINERY Limited

Britannia Joinery Limited.
Tramway Road, Banbury,
Oxfordshire. OX16 5TD

Tel / Fax : 01295 250623

Email : enquiries@britanniajoinery.co.uk

Web : www.britanniajoinery.co.uk



QUOTATION

Reference The Old Bakery, Bodicote
Quotation Number Q0566
Date of Quotation 18 May 2021
Validity 30 days

To Supply Only

Dear Mr & Mrs Nash

Thank you for your enquiry, Below is a detailed specification to supply your project.
If required Britannia Joinery can take site measurements prior to manufacture.
All of our joinery is manufactured at our factory using traditional Mortise & Tenon Joints


N.B Price does not include site fixing.

Item (sizes)	Description	Qty	Unit Cost	Total Cost
--------------	-------------	-----	-----------	------------

Casement Window - (W1)

Window type: Traditional Britannia Heritage Flush window to include Aquamac 21 draught excluders
Timber Type : Red Grandis
Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge
87.22 kgs

1



Casement

Ironmongery type : Stormproof Hinges - Kirkpatrick 1167 fasteners and 1180 Stays
Timber Type : Red Grandis
Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge

Carried Forward




Item (sizes)	Description	Qty	Unit Cost	Total Cost
--------------	-------------	-----	-----------	------------

Brought Forward

Casement Window - (W2)

Window type: Traditional Britannia Heritage Flush window to include Aquamac 21 draught excluders
 Timber Type : Red Grandis
 Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge
 87.22 kgs

1




Casement

Ironmongery type : Stormproof Hinges - Kirkpatrick 1167 fasteners and 1180 Stays
 Timber Type : Red Grandis
 Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge

Casement Window - (W3)

Window type: Traditional Britannia Heritage Flush window to include Aquamac 21 draught excluders
 Timber Type : Red Grandis
 Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge
 87.22 kgs

1




Casement

Ironmongery type : Stormproof Hinges - Kirkpatrick 1167 fasteners and 1180 Stays
 Timber Type : Red Grandis
 Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge

Casement Window - (W4)

Window type: Traditional Britannia Heritage Flush window to include Aquamac 21 draught excluders
 Timber Type : Red Grandis
 Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge
 87.22 kgs

1



Casement

Ironmongery type : Stormproof Hinges - Kirkpatrick 1167 fasteners and 1180 Stays
 Timber Type : Red Grandis
 Glass : Heritage 12mm 4/4/4 Clear Leaded DG Units (Krypton) Warm edge

Teknos Factory Spraying: All joinery to be end grain sealed using Teknos TS0050 end grain sealer with a coat of Teknos 2901 anti stain primer and 2 coats Teknos 2600 microporous top coat. All Boarded and Panelled doors to be individually decorated prior to assembly. - TKNS



VAT @ 20%

Total



Total Weight 348.86 kgs

NOTES:

Diagrams of windows, doors and frames indicate style viewed from the outside and do not reflect size. All weights shown on this document are approximate and are intended to assist in manual handling considerations.

The colours shown are for presentation only and do not reflect the true finish colour of your timber or Joinery item.

Please note prices for individual items may vary if other items are omitted or added to the quotation. All double glazed units with sightlines 7mm to 11mm have a manufacturers gauranteed for 2 years against a breakdown.

If this is the case a new unit will be supplied FOC.

Assuring you of our best attention at all times and looking forward to your further instructions.

For and on behalf of
Britannia Joinery Limited
G. Johnson

All goods are supplied to the company`s standard conditions of Sale.

vat number 387 6481 00

Company No 07896681