



FRONT ELEVATION

SIDE ELEVATION




REAR ELEVATION

SIDE ELEVATION



GROUND FLOOR PLAN

50sq.m.



FIRST FLOOR PLAN

57sq.m.

NOTES:
DIMENSIONS ARE NOT TO BE SCALED FROM THIS DRAWING
ALL DIMENSIONS ARE TO BE CHECKED AGAINST ACTUAL SIZE
DIMENSIONS BEFORE ANY WORK IS FABRICATED

COPYRIGHT RESERVED
THIS DRAWING IS THE PROPERTY OF BHP HARWOOD
ARCHITECTS AND MAY NOT BE COPIED, REPRODUCED, LENT OR
DISCLOSED WITHOUT THEIR EXPRESS PERMISSION IN WRITING.

REVISIONS

Rev.	Date	Description

M4(2) Checklist

Entrance

- Canopy at level entrance 900mm wide and 600mm deep.
- Dusk to dawn timer or motion detection lighting adjacent to entrance.
- Entrance door minimum 850mm clear opening.
- If a porch is included it must allow 1,500mm between the two door swings.

Circulation

- Minimum nib of 300mm to the leading edge of doors (entrance storey only).
- Step free to all rooms within entrance storey.
- 900mm unobstructed corridor widths.
- Living area to be included on entrance storey (living room, dining room or kitchen/dining).
- Stairs 850mm clear width.
- 1200mm minimum clear space in front of kitchen units and appliances.
- 850mm maximum to glazing of principal window in living room.

Bedrooms

- Main double bedroom to have 750mm clear zone to both sides and foot of bed (2m x 1.5m bed).
- Other double beds to have 750mm clear zone to one side and foot of bed (1.9m x 1.350m bed).
- Single beds and twins to have 750mm clear zone to one side of each bed (1.9m x 0.9m bed).
- All bedrooms to have clear access route 750mm from windows and doors.

Sanitary Facilities

- For 1 or 2 bedroom houses, WC within entrance storey 1600mm x 850mm or 1050mm x 1,500mm.
- For 3 bedroom and houses, WC within entrance storey capable of taking a future level access shower, 1,450mm x 1,800mm room size.
- WC doors to open outwards.

Bathrooms

- Every dwelling to have a bathroom including WC, basin and bath on the same floor as the main double bedroom.
- 1,100mm x 700mm clear access zones in front of WC and basin and to the side of a bath.
- Provision for future level access shower within the bathroom (1 or 2 bed houses).

Client :
GADE HOMES

Job :
SIBFORD FERRIS
BANBURY

Drawing Title:
Plots 1 & 2
Proposed Plans and
Elevations

Scale:
1:100 @ A1

Date: Jan 2022
Drawn By: MM
Checked: MM

Drawing No: 3699.102
Revision: H

PLANNING

The White Barn, Manor Farm, Manor Road
Wantage, Oxfordshire, OX12 8NE
T: 01235 765322 F: 01235 765373

The Mansion House, Hartham Park, Corsham,
Wiltshire, SN13 0RP
T: 01249 700489 F: 01249 470077

info@bpharwood.co.uk - www.bpharwood.co.uk

