



Tree care

- Trees should be single vertically staked for their first five years, and longer until the tree is sufficiently self-stable. Tree stake with 1.2m stake, 75mm Ø spacer, secured softwood stake, secured with adjustable bio-degradable rubber belt with spacers, secured approx. 100mm below the top of the stake.
- Trees should be protected against rabbits and deer using open-mesh guards - 60cm square polypropylene open mesh tree-guard and two nylon adjustable cable ties.
- A 1m circle of clear ground with 50-75mm bark mulch layer around the base of the tree to allow it to establish properly and maintained as a permanent feature.

	A	Update to Client and LPA comments	16/02/22	LP/VR	Scale	By/Chk	Date
					1:200@A1	VR/LP	04/08/21
	Rev	Description	Date	By/Chk	Drawing Number		Revision
					A318_PP02		A