

MH REF	CL	IL	DEPTH	DIA	OPENING	COVER	COMMENTS
F1	84.000	79.950	4.050	1050	600x600	D400	
F8	83.800	80.575	3.225	1050	600x600	D400	
F9	83.800	80.875	2.925	1050	600x600	D400	
F10	83.800	81.300	2.500	1050	600x600	D400	
F11	83.800	81.475	2.325	1050	600x600	D400	
F12	83.800	81.925	1.875	1050	600x600	D400	
F13	83.800	82.200	1.600	1050	600x600	D400	
F14	83.700	82.425	1.275	1050	600x600	D400	
F15	84.000	82.775	1.225	1050	600x600	D400	
F16	84.000	83.200	800	450	450x450	D400	450 Dia. PPHC 150mm Concrete Encased
F17	84.000	82.700	1.300	450	450x450	D400	450 Dia. PPHC 150mm Concrete Encased
F18	84.000	83.000	1000	450	450x450	D400	450 Dia. PPHC 150mm Concrete Encased
F19	83.400	82.400	1000	1050	600x600	D400	
F20	83.700	82.050	1680	1050	600x600	D400	
F21	84.000	82.600	1400	1050	600x600	D400	
F22	83.950	83.200	750	450	450x450	D400	450 Dia. PPHC 150mm Concrete Encased
F23	83.700	82.000	1700	1050	600x600	D400	
F24	84.000	82.600	1400	1050	600x600	D400	
F25	84.075	83.200	875	450	450x450	D400	450 Dia. PPHC 150mm Concrete Encased


Schedule of approximate areas	UNIT	Ground Floor GFA sqm	Ground Floor GFA sq ft	First Floor GFA sqm	First Floor GFA sq ft	Second Floor GFA sqm	Second Floor GFA sq ft	Total Unit GFA sqm	Total Unit GFA sq ft
1		1759	18934	195	2104	0	0	1954	21038
2		1613	17382	179	1929	0	0	1792	19291
3		1650	17761	183	1973	0	0	1833	19734
4		4278	46048	238	2558	238	2568	4733	51165
5		3433	36953	423	4553	0	0	3856	41506
TOTAL		12733	137038	1219	13118	238	2538	14189	152734

NOTE: ESTIMATED PEAK FLOW FROM PHASE 3 Units 1-5 = 2.3 L/S (Max)

NOTE: ALL DISCHARGE IS THROUGH GRAVITY FLOW INTO PUBLIC SEWER

NOTE: FOWL DISCHARGE IS SUBJECT TO TW AGREEMENT

FOUL WATER ASSESSMENT		
Units 1-5	Ground Floor	= 12,733m ²
	1st & 2nd Floor Offices	= 1,457m ²
DWF	12,733 x 150 L/D	= 19,100 L/D
	100	
	1457 x 750 L/D	= 10,928 L/D
	100	
PEAK FLOW	30,028 x 6 x 1.1	= 30,028 L/D
	24 x 60 x 60	
		= 2.3 L/S



Application Boundary

Other Land in Control of the Applicant

Phase 3 FW Drainage Layout 1:1000

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND BAILEY JOHNSON HAYES DRAWINGS AND SPECIFICATIONS.
- DRAINS TO BE HEPPWORTH SUPERSEWER, LAND IN CLASS S BEDDING TO BS 882:1983; TABLE 4, OR TO BS 5301:1984; APPENDIX D, 450 DIA DRAINS AND ABOVE TO BE HEPPWORTH CONCRETE PIPES CLASS H, OR EQUAL APPROVED DRAINS WITHIN THE SITE MAY BE THERMOPLASTIC STRUCTURED WALL PIPE IN ACCORDANCE WITH CLAUSE E2.22 OF SFA 8th EDITION
- ALL TRENCHES WITHIN TRAFFICKED AREAS TO BE BACKFILLED WITH 75 MM DOWN GRADED STONE FILL, PLACED AND COMPACTED IN 150 MM LAYERS. ALL PIPES IN ROADWAYS, SERVICE YARDS AND CARPARKS LESS THAN 1200 MM DEEP TO BE ENCASED IN CONCRETE. PROVIDE FLEXIBLE JOINTS AT 3 METRE CENTRES.
- MANHOLES TO BE CONSTRUCTED IN PRECAST CONCRETE RINGS TO BS 5911: PART 1. RINGS TO BE BEDDED IN SEALANT STRIPS.
- MANHOLES IN FOOTPATHS OR LANDSCAPED AREAS TO BE CONSTRUCTED IN LAYERS NOT EXCEEDING 150 MM THICK. MANHOLES BENEATH ROADS AND PARKING AREAS TO BE CASSED IN 150 MM CONCRETE SURROUND.
- ALL CONNECTIONS TO RAIN WATER PIPES TO BE PROVIDED WITH RODDING ACCESS.
- ALL ROAD GULLIES TO BE HEPPWORTH ROAD GULLIES, REF RGR4 WITH 150 MM DIAMETER OUTLETS. GULLIES TO BE ENCASED IN 150 MM MINIMUM CONCRETE.
- DRAINS UNDER BUILDING AND WITHIN 300 MM OF THE UNDERSIDE OF FLOOR SLABS TO BE ENCASED IN 150 MM CONCRETE. ALL DRAINS UNDER BUILDINGS TO BE MANUFACTURER DRAINS UNDER BUILDINGS GENERALLY TO HAVE MIN 100 FULL GRANULAR SURROUND TO CLASS S BS8301
- WHERE PIPES RUN THROUGH GROUND BEAMS, FLEXIBLE JOINT CASINGS AT EACH FACE OF THE GROUND BEAM ARE TO BE PROVIDED. PIPES WHICH RUN UNDER GROUND BEAMS TO BE MANUFACTURER DRAINS UNDER BUILDINGS. FLEXIBLE JOINTS TO BE OVER THE CROWN OF THE PIPE.
- WHERE PIPES RUN THROUGH GROUND BEAMS, FLEXIBLE JOINT CASINGS AT EACH FACE OF THE GROUND BEAM ARE TO BE PROVIDED. PIPES WHICH RUN UNDER GROUND BEAMS TO BE MANUFACTURER DRAINS UNDER BUILDINGS. FLEXIBLE JOINTS TO BE OVER THE CROWN OF THE PIPE.
- ALL WORK TO EXISTING PUBLIC SEWERS TO BE IN ACCORDANCE WITH SEWERS FOR ADOPTION 8TH EDITION AND BS 8301: CODE OF PRACTICE FOR BUILDING DRAINAGE
- WHERE DRAINS RUN CLOSE TO BUILDINGS AND INVERT LEVELS ARE BELOW FOUNDATIONS THE DRAINS SHOULD BE ENCASED AS FOLLOWS:-
 - WHERE THE DRAIN TRENCH IS WITHIN 1M3 OF THE BUILDING FOUNDATION FORMATION LEVEL, OR
 - WHERE THE DRAIN TRENCH IS FURTHER THAN 1M OF THE BUILDING FOUNDATION FORMATION LEVEL TO BE FILLED WITH CONCRETE TO A LEVEL BELOW FOUNDATION FORMATION EQUAL TO THE DISTANCE FROM THE BUILDING LESS 150mm.

KEY:

- INDICATES GULLIES
- INDICATES FOWL WATER MANHOLES
- INDICATES NEW PIPE RUNS
- INDICATES EXISTING MANHOLES

ALL PIPES CONNECTED DIRECTLY INTO GULLIES TO BE 150MM DIAMETER

TOWN PLANNING

Rev	DATE	Revision Description
A	20.07.21	Updated Ditches, Mounds & SLR

Project Title
Axis J9 - Bicester



Drawing Title
**PHASE 3
FW Drainage Layout**

BAILEY JOHNSON HAYES
Consulting Engineers

ST ALBANS - Suit 4, Phoenix House, 63 Cornhill Rd, ST ALBANS, Herts, AL1 5PL
MANCHESTER - George House, 240 Oxford Street, MANCHESTER, M2 6DY

Scale: 1:1000 @A1
Date: 23.06.21
Drawing Number: S1209-PH3-03 F
Drawn: JNG