

DRAINAGE NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND BAILEY JOHNSON HAYES DRAWINGS AND SPECIFICATIONS.
- DRAINS TO BE HEPMORTH SUPERSEWER LINED IN CLASS S APPENDIX D 450 DIA DRAINS AND ABOVE TO BE HEPMORTH CONCRETE PIPES CLASS H, OR EQUAL APPROVED DRAINS WITHIN THE SITE MAY BE THERMOPLASTIC STRUCTURED WALL PIPE IN ACCORDANCE WITH CLAUSE E2.22 OF SFA 8th ED.
- ALL TRENCHES WITHIN TRAFFICABLE AREAS TO BE BACKFILLED WITH 75 MM DOWN GRADED STONE FILL, PLACED AND COMPACTED IN 150 MM LAYERS. ALL PIPES IN ROADWAYS, SERVICE YARDS AND CARPARKS LESS THAN 1200 MM DEEP TO BE ENCASED IN CONCRETE. PROVIDE FLEXIBLE JOINTS AT 3 METRE CENTRES.
- MANHOLES TO BE CONSTRUCTED IN PRECAST CONCRETE RINGS TO BS 5911: PART 1. RINGS TO BE BEDDED IN SEALANT STRIPS.
- MANHOLES IN FOOTPATHS OR LANDSCAPED AREAS TO BE BACKFILLED WITH 40 MM DOWN GRADED STONE FILL, PLACED AND COMPACTED IN 150 MM LAYERS. ALL PIPES IN ROADWAYS, MANHOLES BENEATH ROADS AND PARKING AREAS TO BE ENCASED IN 150 MM CONCRETE SURROUND.
- ALL CONNECTIONS TO RAIN WATER PIPES TO BE PROVIDED WITH RODDING ACCESS.
- ALL ROAD GULLIES TO BE HEPMORTH ROAD GULLIES, REF RGR4, WITH 150 MM DIAMETER OUTLETS. GULLIES TO BE ENCASED IN 150 MM MINIMUM CONCRETE.
- DRAINS UNDER BUILDING AND WITHIN 300 MM OF THE UNDERSIDE OF FLOORS/SLAB TO BE ENCASED IN 150 MM CONCRETE. DRAINS UNDER ROADS AND DRIVEWAYS TO BE ENCASED IN 150 MM CONCRETE. ALL PIPES TO BE ENCASED IN 150 MM CONCRETE. ALL PIPES TO BE ENCASED IN 150 MM CONCRETE. ALL PIPES TO BE ENCASED IN 150 MM CONCRETE.
- WHERE PIPES RUN THROUGH GROUND BEAMS, FLEXIBLE JOINT CASINGS AT EACH FACE OF THE GROUND BEAM ARE TO BE PROVIDED. PIPES WHICH RUN UNDER GROUND BEAMS TO BE PROTECTED WITH 50 MM MINIMUM POLYSTYRENE PLACED OVER THE CROWN OF THE PIPE.
- ALL WORK TO EXISTING PUBLIC SEWERS TO BE IN ACCORDANCE WITH SEWERS FOR ADOPTION 8TH EDITION AND BS 8301 : CODE OF PRACTICE FOR BUILDING DRAINAGE
- WHERE DRAINS RUN CLOSE TO BUILDINGS AND INVERT LEVELS ARE BELOW FOUNDATIONS THE DRAINS SHOULD BE ENCASED AS FOLLOWS:-
 - WHERE THE DRAIN TRENCH IS WITHIN 1M OF THE BUILDING THE TRENCH SHOULD BE FILLED WITH CONCRETE UP TO FOUNDATION FORMATION LEVEL, or
 - WHERE THE DRAIN TRENCH IS FURTHER THAN 1M OF THE BUILDING THE TRENCH SHOULD BE FILLED WITH CONCRETE TO A LEVEL BELOW FOUNDATION FORMATION EQUAL TO THE DISTANCE FROM THE BUILDING LESS 150mm.

- KEY:
- INDICATES SURFACE WATER MANHOLES
 - INDICATES SW PIPE RUNS
 - INDICATES FOLL WATER MANHOLES
 - INDICATES FW PIPE RUNS

Rev	Date	Revision Description

Project Title
Junction 10 - M40






ENABLING WORKS
Infiltration Basin Details

BAILEY JOHNSON HAYES
Consulting Engineers

ST ALBANS: Suite 4, Phoenix House, 63 Cornwell Rd, ST ALBANS, Herts AL1 5PL
MANCHESTER: George House, 200 Dalton Street, MANCHESTER, M2 6JY

Scale	1:500, 100 @A1	Drawing Number	S1299-P-04
Date	17.09.21	Drawn	JNG



BAILEY JOHNSON HAYES
Consulting Engineers

ST ALBANS: Suite 4, Phoenix House, 63 Cornwell Rd, ST ALBANS, Herts AL1 5PL
MANCHESTER: George House, 200 Dalton Street, MANCHESTER, M2 6JY

Scale	1:500, 100 @A1	Drawing Number	S1299-P-04
Date	17.09.21	Drawn	JNG