



Our ref: 11461Dougall

Notice of intended tree work in the CA of Sibford Ferris

Address: 10 Walford Road, Sibford Ferris, Banbury, OX15 5BL

Works Specification:

- 1. Sycamore**
Reduce south facing crown spread over junction and close by up to 2.5 metres in circumference
Reduce west facing crown spread adjacent to property to previous
Reduce remaining circumference to north and east proportionately to balance symmetry
Remove major deadwood
- 2. Beech** - Compression fork with included bark with the possible formation of a longitudinal crack
Reduce stem to east by approximately 4.5 metres
Reduce lateral spread of crown to east by up to 3 metres in branch length
Reduce overall crown height by up to 2 metres
Prune remaining crown circumference proportionately to contain and shape
Install x1 GEFA crown support system (brace) between stems to west and east
- 3. Ash** - Section fell to leave the remaining stump cut as close to ground level as situation allows
- 4. Beech**
Remove lower smaller diameter stem overhanging adjacent Cherry
Prune south facing section of crown overhanging property by up to 2 metres in branch length
Reduce and balance north facing side of crown by up to 3 metres in branch length
Prune to shape
- 5. Cherry**
Prune extending branch ends to contain and improve shape



Site/tree location plan

