

| Date | Site: Upper Heyford | | | | | | | | | | | | Surveyor: PC/DP/MP/ | | | Client: | Dorchester | | | | | | | | | | Job no: D.0340 | |
|------------|---------------------|--------|----------|----------|----------|--------|----------|-----|----------|---|----------|------------------------|---------------------|------------|----------|----------------------|------------|---|----------------------|---|--------|-----------------|------------|----------|--------|----------|----------------|--|
| Ref number | Species | Height | Estimate | Stem dia | Estimate | Spread | | | | | | Crown clearance height | | | | | Life stage | General observations Physiological and structural condition. Preliminary management recommendations | Structural Condition | Physiological Condition | ULE | Quality grading | RPA radius | RPA area | | | | |
| | | | | | | N | Estimate | S | Estimate | E | Estimate | W | Estimate | 1st branch | Estimate | 1st branch direction | | | | | | | | | Canopy | Estimate | | |
| T1 | Beech (Common) | 4.5 | - | 100 | - | 1.5 | - | 1.5 | - | 2 | - | 1.5 | - | 1.5 | - | East | 1.5 | - | SM | Minor bark damage lower trunk. Centre of raised roundabout. | High | Low | 20+ | C1 | 4.8 | 72.4 | | |
| T2 | Lilac | 4 | - | 219 | - | 3 | - | 2.5 | - | 3 | - | 2 | - | 1.5 | - | North | 2 | - | OM | Bark damage, weak fork at 1.5m. | Medium | Low | 10+ | C1 | 2.6 | 21.8 | | |
| T3 | Laburnam | 11 | - | 480 | - | 4 | - | 2 | - | 4 | - | 3 | - | 1.5 | - | East | 3 | - | OM | Minor deadwood upper canopy. Suppressed to south. | Low | Medium | 10+ | C1 | 5.8 | 104.2 | | |
| T4 | Laburnam | 10 | - | 290 | - | 2 | - | 1 | - | 5 | - | 2 | - | 1.8 | - | North | 3 | - | M | Weak fork at 1m. Suppressed to south. | Low | Medium | 10+ | C1 | 3.5 | 38.1 | | |
| T5 | Laburnam | 10 | - | 580 | - | 6 | - | 3 | - | 4 | - | 4.5 | - | N/A | - | N/A | 4 | - | OM | Historically pollarded at 1.5m. Major limbs to south dead, adjacent footpath. | Low | Low | <10 | U | 7.0 | 152.2 | | |
| T6 | Laburnam | 10 | - | 400 | - | 3.5 | - | 2 | - | 7 | - | 2 | - | 1.5 | - | East | 2 | - | OM | Lean to east. Exposed damaged roots to west. Adjacent to concrete path. Pruning wounds, partial occlusion. | Medium | Medium | 10+ | C1 | 4.8 | 72.4 | | |
| T7 | Birch (Silver) | 12 | - | 270 | - | 3 | - | 2 | - | 3 | - | 2 | - | N/A | - | N/A | 2.5 | - | M | Exposed heartwood 1m south. Lean to north. Suppressed to south. | Medium | Medium | 10+ | C1 | 3.2 | 33.0 | | |
| T8 | Laburnam | 10 | - | 380 | - | 6 | - | 2 | - | 4 | - | 3 | - | 1.5 | - | East | 2 | - | M | Exposed roots at base. Exposed heartwood at base on north side. Weak forks at 1.5m. | Medium | Medium | 10+ | C1 | 4.6 | 65.3 | | |
| T9 | Cherry (Wild) | 12 | - | 400 | - | 5 | - | 3 | - | 7 | - | 3 | - | 2.5 | - | South east | 3.5 | - | OM | Exposed damaged roots. Decay at main fork at 2m. Longitudinal split on western limb. Gummosis. Ripped off limb | Low | Low | <10 | U | 4.8 | 72.4 | | |
| G10 | Lilac | 4 | - | 100 | - | 0.5 | - | 3.5 | - | 3 | - | 3 | - | N/A | - | N/A | 1.5 | - | M | Suppressed to north. Decay in stems. | Low | Low | <10 | U | 1.2 | 4.5 | | |
| G11 | Laburnam | 8 | - | 440 | - | 4.5 | - | 2.5 | - | 3 | - | 3 | - | N/A | - | N/A | 1.5 | - | OM | Three trees adjacent footpath. Middle tree leans to north. All Fork at 1.5m. Eastern tree bark damage with decay. | Low | Medium | 10+ | C2 | 5.3 | 87.6 | | |
| G12 | Birch (Silver) | 14 | - | 380 | - | 5 | - | 7 | - | 5 | - | 5 | - | N/A | - | N/A | 1.5 | - | M | Minor amounts of minor deadwood. Adjacent footpath. 7 trees. | Medium | Medium | 10+ | C2 | 4.6 | 65.3 | | |
| G13 | Birch (Silver) | 14 | - | 380 | - | 5 | - | 7 | - | 5 | - | 5 | - | 0 | - | - | 1.5 | - | M | Minor ivy on western tree. Cavities observed throughout, associated with pruning wounds. | Medium | Medium | 10+ | C2 | 4.6 | 65.3 | | |
| H14 | Privet | 1 | - | 50 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Managed privet hedge with Hawthorn and ivy. Sycamore, elder also observed. | - | - | - | - | 0.6 | 1.1 | | |
| T15 | Birch (Silver) | 15 | - | 510 | - | 7 | - | 6 | - | 7 | - | 5 | - | N/A | - | N/A | 2 | - | M | Minor pruning wounds observed. Several holes with slugs. Pruning wounds with associated decay, points of entry for | Medium | Medium | 10+ | C1 | 6.1 | 117.7 | | |
| T16 | Birch (Silver) | 12 | - | 350 | - | 3 | - | 4 | - | 3 | - | 5 | - | 3 | - | South west | 1.5 | - | M | Weak fork at 3m. Good form. Minor bark damage. | Medium | Medium | 20+ | B1 | 4.2 | 55.4 | | |
| G17 | Birch (Silver) | 12 | - | 400 | - | 6 | - | 7 | - | 5 | - | 5 | - | N/A | - | N/A | 0.5 | - | M | Three trees. Middle tree has blunt nosed ribs observed, indication of internal cracks. | Medium | Medium | 20+ | B2 | 4.8 | 72.4 | | |
| T18 | Birch (Silver) | 10 | - | 420 | - | 5 | - | 4 | - | 5 | - | 4 | - | 3 | - | East | 1 | - | M | Exposed roots. | High | High | 20+ | B1 | 5.0 | 79.8 | | |
| G19 | Birch (Silver) | 10 | - | 300 | - | 5 | - | 4 | - | 5 | - | 5 | - | N/A | - | N/A | 1.5 | - | EM | Minor amounts minor deadwood. Occluded pruning wounds. Exposed roots. Eastern tree roots lifting path. | High | High | 20+ | B2 | 3.6 | 40.7 | | |
| T20 | Birch (Silver) | 10 | - | 300 | - | 7 | - | 6 | - | 6 | - | 5 | - | N/A | - | N/A | 1.5 | - | EM | Middle tree bent form, could be removed to better other trees. | Medium | Medium | 20+ | B2 | 3.6 | 40.7 | | |
| G21 | Birch (Silver) | 13 | - | 350 | - | 6.5 | - | 7 | - | 0 | - | 5 | - | N/A | - | N/A | 1 | - | EM | Exposed roots. Adjacent path. Helical growth on western tree. Blunt nosed ribs observed, suggest internal cracks. | Medium | Medium | 20+ | B2 | 4.2 | 55.4 | | |
| T22 | Cherry (Wild) | 8 | - | 460 | - | 7.5 | - | 6 | - | 5 | - | 5 | - | 2 | - | South | 2 | - | M | Minor amounts minor deadwood. Exposed roots with mower damage. Minor pruning ounces. | Medium | High | 10+ | C1 | 5.5 | 95.7 | | |
| T23 | Cherry (Wild) | 12 | - | 600 | - | 5 | - | 5 | - | 6 | - | 5 | - | 2 | - | All round | 2 | - | M | Exposed roots. Minor amounts minor deadwood. Minor pruning wounds. | High | High | 10+ | C1 | 7.2 | 162.9 | | |
| T24 | Maple (Norway) | 11 | - | 550 | - | 5 | - | 3 | - | 4 | - | 6 | - | 2 | - | All round | 2 | - | M | Exposed roots. Minor amounts of minor deadwood. | Medium | Medium | 10+ | C1 | 6.6 | 136.9 | | |
| T25 | Cherry (Wild) | 9 | - | 320 | - | 5 | - | 2 | - | 6 | - | 0.5 | - | 2 | - | All round | 1.5 | - | EM | Suppressed to west and south. Pruning wounds. Poor form. | Medium | Medium | 10+ | C1 | 3.8 | 46.3 | | |
| T26 | Leylandii | 3 | - | 112 | - | 1 | - | 1 | - | 1 | - | 1 | - | N/A | - | N/A | 0.5 | - | EM | Forms a hedge. | High | High | 10+ | C1 | 1.3 | 5.7 | | |
| T27 | Sycamore | 6 | - | 290 | - | 3 | - | 2 | - | 2 | - | 3 | - | N/A | - | N/A | 2 | - | EM | Bark damage. In hedge. Ivy. Poor. | High | High | 10+ | C1 | 3.5 | 38.2 | | |
| T28 | Sycamore | 6 | - | 215 | - | 3 | - | 0.5 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | EM | Low pollarded. Adjacent fence. Lopped. | Medium | Medium | 10+ | C1 | 2.6 | 20.9 | | |
| G29 | Lime (Common) | 12 | - | 450 | - | 6 | - | 5 | # | 6 | - | 6 | - | 2.5 | - | All round | 3 | - | M | Minor amounts minor deadwood. Epicormic growth at base. Suppression generally. Potential cavity at 1.5m west northern tree. Pruning wounds, occluded. | Medium | Medium | 20+ | B1 | 5.4 | 91.6 | | |
| G30 | Maple (Norway) | 12 | - | 530 | - | 6 | - | 6 | - | 7 | - | 6 | - | N/A | - | N/A | 3 | - | M | Eastern tree rubbing branches at 6m east. Minor amounts minor deadwood. | Medium | Medium | 20+ | B2 | 6.4 | 127.1 | | |
| T31 | Maple (Norway) | 12 | - | 450 | - | 5 | - | 5 | - | 6 | - | 5 | - | 3 | - | West | 3 | - | M | Cavities associated with previous pruning wounds. Potential coalescent decay on southern limb. | Medium | Medium | 10+ | C1 | 5.4 | 91.6 | | |
| G32 | Maple (Norway) | 12 | - | 400 | - | 5 | - | 6 | - | 5 | - | 2 | - | N/A | - | N/A | 2 | - | M | Two trees. Weak fork in western tree at 1.5m. | Medium | Medium | 10+ | C2 | 4.8 | 72.4 | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|-----|------------------|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|----|--|--------|--------|-----|----|-----|-------|
| G33 | Maple (Norway) | 14 | - | 600 | - | 6 | - | 6 | - | 6 | - | 6 | - | N/A | - | N/A | 3 | - | M | Close to concrete footpath. Minor amounts minor deadwood. | Medium | Medium | 20+ | B2 | 7.2 | 162.9 |
| T34 | Raywood Ash | 12 | - | 430 | - | 7.5 | - | 8 | - | 6 | - | 6 | - | 3.5 | - | South | 3 | - | M | Exposed tree. Leader been snapped off. Weak forks. Leader hanging in canopy. Raywood ash renown for weak structure. | Medium | Medium | 10+ | C1 | 5.2 | 83.7 |
| T35 | Whitebeam | 6 | - | 300 | - | 3 | - | 2.5 | - | 3 | - | 3 | - | 2 | - | East | 2 | - | M | Minor bark damage. Girdled roots. Lean to north east. | High | High | 10+ | C1 | 3.6 | 40.7 |
| G36 | Whitebeam | 6 | - | 300 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 2 | - | M | Lean to north east. Helical growth. Minor bark damage. | High | High | 10+ | C1 | 3.6 | 40.7 |
| T37 | Whitebeam | 5 | - | 230 | - | 2 | - | 1.5 | - | 5 | - | 1.5 | - | N/A | - | N/A | 2 | - | EM | Lean to north east. | Low | Medium | 10+ | U | 2.8 | 23.9 |
| T38 | Sycamore | 10 | - | 320 | - | 6 | - | 4 | - | 3 | - | 3 | - | 3 | - | All round | 2.5 | - | M | Minor branch damage,associated with wind. Suppressed to west. | Medium | Medium | 10+ | C1 | 3.8 | 46.3 |
| T39 | Ash (Common) | 15 | - | 763 | - | 7 | - | 6 | - | 7 | - | 9 | - | 2 | - | South west | 3 | - | M | Exposed roots. Minor amounts of minor deadwood. Pruning wounds observed, well occluded. | High | High | 20+ | B1 | 9.2 | 263.2 |
| G40 | Chestnut (Horse) | 5 | - | 150 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 2 | - | SM | Blending canker observed. Western tree dead, stem snapped off. | High | Low | <10 | U | 1.8 | 10.2 |
| T41 | Chestnut (Horse) | 6 | - | 240 | - | 3.5 | - | 2 | - | 4 | - | 3 | - | N/A | - | N/A | 2 | - | EM | Good shape. | High | High | 20+ | B1 | 2.9 | 26.1 |
| T42 | Sycamore | 10 | - | 350 | - | 3 | - | 4 | - | 4 | - | 6 | - | 2.5 | - | West | 1.5 | - | M | Abscised branches. Suppressed to south. | High | Medium | 10+ | C1 | 4.2 | 55.4 |
| T43 | Sycamore | 10 | - | 300 | - | 3 | - | 3 | - | 5 | - | 5 | - | 2 | - | South | 2 | - | M | Minor epicormic growth at base. Good shape. | High | High | 20+ | B1 | 3.6 | 40.7 |
| T44 | Cherry (Wild) | 6 | - | 230 | - | 2 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 1.5 | - | EM | Ivy on western tree. Good form. | High | High | 40+ | A2 | 2.8 | 23.9 |
| T45 | Birch (Silver) | 8 | - | 140 | - | 1.5 | - | 1.5 | - | 2 | - | 1 | - | 2 | - | West | 1.5 | - | SM | Slight lean north east. | High | High | 40+ | C1 | 1.7 | 8.9 |
| T46 | Sycamore | 12 | - | 400 | - | 6 | - | 6 | - | 6 | - | 6 | - | 2 | - | North | 2 | - | M | Good shape. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 |
| T47 | Sycamore | 12 | - | 350 | - | 6 | - | 5 | - | 5 | - | 5 | - | 2 | - | East | 1.5 | - | M | Exposed girdled roots. Minor amounts minor deadwood. | Medium | Medium | 20+ | B1 | 4.2 | 55.4 |
| T48 | Sycamore | 10 | - | 330 | - | 4 | - | 5 | - | 4 | - | 5 | - | 2 | - | South | 1.5 | - | M | Minor pruning wounds observed, well occluded. Exposed | Medium | Medium | 20+ | B1 | 4.0 | 49.3 |
| T49 | Cherry (Wild) | 7 | - | 180 | - | 3 | - | 3 | - | 3 | - | 3 | - | 2 | - | South | 1.5 | - | SM | Exposed roots. | High | High | 40+ | A1 | 2.2 | 14.7 |
| G50 | Chestnut (Horse) | 5 | - | 150 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 2 | - | SM | Lower bark damage, likely cause mower, south side. | High | High | 10+ | C1 | 1.8 | 10.2 |
| G51 | Chestnut (Horse) | 5 | - | 150 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 2 | - | SM | Two trees. Eastern tree leader ripped out, mower damage at base. | Medium | Medium | 10+ | C1 | 1.8 | 10.2 |
| T52 | Lime (Common) | 3.5 | - | 50 | - | 1.5 | - | 1.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | 2 | - | Y | Three trees in raised roundabout. Southern tree better tree, others dead. | Medium | Medium | 10+ | C1 | 0.6 | 1.1 |
| T53 | Oak (Red) | 8 | - | 260 | - | 3 | - | 2.5 | - | 3 | - | 4 | - | 2 | - | South | 1.5 | - | EM | Wind blowing top of tree,potential storm damage. | High | High | 40+ | A1 | 3.1 | 30.6 |
| G54 | Ash (Common) | 10 | - | 360 | - | 4.5 | - | 4.5 | - | 5 | - | 4.5 | - | N/A | - | N/A | 2 | - | M | Exposed and girdled roots. | High | High | 20+ | B2 | 4.3 | 58.6 |
| T55 | Maple | 12 | - | 480 | - | 6 | - | 6 | - | 6 | - | 7 | - | N/A | - | N/A | 1 | - | M | Weak fork with included bark at 2m. Exposed damaged roots. Minor amounts minor deadwood. | Low | Medium | 10+ | C1 | 5.8 | 104.2 |
| T56 | Whitebeam | 8 | - | 200 | - | 2 | - | 3.5 | - | 3 | - | 3.5 | - | 2 | - | West | 1.5 | - | M | Mower damage at base east side. Suppressed to north east. Minor amounts major deadwood. | Medium | Medium | 10+ | C1 | 2.4 | 18.1 |
| T57 | Maple | 8 | - | 280 | - | 4 | - | 4 | - | 4 | - | 4.5 | - | 2 | - | All round | 2 | - | EM | Exposed damaged roots. Minor amounts minor deadwood. | Medium | Medium | 20+ | B1 | 3.4 | 35.5 |
| T58 | Whitebeam | 4 | - | 100 | - | 2 | - | 1 | - | 2 | - | 1.5 | - | 2 | - | North | 2 | - | SM | Severe bark damage at base. | Medium | Medium | 10+ | C1 | 1.2 | 4.5 |
| T59 | Whitebeam | 6 | - | 180 | - | 3 | - | 2.5 | - | 3 | - | 3 | - | 1.5 | - | South | 2 | - | SM | Bark damage at base. | Medium | Medium | 10+ | C1 | 2.2 | 14.7 |
| T60 | Maple | 9 | - | 380 | - | 5 | - | 5 | - | 4 | - | 5 | - | 1.5 | - | North | 1 | - | M | Exposed roots. Weak fork at 2m west. | Medium | Medium | 20+ | B1 | 4.6 | 65.3 |
| T61 | Maple | 11 | - | 420 | - | 5 | - | 3 | - | 6 | - | 4 | - | 2 | - | East | 2 | - | M | Exposed girdling roots. Weak fork at 2.5m. Fire hydrant at base to east. | Medium | Low | 10+ | C1 | 5.0 | 79.8 |
| T62 | Whitebeam | 6 | - | 390 | - | 4 | - | 3 | - | 4 | - | 4 | - | 2 | - | West | 2 | - | M | Minor bark damage at base. | High | High | 10+ | C1 | 4.7 | 68.8 |
| T63 | Sycamore | 12 | - | 580 | - | 7 | - | 6.5 | - | 6 | - | 6 | - | 3 | - | North | 3 | - | M | Small wet cavity at 2m west. Pruning wounds well occluded. | High | High | 20+ | B1 | 7.0 | 152.2 |
| T64 | Ash (Common) | 14 | - | 570 | - | 6 | - | 7 | - | 7 | - | 7.5 | - | 4 | - | West | 4 | - | M | Several pruning wounds and branch damage associated with lighting columns. Cavity at 2.5m north west. Exposed roots. | Medium | Medium | 20+ | C1 | 6.8 | 147.0 |
| T65 | Whitebeam | 10 | - | 550 | - | 5 | - | 5 | - | 5 | - | 5 | - | 2 | - | South | 1.5 | - | M | Veteran tree in terms of size for species. | High | High | 20+ | B1 | 6.6 | 136.9 |
| T66 | Whitebeam | 8 | - | 540 | - | 5 | - | 5 | - | 5 | - | 5 | - | 2 | - | South | 1.5 | - | M | Veteran tree in terms of size for species. | High | High | 20+ | B1 | 6.5 | 131.9 |
| T67 | Ash (Common) | 12 | - | 520 | - | 6 | - | 5 | - | 8 | - | 4.5 | - | 2.5 | - | East | 2 | - | M | Exposed roots. Pruning wound and cavity at 1m west. Moderate amounts minor deadwood. Longitudinal crack at | Medium | Medium | 10+ | C1 | 6.2 | 122.3 |
| T68 | Ash (Common) | 14 | - | 630 | - | 6 | - | 6 | - | 7 | - | 7 | - | 2.5 | - | West | 2 | - | M | Minor amounts minor deadwood. | Medium | Medium | 20+ | B1 | 7.6 | 179.6 |
| T69 | Chestnut (Horse) | 14 | - | 750 | - | 6 | - | 6 | - | 6 | - | 4 | - | 2 | - | All round | 3 | - | M | Indication of bacterial wetwood. Weak forks observed with included bark. Elder growing within fork at 1.8m, indication of decay. | High | Medium | 20+ | B1 | 9.0 | 254.5 |
| T70 | Ash (Common) | 14 | - | 680 | - | 4 | - | 6 | - | 4 | - | 7 | - | 4 | - | West | 3 | - | M | Wet cavity at 1.8m north east. Minor amounts minor deadwood. Potential hazard beam observed at 4m west. | Medium | Medium | 10+ | C1 | 8.2 | 209.2 |
| T71 | Willow | 7.5 | - | 450 | - | 2 | - | 2 | - | 3 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Pollarded at 3m. Slight lean north east. | High | High | 20+ | C1 | 5.4 | 91.6 |
| T72 | Willow | 6 | - | 495 | - | 3 | - | 2 | - | 3 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Pollarded at 3m. Slight lean north east. | High | High | 20+ | C1 | 5.9 | 110.8 |
| T73 | Willow | 6 | - | 693 | - | 3 | - | 2.5 | - | 3 | - | 3 | - | N/A | - | N/A | 0.5 | - | M | Pollarded at 3m. Slight lean north east. | High | High | 20+ | C1 | 8.3 | 217.2 |
| T74 | Lawson cypress | 11 | - | 283 | - | 2.5 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Slightly suppressed to north by security fence. Lighting column obstructing growth north. | High | High | 40+ | C1 | 3.4 | 36.2 |
| T75 | Maple | 12 | - | 500 | - | 5 | - | 5 | - | 6 | - | 6 | - | 2 | - | West | 1.5 | - | M | Exposed roots. Pruning wounds well occluded. | High | High | 20+ | B1 | 6.0 | 113.1 |
| T76 | Sycamore | 12 | - | 500 | - | 6 | - | 4.5 | - | 6 | - | 5 | - | 3 | - | East | 2 | - | M | Exposed roots. Pruning wounds well occluded. Cavity on north side next to fence. | High | Medium | 20+ | B1 | 6.0 | 113.1 |
| T77 | Maple | 12 | - | 600 | - | 5 | - | 6 | - | 4 | - | 7 | - | 2.5 | - | West | 2 | - | M | Dead ivy into canopy. Moderate minor deadwood. | Medium | Medium | 10+ | C1 | 7.2 | 162.9 |
| T78 | Maple | 12 | - | 550 | - | 6.5 | - | 5 | - | 6 | - | 5 | - | 1.5 | - | East | 2 | - | M | Previous pruning wound with decay at 1.5m east. Moderate amounts minor deadwood, minor cavities. | Medium | Medium | 10+ | C1 | 6.6 | 136.9 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|--|------|---|-----|---|-----|---|-----|---|-----|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|------|-------|
| T79 | Maple | 12 | - | 630 | - | 6 | - | 5 | - | 5 | - | 6 | - | 3 | - | West | 3 | - | M | Cavity on south at 1.5m. Exposed roots. Minor amounts minor deadwood. | Medium | Medium | 10+ | C1 | 7.6 | 179.6 |
| T80 | Maple | 9 | - | 290 | - | 4 | - | 3.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 2 | - | EM | Weak fork at 1m. Generally suppressed. | Medium | High | 20+ | C1 | 3.5 | 38.1 |
| T81 | Maple | 12 | - | 620 | - | 7 | - | 6 | - | 6 | - | 8 | - | 2.5 | - | West | 2.5 | - | M | Three main stems, forks at 2m. Bark wound with decay on north west side. Exposed damaged roots. Broken branches roadside to north. | Medium | Medium | 20+ | C1 | 7.4 | 173.9 |
| G82 | Maple | 9 | - | 520 | - | 4 | - | 5 | - | 5 | - | 5 | - | N/A | - | N/A | 2 | - | M | Fruiting body on centre tree, with decay. Eastern tree has longitudinal crack, western tree better tree. Central and eastern tree c category, western tree b category. | Medium | Medium | 10+ | C2 | 6.2 | 122.3 |
| G83 | Maple | 9 | - | 480 | - | 4 | - | 5 | - | 4 | - | 4 | - | N/A | - | N/A | 2 | - | M | Third tree from west has fruiting body. Girdling roots observed generally. Minor amounts minor deadwood. Splits in | Medium | Medium | 20+ | B2 | 5.8 | 104.2 |
| T84 | Elm (English) | 5 | - | 100 | - | 2 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 2 | - | Y | Ivy on trunk, at end of hedge. Likely to get Dutch disease. | High | High | 10+ | C2 | 1.2 | 4.5 |
| H85 | Mixed hedge. Hawthorn, privet, Ionicera nitida | 0.75 | - | 50 | - | N/A | - | N/A | - | N/A | - | N/A | - | N/A | - | N/A | 0 | - | Y | Low managed hedge | N/A | N/A | 10+ | C2 | 0.6 | 1.1 |
| T86 | Beech (Common) | 18 | - | 900 | - | 7 | - | 8 | - | 9 | - | 6 | - | 2 | - | East | 2.5 | - | M | Several fused branches. Exposed roots. Minor amounts minor deadwood. | High | Medium | 40+ | A1 | 10.8 | 366.5 |
| T87 | Beech (Common) | 18 | - | 900 | # | 5 | - | 7 | - | 8 | - | 6 | - | 2 | - | West | 2 | - | M | Unable to access to inspect base. Moderate amounts minor deadwood. Slightly suppressed to north. | High | Medium | 40+ | B1 | 10.8 | 366.5 |
| T88 | Pine | 16 | # | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 4 | - | M | Slight lean to the east. | - | - | - | - | 6.0 | 113.1 |
| T89 | Sycamore | 18 | # | 876 | - | 6 | - | 7 | - | 6 | - | 4 | - | 4 | - | North | 3 | - | M | Ivy on trunk. Multi stem. Well occluded pruning wounds. Minor amounts minor deadwood. | High | High | 20+ | B1 | 10.5 | 347.3 |
| T90 | Sycamore | 18 | # | 450 | - | 6 | - | 2 | # | 3 | - | 6 | - | 4 | - | North | 3 | - | M | Tag 559. Suppressed south and east. Ivy in trunk. | High | High | 10+ | C1 | 5.4 | 91.6 |
| T91 | Maple (Norway) | 12 | # | 600 | - | 5.5 | - | 4 | # | 3 | - | 5 | - | N/A | - | N/A | 2 | - | M | Ivy on trunk - dense. Forks at 1.8m. Sever ivy. Pruning wounds, partial occlusion. | High | High | 10+ | C1 | 7.2 | 162.9 |
| T92 | Maple (Norway) | 13 | # | 700 | - | 6.5 | - | 6 | # | 4 | - | 5 | - | N/A | - | N/A | 2.5 | - | M | Tag 555. Dense ivy into crown. Several dead moderately sized branches on eastern stem at 4m. Several pruning wounds observed. Most well occluded, several potential cavities. Forks at 1.8m | Medium | Medium | 10+ | C1 | 8.4 | 221.7 |
| T93 | Cedar (Western Red) | 8 | - | 350 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 0.5 | - | EM | Suppressed lower branches. | High | High | 20+ | C1 | 4.2 | 55.4 |
| T94 | Cypress (Lawson) | 13 | # | 350 | - | 2.5 | - | 1.5 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | EM | Suppressed to south. | High | High | 20+ | C1 | 4.2 | 55.4 |
| T95 | Cypress (Lawson) | 13 | # | 394 | - | 3 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | EM | Dense ivy into canopy. Smaller tree to west. | High | High | 20+ | C1 | 4.7 | 70.1 |
| T96 | Birch (Silver) | 13 | # | 260 | - | 3.5 | - | 3 | - | 3 | - | 2 | - | 2 | - | West | 1.5 | - | M | Slight lean to east. Ivy on trunk. | Medium | High | 10+ | C1 | 3.1 | 30.6 |
| T97 | Yew (Irish) | 6 | # | 400 | - | 2 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Suppressed. | High | High | 20+ | C1 | 4.8 | 72.4 |
| T98 | Maple (Norway) | 12 | # | 600 | - | 0.5 | - | 6 | - | 7 | - | 1 | - | 2 | - | North | 2.5 | - | M | Large wet cavity at 1.5m south. Ivy into trunk. Forks at 2m. | Medium | Medium | 10+ | C1 | 7.2 | 162.9 |
| T99 | Maple (Norway) | 14 | # | 450 | - | 2 | - | 5 | - | 7 | - | 3 | - | N/A | - | N/A | 8 | - | M | Drawn up form. Tag 4675. Ivy on trunk. Exposed roots. | Medium | Medium | 10+ | C1 | 5.4 | 91.6 |
| T100 | Maple (Norway) | 14 | # | 650 | - | 6 | - | 8 | - | 1 | - | 7.5 | - | 4.5 | - | South west | 4 | - | M | Heavily suppressed to west. Dense ivy into canopy. | Medium | High | 10+ | C1 | 7.8 | 191.2 |
| T101 | Maple (Norway) | 14 | # | 540 | - | 7 | - | 1 | - | 9 | - | 3 | - | N/A | - | N/A | 2.5 | - | M | Forks at 1.5m. Cavity on northern stem at 4m. Ivy on trunk into canopy. Suppressed to south and west. Minor amounts | Medium | Medium | 10+ | C1 | 6.5 | 131.9 |
| T102 | Lime (Common) | 16 | # | 700 | - | 7 | - | 6 | - | 6 | - | 8 | - | 4 | - | North | 2 | - | M | Pruning wounds well occluded. | High | High | 40+ | A1 | 8.4 | 221.7 |
| T103 | Sycamore | 15 | # | 670 | - | 2.5 | - | 3 | - | 7 | - | 7 | - | 3.5 | - | West | 2.5 | - | M | Ustulina deusta at base | Low | Medium | <10 | U | 8.0 | 203.1 |
| T104 | Chestnut (Horse) | 15 | # | 900 | - | 2 | - | 8.5 | - | 10 | - | 7 | - | N/A | - | N/A | 2.5 | - | M | Forks at 1.5m into three stems. Bark and stem splits on middle stem. Pruning wounds, partial occlusion. Pruning | Medium | Medium | 10+ | C1 | 10.8 | 366.5 |
| T105 | Maple (Norway) | 12 | # | 450 | - | 5 | - | 5 | - | 6 | - | 4 | - | 3 | - | South | 2.5 | - | M | Forks at 1.5m. Abscised branches. Multiple pruning wounds partially occluded. Cavity on southern stem at 3m. | Medium | Medium | 10+ | C1 | 5.4 | 91.6 |
| G106 | Sycamore | 16 | # | 600 | - | 9 | - | 8 | - | 7 | - | 3 | - | N/A | - | N/A | 2.5 | - | M | Minor amounts minor deadwood. | High | High | 20+ | B2 | 7.2 | 162.9 |
| T107 | Sycamore | 16 | # | 600 | - | 7 | - | 8 | - | 2 | - | 4 | - | 4 | - | South | 2.5 | - | M | Large cavity at 1.5m west, exposed heartwood with decay. Moderate deadwood. Pruning wounds. Suppressed. | Low | Low | 10+ | C1 | 7.2 | 162.9 |
| T108 | Sycamore | 18 | # | 820 | - | 7.5 | - | 7 | - | 6 | - | 5 | - | 3 | - | West | 1.5 | - | M | Forks at 3m. Three main stems. Minor amounts minor deadwood. | High | High | 20+ | B1 | 9.8 | 304.2 |
| T109 | Walnut (Common) | 17 | # | 400 | - | 6 | - | 0.5 | - | 1 | - | 5.5 | - | 4 | - | West | 3 | - | M | Heavily suppressed. Drawn up form. Minor amounts minor deadwood. | Medium | High | 20+ | C1 | 4.8 | 72.4 |
| T110 | Sycamore | 17 | # | 700 | - | 5 | - | 6 | - | 1 | - | 5 | - | 5 | - | South east | 5 | - | M | Forks at 2m. Pruning wounds well occluded. | High | High | 20+ | B1 | 8.4 | 221.7 |
| T111 | Walnut (Common) | 14 | # | 460 | - | 8 | - | 7 | - | 7 | - | 8 | - | 4 | - | East | 2 | - | M | Forks at 3m. Pruning wound on northern limb at 4m with decay. Girdling roots. | Medium | Medium | 20+ | C1 | 5.5 | 95.7 |
| T112 | Chestnut (Horse) | 13 | # | 520 | - | 3 | - | 7 | - | 5 | - | 7 | - | 4 | - | East | 3 | - | M | Forks at 3m. Pruning wounds well occluded. Leader broken off, decay noted. Poor pruning and tree works observed, torn | Medium | Medium | 20+ | C1 | 6.2 | 122.3 |
| T113 | Cherry (Wild) | 13 | # | 330 | - | 3 | - | 2 | - | 2 | - | 4 | - | 4 | - | North | 3 | - | M | Drawn up form, poor shape. | High | High | 20+ | C1 | 4.0 | 49.3 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|--------------------------------|-----|---|-----|---|-----|---|-----|---|----|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|------|-------|
| T114 | Cedar (Deodar) | 18 | # | 922 | - | 9 | - | 6 | - | 5 | - | 6 | - | 3 | - | North | 2 | - | M | Recent pruning on south side. Good form. | High | High | 40+ | A1 | 11.1 | 384.6 |
| T115 | Cedar (Deodar) | 15 | # | 600 | - | 6 | - | 5 | - | 6 | - | 4 | - | 5 | - | East | 2.5 | - | M | Minor bark damage at base. Suppressed to east. | High | High | 40+ | B1 | 7.2 | 162.9 |
| T116 | Hawthorn | 7 | # | 240 | - | 2 | - | 3.5 | - | 3 | - | 2 | - | 2 | - | East | 2 | - | M | Large branch torn off south side. Poor form. | Medium | Medium | 10+ | C1 | 2.9 | 26.1 |
| G117 | Laburnam | 10 | # | 550 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 2 | - | M | Exposed damaged roots. Cavity at 1.8m in centre of stems. | Medium | Medium | 10+ | C1 | 6.6 | 136.9 |
| T118 | Laburnam | 9 | # | 450 | - | 5 | - | 4 | - | 4 | - | 5 | - | N/A | - | N/A | 0.5 | - | M | Remove lower adventitious growth. Minor bark damage. Forks at 1.8m, possible decay entry point. | Medium | Medium | 10+ | B1 | 5.4 | 91.6 |
| T119 | Lilac | 3.5 | # | 180 | - | 3.5 | - | 0.5 | - | 3 | - | 1 | - | N/A | - | N/A | 1.5 | - | M | Leans north. Poor form. | Medium | Medium | 10+ | C1 | 2.2 | 14.7 |
| T120 | Laburnam | 7 | # | 650 | - | 6 | - | 3 | - | 6 | - | 2 | - | N/A | - | N/A | 3 | - | OM | Lean to north east. Bark damage at base. Moderate amounts moderate deadwood. | Medium | Low | 10+ | C1 | 7.8 | 191.2 |
| T121 | Beech (Common) | 16 | # | 790 | - | 9 | - | 8 | - | 12 | - | 8 | - | 3 | - | East | 2 | - | M | Minor bark damage at 1.5m west. Exposed roots. Minor amounts minor deadwood. | High | Medium | 40+ | B1 | 9.5 | 282.4 |
| G122 | Cypress (Lawson) | 6 | # | 130 | - | 1.5 | - | 1.5 | - | 2 | - | 1 | - | N/A | - | N/A | 1.5 | - | SM | Suppressed by beech tree. | High | High | 40+ | C1 | 1.6 | 7.6 |
| T123 | Cypress (Lawson) | 14 | # | 600 | - | 3.5 | - | 4 | - | 4 | - | 4 | - | N/A | - | N/A | 1.5 | - | M | Pruning observed. Good tree. | High | High | 40+ | A1 | 7.2 | 162.9 |
| G124 | Birch (Silver) | 10 | # | 150 | - | 1.5 | - | 1.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | 2 | - | SM | Eastern tree stunted and poor form. | High | High | 20+ | C2 | 1.8 | 10.2 |
| G125 | Birch (Silver) | 10 | # | 150 | - | 2 | - | 2 | - | 2 | - | 2.5 | - | N/A | - | N/A | 2 | - | SM | Eastern tree stunted and poor form. | High | High | 20+ | C2 | 1.8 | 10.2 |
| T126 | Ash (Common) | 8 | # | 160 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | 2 | - | East | 1.5 | - | SM | Minor branch damage roadsides. Lifting up tree grille. | Medium | Medium | 10+ | C1 | 1.9 | 11.6 |
| T127 | Lime (Common) | 13 | # | 430 | - | 3 | - | 6 | - | 5 | - | 5 | - | 2 | - | South | 1.5 | - | M | Pruning wounds well occluded. Suppressed to north west. Slight lean to south east. | Medium | Medium | 40+ | B1 | 5.2 | 83.7 |
| H128 | Cedar (Western Red) | 10 | # | 150 | # | - | - | - | - | - | - | - | - | - | - | - | 0.5 | - | M | Trim into shape. | High | High | 20+ | C2 | 1.8 | 10.2 |
| T129 | Sycamore | 18 | # | 634 | - | 6 | - | 6 | - | 6 | - | 6 | - | N/A | - | N/A | 3 | - | M | Ivy into canopy. Broken branches. Concrete embedded into base of trunk. | Medium | Medium | 20+ | C1 | 7.6 | 182.1 |
| T130 | Sycamore | 16 | # | 450 | - | 6 | - | 6 | - | 6 | - | 6 | - | 3 | - | South | 3 | - | M | Ivy into canopy. Suppressed by thuja hedge. Suppressed to north. | Medium | Medium | 20+ | C1 | 5.4 | 91.6 |
| T131 | Lilac | 5 | # | 300 | - | 3 | - | 3 | - | 3 | - | 2 | - | N/A | - | N/A | 1.5 | - | OM | Decay, twisted branches, poor. | Medium | Medium | 10+ | C1 | 3.6 | 40.7 |
| T132 | Ash (Common) | 12 | # | 550 | - | 6 | - | 6 | - | 9 | - | 6 | - | 2 | - | South | 2 | - | M | Ivy into canopy. Minor amounts minor deadwood. | High | High | 20+ | B1 | 6.6 | 136.9 |
| H133 | Mixed hedge. Hawthorn, privet, | 1.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | Trim as appropriate. | - | - | - | - | - | - |
| T134 | Sycamore | 15 | # | 520 | - | 4 | - | 6 | - | 5 | - | 3 | - | 4 | - | South east | 3.5 | - | M | Epicormic growth at base could be removed. | Medium | Medium | 40+ | A2 | 6.2 | 122.3 |
| T135 | Ash (Common) | 15 | # | 270 | - | 2 | - | 5.5 | - | 3 | - | 1 | - | N/A | - | N/A | 5 | - | M | Forks at 5m. Drawn up and suppressed. Remove to benefit trees either side? | Low | Low | 10+ | C2 | 3.2 | 33.0 |
| T136 | Ash (Common) | 15 | # | 370 | - | 2 | - | 8 | - | 2 | - | 4 | - | 5 | - | South west | 4 | - | M | Minor deadwood. Crossing branches. Kink in the stem. | Medium | Low | 20+ | C2 | 4.4 | 61.9 |
| T137 | Sycamore | 15 | # | 370 | - | 2 | - | 6 | - | 3 | - | 2 | - | 4 | - | South west | 2.5 | - | M | No work required. Suppressed to north. | Medium | Medium | 20+ | B2 | 4.4 | 61.9 |
| T138 | Beech (Common) | 16 | # | 500 | - | 3 | - | 6 | - | 4 | - | 4 | - | 3.5 | - | South east | 2.5 | - | M | Girdled roots. Good tree. No work required. | High | High | 40+ | A2 | 6.0 | 113.1 |
| T139 | Sycamore | 15 | # | 420 | - | 0.5 | - | 6 | - | 3 | - | 2 | - | 3.5 | - | West | 4 | - | M | Remove epicormic growth at base. Minor pruning wounds and decay. Suppressed to north and east. | Medium | Medium | 20+ | B2 | 5.0 | 79.8 |
| T140 | Beech (Common) | 17 | # | 580 | - | 6 | - | 6 | - | 5 | - | 3.5 | - | 4 | - | East | 2 | - | M | Weak fork with included bark at 2m. | Medium | High | 20+ | B2 | 7.0 | 152.2 |
| T141 | Beech (Common) | 17 | # | 420 | - | 1 | - | 8.5 | - | 2 | - | 0.5 | - | 2 | - | South | 2 | - | M | Heavily suppressed to north. Remove rotten branch at 2m. | Medium | Medium | 10+ | C2 | 5.0 | 79.8 |
| T142 | Beech (Common) | 17 | # | 450 | - | 5 | - | 6 | - | 4 | - | 1.5 | - | 4 | - | East | 4 | - | M | Minor pruning wounds. Suppressed to west. | Medium | Medium | 10+ | C2 | 5.4 | 91.6 |
| T143 | Beech (Common) | 17 | # | 850 | - | 6 | - | 8 | - | 4 | - | 5 | - | 4 | - | South | 3 | - | M | No works required. | Medium | High | 20+ | A2 | 10.2 | 326.9 |
| T144 | Sycamore | 15 | # | 320 | - | 3 | - | 0.5 | - | 2 | - | 3 | - | N/A | - | N/A | 3 | - | M | Suppressed to south. Poor. Remove central stem. | Medium | Low | 10+ | C2 | 3.8 | 46.3 |
| T145 | Beech (Common) | 15 | # | 297 | - | 4 | - | 3 | - | 3 | - | 4 | - | 3 | - | South east | 2.5 | - | M | No works required. Weak fork at 1m. | Medium | Medium | 10+ | C2 | 3.6 | 40.0 |
| T146 | Sycamore | 17 | # | 480 | - | 4 | - | 7 | - | 3 | - | 4 | - | 2 | - | South | 3 | - | M | Severe decay on north side where stem has been removed. Monitor decay. | Medium | Medium | 10+ | C2 | 5.8 | 104.2 |
| T147 | Hawthorn | 4 | # | 220 | - | 1 | - | 3 | - | 3 | - | 3 | - | 2 | - | West | 2 | - | M | In hedge. Evidence of past pruning on roadside. Remove ivy on stem. | Medium | Medium | 10+ | C2 | 2.6 | 21.9 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|----------------|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|---|---|--------|--------|-----|----|-----|-------|
| T148 | Sycamore | 15 | # | 347 | - | 4 | - | 6 | - | 3 | - | 2 | - | 3.5 | - | South | 4.5 | - | M | Removed limb at base, partial occlusion with cavity and decay. Probed to 20cm, soft with decay. Deadwood, | Medium | Low | 10+ | C2 | 4.2 | 54.3 |
| T149 | Sycamore | 15 | # | 509 | - | 6 | - | 6 | - | 2 | - | 3 | - | 2.5 | - | North | 2 | - | M | Multiple weak forks. Minor deadwood. Suppressed to east. | Medium | Medium | 20+ | C2 | 6.1 | 117.3 |
| T150 | Hawthorn | 6 | # | 300 | - | 1 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 2.5 | - | M | Forks at 2m. Remove ivy and re assess. | Medium | Medium | 10+ | C2 | 3.6 | 40.7 |
| T151 | Hawthorn | 4.5 | # | 230 | - | 0.5 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 2.5 | - | M | Forks at 1.5m. Remove ivy and re assess. | Medium | Medium | 10+ | C2 | 2.8 | 23.9 |
| T152 | Sycamore | 17 | # | 460 | - | 7 | - | 6 | - | 4 | - | 3 | - | 2 | - | South | 4 | - | M | Some pruning wounds with deadwood and decay. Clean through canopy. | Medium | Medium | 20+ | C2 | 5.5 | 95.7 |
| T153 | Plum (Purple) | 9 | # | 377 | - | 4 | - | 2.5 | - | 5 | - | 3 | - | N/A | - | N/A | 2 | - | M | Remove ivy. Forks at 1m. | Medium | Medium | 10+ | C2 | 4.5 | 64.5 |
| T154 | Beech (Common) | 16 | # | 742 | - | 8 | - | 8 | - | 8 | - | 7 | - | 2.5 | - | South west | 2 | - | M | No works required. Minor deadwood. | Medium | High | 20+ | B2 | 8.9 | 249.4 |
| T155 | Hawthorn | 6 | # | 250 | - | 0.5 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 2 | - | M | Forks at 2m. Remove ivy and re assess. | Medium | Medium | 10+ | C2 | 3.0 | 28.3 |
| T156 | Sycamore | 15 | # | 550 | - | 7 | - | 6 | - | 5 | - | 5 | - | 2 | - | North west | 2.5 | - | M | Minor deadwood. | High | High | 20+ | B2 | 6.6 | 136.9 |
| T157 | Sycamore | 15 | # | 600 | - | 6 | - | 6 | - | 5 | - | 3 | - | 2.5 | - | South east | 2.5 | - | M | Possible decay at junction of stems at 1.5m. Suppressed to west. | Medium | Medium | 20+ | B2 | 7.2 | 162.9 |
| T158 | Beech (Common) | 16 | # | 630 | - | 4 | - | 7 | - | 6 | - | 5 | - | 2.5 | - | East | 2 | - | M | Suppressed to north. | High | High | 20+ | B2 | 7.6 | 179.6 |
| T159 | Sycamore | 16 | # | 450 | - | 2 | - | 4 | - | 4 | - | 2 | - | 1.5 | - | North | 6 | - | M | Suppressed generally, minor deadwood. Possible removal to benefit other trees. | Medium | Low | 10+ | C2 | 5.4 | 91.6 |
| T160 | Sycamore | 16 | # | 250 | - | 3 | - | 1.5 | - | 2 | - | 3 | - | N/A | - | N/A | 2 | - | M | Decay at base. Remove epicormic growth. Possible removal to benefit other trees. Suppressed generally. | Medium | Low | 10+ | C2 | 3.0 | 28.3 |
| T161 | Elm | 16 | # | 550 | - | 5 | - | 4 | - | 8 | - | 1.5 | - | 4 | - | North east | N/A | - | M | Dead. Remove due to health and safety risk. | Low | Low | <10 | U | 6.6 | 136.9 |
| T162 | Sycamore | 15 | # | 670 | - | 6 | - | 4 | - | 4 | - | 5 | - | 4 | - | West | 5 | - | M | Poor shape. Suppressed to south. | Medium | Low | 20+ | B2 | 8.0 | 203.1 |
| T163 | Maple? | 16 | # | 450 | - | 2 | - | 4 | - | 4 | - | 5.5 | - | 4 | - | South west | 4 | - | M | Major dead in canopy. In decline? Remove to benefit other trees. | Low | Low | <10 | U | 5.4 | 91.6 |
| T164 | Beech (Common) | 16 | # | 750 | - | 6 | - | 4 | - | 5 | - | 6 | - | 5 | - | North east | 3 | - | M | Overhangs building to west. Weak fork at 1.5m. Meters embedded at 1.5m south. | Medium | Medium | 20+ | B2 | 9.0 | 254.5 |
| T165 | Beech (Common) | 16 | # | 310 | - | 3 | - | 0.5 | - | 1 | - | 5.5 | - | 5 | - | North west | 2 | - | M | Severe lean to north west. Remove to benefit other trees. | Low | Medium | 10+ | C2 | 3.7 | 43.5 |
| T166 | Sycamore | 16 | # | 500 | - | 5 | - | 3 | - | 5 | - | 4 | - | 4 | - | West | 4 | - | M | No works required. | Medium | Medium | 10+ | C2 | 6.0 | 113.1 |
| T167 | Beech (Common) | 16 | # | 480 | - | 6 | - | 3 | - | 4 | - | 3 | - | 4 | - | North east | 2 | - | M | No works required. | Medium | Medium | 40+ | B2 | 5.8 | 104.2 |
| T168 | Beech (Common) | 16 | # | 540 | - | 7 | - | 3 | - | 5 | - | 6 | - | 5 | - | North west | 3.5 | - | M | No works required. | Medium | Medium | 20+ | B2 | 6.5 | 131.9 |
| T169 | Sycamore | 16 | # | 360 | - | 1.5 | - | 1.5 | - | 1 | - | 1.5 | - | 2.5 | - | South | 3 | - | M | Suppressed shape. No works required. | Medium | Medium | 20+ | C2 | 4.3 | 58.6 |
| T170 | Beech (Common) | 16 | # | 220 | - | 3 | - | 1 | - | 2 | - | 2 | - | 2 | - | South | 2 | - | M | Remove side shoots to south to 2m. | Medium | Medium | 20+ | C2 | 2.6 | 21.9 |
| T171 | Beech (Common) | 16 | # | 360 | - | 3 | - | 4 | - | 4 | - | 4.5 | - | 4 | - | East | 3 | - | M | No works required. | Medium | Medium | 20+ | C2 | 4.3 | 58.6 |
| T172 | Beech (Common) | 16 | # | 440 | - | 2 | - | 5 | - | 8 | - | 3 | - | 4 | - | South east | 4 | - | M | Suppressed to north west. Twisted branches at top of canopy. | Medium | Medium | 20+ | C2 | 5.3 | 87.6 |
| T173 | Beech (Common) | 16 | # | 320 | - | 2 | - | 4 | - | 3 | - | 3 | - | 9 | - | South east | 9 | - | M | No works required. | Medium | Medium | 40+ | B2 | 3.8 | 46.3 |
| T174 | Hornbeam | 16 | - | 275 | - | 2 | - | 4 | - | 6 | - | 2.5 | - | 2.5 | - | East | 2.5 | - | M | No works required. | Medium | Medium | 20+ | C2 | 3.3 | 34.1 |
| T175 | Sycamore | 16 | - | 286 | - | 2.5 | - | 3 | - | 3 | - | 2 | - | N/A | - | N/A | 9 | - | M | Remove to benefit other trees. | Medium | Low | 20+ | C2 | 3.4 | 37.0 |
| T176 | Beech (Common) | 16 | - | 280 | - | 0.5 | - | 8 | - | 8 | - | 0.5 | - | N/A | - | N/A | 10 | - | M | Moderate lean to the south. Remove to benefit other trees. | Low | Low | 20+ | C2 | 3.4 | 35.5 |
| T177 | Beech (Common) | 16 | - | 370 | - | 3 | - | 5 | - | 7 | - | 4 | - | N/A | - | N/A | 10 | - | M | No works required. | Medium | Low | 20+ | C2 | 4.4 | 61.9 |
| T178 | Hornbeam | 16 | - | 520 | - | 5 | - | 6 | - | 7 | - | 5 | - | 2.5 | - | East | 2 | - | M | No works required. | High | Medium | 20+ | B2 | 6.2 | 122.2 |
| T179 | Beech (Common) | 16 | - | 550 | - | 8 | - | 5 | - | 9 | - | 4 | - | 2.5 | - | North | 0.5 | - | M | Raise canopy to 2m. Remove deadwood. Overhangs building to east. Suppressed to west. | Medium | Medium | 20+ | B2 | 6.6 | 136.9 |
| T180 | Beech (Common) | 16 | - | 640 | - | 8 | - | 6 | - | 4 | - | 5 | - | 5 | - | North | 7 | - | M | Cavities observed. Suppressed to west. | Medium | Medium | 20+ | B2 | 7.7 | 185.3 |
| T181 | Sycamore | 16 | - | 340 | - | 1 | - | 3 | - | 3 | - | 1 | - | N/A | - | N/A | 10 | - | M | No works required. | Medium | Low | 20+ | C2 | 4.1 | 52.3 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|----------------------------------|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|-----|-------|
| T182 | Beech (Common) | 16 | - | 440 | - | 7 | - | 3.5 | - | 5 | - | 3 | - | 4 | - | South east | 4 | - | M | No works required. | Medium | Medium | 20+ | B2 | 5.3 | 87.6 |
| T183 | Beech (Common) | 16 | - | 190 | - | 3 | - | 1.5 | - | 2 | - | 1.5 | - | 2.5 | - | North east | 2 | - | EM | Remove to benefit adjacent tree. | Medium | Low | 20+ | C2 | 2.3 | 16.3 |
| T184 | Sycamore | 16 | - | 670 | - | 7 | - | 3.5 | - | 5 | - | 3 | - | 5 | - | North | 5 | - | M | Concrete to north. | Medium | Medium | 40+ | B2 | 8.0 | 203.1 |
| T185 | Beech (Common) | 16 | - | 300 | - | 1.5 | - | 3.5 | - | 3 | - | 4 | - | 2.5 | - | West | 2.5 | - | M | No works required. | Medium | Medium | 40+ | B2 | 3.6 | 40.7 |
| T186 | Beech (Common) | 16 | - | 670 | - | 7 | - | 5.5 | - | 5 | - | 7 | - | 4 | - | South west | 3 | - | M | Overhangs building to north.No works required. | Medium | Medium | 20+ | B2 | 8.0 | 203.1 |
| T187 | Beech (Common) | 16 | - | 370 | - | 7 | - | 5 | - | 2 | - | 4 | - | 2 | - | West | 2 | - | M | Remove side shoots to 2m. Raise canopy to 2m. | Medium | Medium | 20+ | C2 | 4.4 | 61.9 |
| T188 | Sycamore | 15 | # | 453 | - | 5.5 | - | 0.5 | - | 3 | - | 5 | - | N/A | - | N/A | 3 | - | M | Suppressed to south and east. | Medium | Medium | 20+ | C1 | 5.4 | 92.8 |
| T189 | Beech (Common) | 16 | # | 460 | - | 4 | - | 3.5 | - | 2 | - | 5 | - | 4 | - | West | 5 | - | M | Suppressed to south and east. Minor amounts minor deadwood. | Medium | Medium | 20+ | B1 | 5.5 | 95.7 |
| T190 | Sycamore | 16 | # | 570 | - | 4 | - | 3 | - | 3 | - | 2 | - | N/A | - | N/A | 5 | - | M | Several cavities with decay. Suppressed to the west. Broken branches. Kerb and Tarmac to east. | Medium | Medium | 20+ | C1 | 6.8 | 147.0 |
| T191 | Sycamore | 15 | # | 480 | - | 1 | - | 3 | - | 2 | - | 6 | - | N/A | - | N/A | 5 | - | M | Pruning wounds, cavities, minor amounts minor deadwood. | Medium | Medium | 20+ | C1 | 5.8 | 104.2 |
| T192 | Sycamore | 15 | # | 200 | - | 1.5 | - | 2 | - | 3 | - | 0.5 | - | 2.5 | - | West | N/A | - | EM | Poor. Remove to benefit other trees. | Medium | Medium | 10+ | C1 | 2.4 | 18.1 |
| T193 | Sycamore | 15 | # | 424 | - | 3 | - | 2 | - | 6 | - | 3 | - | N/A | - | N/A | 5 | - | M | Pruning wounds and cavities with decay. suppressed to the south. Minor amounts minor deadwood. Forks at 1m. Lower | Medium | Medium | 10+ | C1 | 5.1 | 81.5 |
| T194 | Sycamore | 1.5 | - | 400 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | M | Dead stump. | High | Low | <10 | U | 4.8 | 72.4 |
| T195 | Whitebeam | 7 | - | 160 | - | 2.5 | - | 2.5 | - | 2 | - | 2 | - | 2 | - | East | 2 | - | SM | Weak fork, mower damage at base | Low | Low | 20+ | C1 | 1.9 | 11.6 |
| G196 | Hawthorn | 5 | - | 160 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | N/A | - | M | Poor group | Low | Low | 20+ | C2 | 1.9 | 11.6 |
| H197 | Laurel hedge | 1 | - | 100 | - | 0 | - | 0 | - | 1 | - | 0.5 | - | N/A | - | N/A | N/A | - | M | Manage as appropriate. Ash saplings and bramble to be removed. | N/A | N/A | 20+ | C2 | 1.2 | 4.5 |
| T198 | Cherry (Wild) | 8 | - | 400 | - | 5 | - | 5 | - | 6 | - | 5 | - | 2 | - | South | 1.5 | - | M | Tag 4980. Growing into building on east side. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 |
| T199 | Hawthorn | 4 | - | 200 | - | 3 | - | 2.5 | - | 3 | - | 3 | - | 1.5 | - | South west | 1.5 | - | M | Allot of decay, hard landscape at base. Splits in trunk. | Low | Low | 10+ | C1 | 2.4 | 18.1 |
| T200 | Hawthorn | 4 | - | 210 | - | 3 | - | 2.5 | - | 3 | - | 2.5 | - | 2 | - | South | 2.5 | - | M | Sever decay at base of trunk. Multiple pruning wounds and crossing branches. Poor. | Low | Medium | 10+ | C1 | 2.5 | 20.0 |
| T201 | Cypress (Leyland) | 9 | - | 316 | - | 2 | - | 1.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | 0.5 | - | M | In low raised bed. Roots damaging wall. | Low | Low | 10+ | C1 | 3.8 | 45.2 |
| T202 | Cypress (Lawson) | 9 | - | 200 | - | 1.5 | - | 1.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | 0.5 | - | M | In low raised bed. Roots damaging wall. Recommend remove lower branches. | Medium | Medium | 20+ | B1 | 2.4 | 18.1 |
| G203 | Chestnut (Horse) | 10 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 3 | - | M | All in circular beds within block paving. All show signs of pruning wounds with minor decay. Minor bark damage noted. | Medium | Medium | 20+ | B2 | 4.2 | 55.4 |
| T204 | Sycamore | 12 | - | 410 | - | 5 | - | 5 | - | 4 | - | 5 | - | 2.5 | - | North | 4 | - | M | Low retaining wall to north and east. Pruning wounds with decay, partial occlusion. | Medium | Medium | 20+ | B1 | 4.9 | 76.1 |
| T205 | Maple (Norway) | 12 | - | 550 | - | 5.5 | - | 7.5 | - | 5 | - | 6 | - | 2.5 | - | West | 1.5 | - | M | Kerb and bollards at base. Pruning wounds have not occluded to east. | Medium | Medium | 20+ | B1 | 6.6 | 136.9 |
| T206 | Sycamore | 12 | - | 400 | - | 5 | - | 6 | - | 6 | - | 3 | - | 3 | - | East | 3 | - | M | Suppressed to north and west. Surrounded by concrete and hard surfacing. Growing in grassed area. Deadwood and | Medium | Medium | 10+ | C1 | 4.8 | 72.4 |
| T207 | Sycamore | 16 | - | 750 | - | 7.5 | - | 7 | - | 8 | - | 7 | - | 3 | - | West | 3 | - | M | In grassed area surrounded by concrete. Minor deadwood. Few pruning wounds. | High | High | 20+ | B1 | 9.0 | 254.5 |
| T208 | Sycamore | 14 | - | 380 | - | 4.5 | - | 6 | - | 2 | - | 2 | - | 2 | - | South | 3.5 | - | M | Concrete path to west. Poor shape. Suppressed to east and west. Minor deadwood and decay. | Low | Medium | 10+ | C1 | 4.6 | 65.3 |
| T209 | Sycamore | 15 | - | 570 | - | 5.5 | - | 7 | - | 6 | - | 4 | - | 3 | - | South | 3 | - | M | Minor amounts minor deadwood. Inspect fork at 3.5m. | Medium | Medium | 20+ | B1 | 6.8 | 147.0 |
| G210 | Sycamore | 15 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Several pruning wounds observed, not occluded with minor decay. Typical of age and species. Minor deadwood. Weak | Medium | Medium | 20+ | C2 | 6.0 | 113.1 |
| G211 | Birch (Silver) | 15 | - | 300 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 0.5 | - | M | Suppressed, generally poor. | High | Medium | 20+ | C2 | 3.6 | 40.7 |
| G212 | Hawthorn | 5 | - | 200 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 0.5 | - | M | Very poor shape, damaged bark. | Medium | Low | 20+ | C2 | 2.4 | 18.1 |
| T213 | Maple (Norway) | 12 | - | 390 | - | 5 | - | 5 | - | 6 | - | 5.5 | - | 2 | - | East | 1.5 | - | M | Exposed roots. Overhanging building to east. Minor branch damage, slightly suppressed to east. | High | Medium | 20+ | B1 | 4.7 | 68.8 |
| G214 | Whitebeam | 9 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Heavily suppressed. Decay in trunks, hollow. Twisted form. Generally very poor. U graded for two eastern trees. | Low | Low | 10+ | C2 | 3.6 | 40.7 |
| G215 | Maple, elder, bramble, sycamore. | 7 | - | 150 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | Y | Unable to access. Pond covered with netting in isolated fenced area. Damaged bark, poor quality. | Low | Low | <10 | U | 1.8 | 10.2 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|--------------------------|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|---|-------|-----|---|----|--|--------|--------|-----|----|-----|-------|
| G216 | Cedar (Western Red) | 18 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Group of 15 trees. Outgrown location. Screen. Poor generally. | Medium | Medium | 20+ | C2 | 4.8 | 72.4 |
| G217 | Chestnut (Horse) | 18 | - | 480 | - | 7 | - | 8.5 | - | 7 | - | 7.5 | - | N/A | - | N/A | 1.5 | - | M | Pruning wounds, deadwood. Northern tree suppressed by conifers to north. | Medium | Medium | 20+ | C2 | 5.8 | 104.2 |
| G218 | Cypress (Leyland) | 10 | - | 175 | - | 2.5 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 0.5 | - | M | Suppressed. Interfering with growth of chestnuts. | High | Medium | 20+ | C2 | 2.1 | 13.9 |
| G219 | Lime, sycamore | 14 | - | 450 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | Remove trees identified in plan. Coalescent decay from multiple pruning wounds on same part of stem, potential | Medium | Medium | 20+ | C2 | 5.4 | 91.6 |
| G220 | Cypress (Leyland) | 9 | - | 250 | - | 3 | - | 4 | - | 2 | - | 2.5 | - | N/A | - | N/A | 2 | - | M | Northern tree smaller, suppressed and shaded out by southern tree. Generally poor as a group. | Medium | Low | 20+ | C2 | 3.0 | 28.3 |
| G221 | Ash, sycamore | 8 | - | 367 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Growing on edge of building, surrounded by hard landscaping. Impractical to retain. | Low | Low | 20+ | C2 | 4.4 | 61.1 |
| T222 | Sycamore | 8 | - | 235 | - | 2 | - | 4 | - | 3 | - | 4 | - | N/A | - | N/A | 0.5 | - | M | Growing on edge of building. Impractical to retain. | Low | Low | 20+ | C2 | 2.8 | 24.9 |
| G223 | Sycamore | 8 | - | 292 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Two tree heavily suppressed and in between two buildings, impractical to retain. | Low | Low | 20+ | C2 | 3.5 | 38.5 |
| G224 | Sycamore | 8 | - | 229 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Growing in tarmac, next to temporary building. Impractical to retain. | Low | Low | 10+ | C2 | 2.7 | 23.8 |
| G225 | Birch, sycamore | 8 | - | 150 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Growing in tarmac, next to temporary building. Impractical to retain. | Low | Low | 10+ | C2 | 1.8 | 10.2 |
| G226 | Elder, birch | 8 | - | 367 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Two birch, one large elder growing next to buildings. Impractical to retain. | Low | Low | 10+ | C2 | 4.4 | 61.1 |
| G227 | Sycamore | 9 | - | 367 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Growing out from side of buildings. Impractical to retain. | Low | Low | 10+ | C2 | 4.4 | 61.1 |
| G228 | Chestnut (Horse) | 7 | - | 150 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Growing out from side of buildings. Impractical to retain. | Low | Low | 10+ | C2 | 1.8 | 10.2 |
| T229 | Hawthorn | 5 | - | 50 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Growing out from side of buildings. Impractical to retain. | Low | Low | 10+ | C2 | 0.6 | 1.1 |
| T230 | Sycamore | 12 | - | 590 | - | 6 | - | 6 | - | 6 | - | 6 | - | 1 | - | South | 3 | - | M | Remove southern branch at 1m growing through fence. | High | High | 40+ | A1 | 7.1 | 157.5 |
| G231 | Horse chestnut, sycamore | 14 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Group along boundary. Species planted alternately, 1 chestnut missing. Minor deadwood, pruning wounds | Medium | Medium | 20+ | B2 | 6.0 | 113.1 |
| T232 | Chestnut (Horse) | 15 | - | 660 | - | 6 | - | 7 | - | 5 | - | 5 | - | 2.5 | - | West | 0.5 | - | M | Weak branching structure, rubbing branches. Cavity observed at 2.5m north west stem. | Medium | Medium | 20+ | C1 | 7.9 | 197.1 |
| T233 | Maple | 13 | - | 380 | - | 4 | - | 5 | - | 2 | - | 2.5 | - | 4 | - | South | 4 | - | M | Suppressed. Deadwood. Abscised branches due to shading out. | Medium | Low | 20+ | C1 | 4.6 | 65.3 |
| T234 | Chestnut (Horse) | 12 | - | 360 | - | 3 | - | 2 | - | 4 | - | 3 | - | 2 | - | South | 4 | - | M | Fork at 2m. Cavity at 2m on western stem. | Medium | Medium | 20+ | C1 | 4.3 | 58.6 |
| G235 | Cypress | 18 | - | 380 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | Mutual suppression. Split branches. | High | Medium | 20+ | C2 | 4.6 | 65.3 |
| G236 | Hawthorn | 4 | - | 150 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Suppressed by conifers. Previously pollarded. | Medium | Low | 20+ | C2 | 1.8 | 10.2 |
| T237 | Birch (Silver) | 10 | - | 250 | - | 3.5 | - | 2 | - | 2 | - | 2.5 | - | 3 | - | South | 2 | - | M | Leans north. Minor deadwood. Adjacent underground tanks. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 |
| G238 | Chestnut (Horse) | 13 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Adjacent paths and underground chambers. Generally poor. | Medium | Low | 20+ | C2 | 4.8 | 72.4 |
| T239 | Chestnut (Horse) | 13 | - | 440 | - | 4 | - | 5 | - | 4 | - | 5 | - | 3 | - | West | 1.5 | - | M | In decline with hanging dead leader in canopy. Suffering from chestnut canker. Cavities and deadwood. | Low | Low | <10 | U | 5.3 | 87.6 |
| T240 | Cotoneaster | 7 | - | 260 | - | 5 | - | 2 | - | 4 | - | 5 | - | N/A | - | N/A | 2.5 | - | M | Adjacent to and growing from base of building. Impractical to retain. | Medium | Medium | 10+ | C2 | 3.1 | 30.5 |
| T241 | Cypress (Leyland) | 7.5 | - | 260 | - | 2.5 | - | 2.5 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Allot of dead foliage. Close to building. Impractical to retain. Coppiced goat willow at base. | Medium | Medium | 10+ | C2 | 3.1 | 30.5 |
| G242 | Ash (Common) | 5 | - | 100 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 2 | - | SM | Growing on concrete rings and Tarmac in car park. Poor. | Medium | Low | 10+ | C2 | 1.2 | 4.5 |
| T243 | Birch (Silver) | 5 | - | 100 | - | 1.5 | - | 1.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | 0.5 | - | Y | Poor, leaning. Growing from Tarmac. | Medium | Low | 10+ | C2 | 1.2 | 4.5 |
| G244 | Chestnut (Horse) | 13 | - | 450 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Cavities, deadwood. Fair to poor. | Medium | Medium | 20+ | C2 | 5.4 | 91.6 |
| G245 | Chestnut (Horse) | 10 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Multiple pruning wounds and coalescent decay. Bleeding canker observed. Deadwood. Poor condition. | Low | Low | <10 | U | 4.2 | 55.4 |
| G246 | Ash, birch, cherry | 10 | - | 250 | - | 2 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | SM | In raised planters in parking court. Impractical to retain. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 |
| T247 | Birch (Silver) | 8.5 | - | 184 | - | 3 | - | 3 | - | 3 | - | 2 | - | N/A | - | N/A | 0.5 | - | EM | Growing out from base of building. Impractical to retain. | Medium | Medium | 10+ | C2 | 2.2 | 15.3 |
| G248 | Chestnut (Horse) | 11 | - | 530 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Multiple cavities observed. Deadwood. Weak unions. | Medium | Medium | 10+ | C2 | 6.4 | 127.1 |
| G249 | Chestnut (Horse) | 11 | - | 480 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | One tree completely dead, woodpecker holes, fallen branches - remove. Cavities and pruning wounds in other | Medium | Medium | 10+ | C2 | 5.8 | 104.2 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|-------------------|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|------|-------|
| T250 | Sycamore | 8 | - | 224 | - | 2.5 | - | 3 | - | 3 | - | 3 | - | 0.5 | - | South east | 1 | - | M | Growing out from base of building. Impractical to retain. | Medium | Medium | 10+ | C2 | 2.7 | 22.6 |
| T251 | Sycamore | 8 | - | 224 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | SM | Growing in fenced compound. Suppressed and generally poor. | Medium | Medium | 10+ | C2 | 2.7 | 22.6 |
| T252 | Birch (Silver) | 10 | - | 400 | - | 5 | - | 5 | - | 6 | - | 5 | - | 2.5 | - | North west | 1 | - | M | Remove lower branches and raise canopy to 2.5m. Bark damage noted. | Medium | High | 20+ | B2 | 4.8 | 72.4 |
| T253 | Lime (Common) | 13 | - | 400 | - | 5 | - | 5 | - | 5 | - | 5 | - | 2 | - | West | 0 | - | M | Remove epicormic growth at base. Drooping branches to ground level. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 |
| T254 | Sycamore | 7 | - | 170 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 1.5 | - | SM | Growing in raised area, concrete surrounds. | Medium | Medium | 10+ | C1 | 2.0 | 13.1 |
| T255 | Birch (Silver) | 13 | - | 350 | - | 3 | - | 3 | - | 3 | - | 3 | - | 2 | - | South | 0 | - | M | Ivy on stem. In raised planting area. | Medium | High | 20+ | B1 | 4.2 | 55.4 |
| T256 | Birch (Silver) | 11 | - | 230 | - | 3 | - | 3 | - | 1 | - | 5 | - | 2 | - | East | 1 | - | M | In raised planting area. Stem leaning west. | Medium | Medium | 20+ | C1 | 2.8 | 23.9 |
| T257 | Hawthorn | 4 | - | 150 | - | 2.5 | - | 1.5 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Leans to north. Suckering from base. Decay. Poor. | Low | Low | 10+ | C1 | 1.8 | 10.2 |
| T258 | Whitebeam | 8 | - | 410 | - | 4.5 | - | 4 | - | 6 | - | 6 | - | N/A | - | N/A | 1.5 | - | M | Close to building, canopy touching building to east. Could be crown thinned. | Medium | High | 20+ | B1 | 4.9 | 76.1 |
| T259 | Sycamore | 8 | - | 330 | - | 4 | - | 4.5 | - | 4 | - | 4 | - | 2 | - | South | 2.5 | - | M | Cracks in bark, fibre buckling. | Medium | Medium | 20+ | B1 | 4.0 | 49.3 |
| G260 | Hawthorn | 4.5 | - | 175 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Historically pollarded. Poor group. | Medium | Medium | 20+ | C2 | 2.1 | 13.9 |
| T261 | Cypress (Lawson) | 16 | - | 900 | - | 4.5 | - | 4.5 | - | 5 | - | 4 | - | N/A | - | N/A | 0.5 | - | M | Good shape. Slight foliage dieback to north observed. Could not see why from ground. | Medium | Medium | 20+ | B1 | 10.8 | 366.5 |
| T262 | Cherry (Wild) | 7 | - | 300 | - | 3 | - | 3.5 | - | 4 | - | 1.5 | - | N/A | - | N/A | 0.5 | - | M | Growing out from base of building. Impractical to retain. | Medium | Medium | 20+ | C1 | 3.6 | 40.7 |
| T263 | Sycamore | 6 | - | 212 | - | 3 | - | 3 | - | 3 | - | 2.5 | - | 1.5 | - | East | 1.5 | - | M | Growing out from base of building. Impractical to retain. | Medium | Medium | 20+ | C1 | 2.5 | 20.4 |
| G264 | Lime (Common) | 11 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Limes have epicormic growth at base. Suppressed, poor shape. Minor deadwood. | Medium | Medium | 20+ | C2 | 4.8 | 72.4 |
| T265 | Sycamore | 16 | - | 770 | - | 7 | - | 6 | - | 8 | - | 8 | - | 3.5 | - | North | 2 | - | M | Minor deadwood. | Medium | Medium | 20+ | B1 | 9.2 | 268.3 |
| T266 | Cherry (Wild) | 6 | - | 280 | - | 1 | - | 2 | - | 4 | - | 3 | - | 2 | - | West | 2 | - | M | Dead. Habitat value. Lots of holes. | Low | Low | <10 | U | 3.4 | 35.5 |
| G267 | Lime, maple | 15 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Central maple cavity on stem and dead branches. Recommend remove. Not safe. Lines need cleaning out, | Medium | Medium | 10+ | C2 | 4.8 | 72.4 |
| T268 | Birch (Silver) | 8 | - | 100 | - | 0.5 | - | 2.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | 0.5 | - | EM | Adjacent building in hard standing, leaning south. | Low | Medium | 10+ | C1 | 1.2 | 4.5 |
| T269 | Lime (Common) | 15 | - | 600 | - | 5 | - | 5 | - | 4 | - | 6 | - | 2.5 | - | West | 0.5 | - | M | Epicormic growth at base. Clean out canopy. | Medium | Medium | 20+ | B1 | 7.2 | 162.9 |
| T270 | Lime (Common) | 15 | - | 400 | - | 4 | - | 5.5 | - | 6 | - | 5 | - | 3 | - | South east | 0.5 | - | M | Deadwood, woodpecker holes. Broken branches. | Medium | Medium | 10+ | C1 | 4.8 | 72.4 |
| T271 | Whitebeam | 8 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Good shape. Northern tree touching building. | Medium | Medium | 20+ | B2 | 3.0 | 28.3 |
| T272 | Cherry (Wild) | 7 | - | 206 | - | 2 | - | 4 | - | 2 | - | 3 | - | N/A | - | N/A | 1 | - | M | In raised bed, next to man hole. Impractical to retain. | Medium | Medium | 10+ | C1 | 2.5 | 19.2 |
| G273 | Lime, sycamore | 15 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Clean through deadwood. Remove ivy and epicormic growth. Potential bat habitat, holes observed. No works to be done | Medium | Medium | 20+ | B2 | 4.8 | 72.4 |
| G274 | Cotoneaster | 7.5 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Three trees, two dead. Adjacent building. Poor and touching building. Impractical to retain. | Medium | Medium | 10+ | C2 | 3.6 | 40.7 |
| G275 | Chestnut (Horse) | 12 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | All stood in brick retaining edge. Remove deadwood and ivy. Clean through, raise canopy to 2m. Most northern tree | Medium | Medium | 20+ | B2 | 6.0 | 113.1 |
| T276 | Cotoneaster | 9 | - | 303 | - | 3.5 | - | 4 | - | 5 | - | 3 | - | 1.5 | - | South east | 2 | - | M | Touching building to south and east. Clean through canopy. | Medium | Medium | 10+ | C1 | 3.6 | 41.6 |
| T277 | Chestnut (Horse) | 13 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | 5 trees. Trees 2 and 5 suffering from bleeding canker, recommend remove. Monitor three remaining trees. | Medium | Medium | 10+ | C2 | 6.0 | 113.1 |
| T278 | Apple | 6 | - | 330 | - | 5 | - | 4 | - | 2 | - | 4 | - | 2 | - | North | 1 | - | M | Heavily suppressed to east. Pruning wounds. Poor shape. | Medium | Medium | 10+ | C1 | 4.0 | 49.3 |
| G279 | Hawthorn | 4.5 | - | 224 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Poor. Historically pollarded. | Medium | Medium | 10+ | C2 | 2.7 | 22.6 |
| T280 | Hornbeam | 12 | - | 380 | - | 5 | - | 5 | - | 5 | - | 5 | - | 2 | - | North west | 0.5 | - | M | Minor broken branches to north. | High | High | 40+ | B1 | 4.6 | 65.3 |
| G281 | Cypress (Leyland) | 15 | - | 550 | - | 5 | - | 3 | - | 5 | - | 3 | - | N/A | - | N/A | 3 | - | M | 2 trees. Good shape. | High | High | 20+ | B2 | 6.6 | 136.9 |
| G282 | Cypress (Lawson) | 14 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 9 trees. Southern tree growing through concrete. | High | High | 20+ | C2 | 4.8 | 72.4 |
| G283 | Lime (Common) | 11 | - | 480 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Several cavities, minor deadwood. | Medium | Medium | 20+ | B2 | 5.8 | 104.2 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|--------------------------------|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|-----|-------|
| T284 | Chestnut (Horse) | 11 | - | 650 | - | 6 | - | 5 | - | 5 | - | 4 | - | 3 | - | East | 2 | - | M | Chestnut has split branches, bark peeling at base, weak union, epicormic growth. Bark necrosis. Monitor | Low | Medium | 20+ | C1 | 7.8 | 191.2 |
| T285 | Maple (Norway) | 12 | - | 520 | - | 4.5 | - | 4.5 | - | 5 | - | 4.5 | - | 2 | - | South | 2 | - | M | Minor deadwood. Good shape. | Medium | Medium | 20+ | B1 | 6.2 | 122.3 |
| G286 | Horse chestnut x3, sycamore x2 | 13 | - | 550 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Monitor chestnuts for canker. Minor deadwood observed. | - | - | 20+ | B2 | 6.6 | 136.9 |
| T287 | Chestnut (Horse) | 13 | - | 550 | - | 6 | - | 5 | - | 4 | - | 4 | - | 2.5 | - | North west | 2 | - | M | Severe bark necrosis. Chestnut canker. Dying. Remove | - | - | <10 | U | 6.6 | 136.9 |
| T288 | Maple | 13 | - | 510 | - | 6 | - | 5 | - | 6 | - | 5 | - | 2 | - | South | 2 | - | M | Bark damage at base. Cavity 2m north. Removing branches touching adjacent fence | - | - | 20+ | B1 | 6.1 | 117.7 |
| T289 | Maple | 13 | - | 450 | - | 6 | - | 6 | - | 4 | - | 6 | - | 2 | - | West | 2 | - | M | Remove branches touching adjacent fence. Clean out deadwood from canopy. Bark damage at base. Remove | - | - | 10+ | C1 | 5.4 | 91.6 |
| G290 | Maple, leylandii | 13 | - | 500 | - | 6 | - | 6 | - | 7 | - | 5 | - | 2 | - | East | 0.5 | - | M | Ivy into canopy of maple. Remove conifers at base. | - | - | 40+ | B2 | 6.0 | 113.1 |
| G291 | Cypress (Lawson) | 2.5 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | Topped at 2.5m. | - | - | <10 | U | 4.8 | 72.4 |
| T292 | Chestnut (Horse) | 11 | - | 450 | - | 3 | - | 3.5 | - | 4 | - | 6 | - | 2 | - | West | 1 | - | M | Branches growing through fence - needs cutting. Minor ivy. Growing against fence. Growing into canopy of chestnut and | - | - | 10+ | C1 | 5.4 | 91.6 |
| G293 | Cypress (Lawson) | 9 | - | 335 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | | - | - | 10+ | C2 | 4.0 | 50.9 |
| G294 | Maple (Norway) | 11 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | 5 trees. Generally good. Remove basal growth from tree three. Raise canopies to 2m. | High | High | 20+ | B2 | 4.8 | 72.4 |
| T295 | Cypress (Leyland) | 8 | - | 300 | - | 3 | - | 1.5 | - | 3 | - | 2.5 | - | 2 | - | North west | 1 | - | M | Split hanging branch 3m north. Bark damage at base. | Medium | Low | 10+ | C1 | 3.6 | 40.7 |
| T296 | Maple (Norway) | 12 | - | 450 | - | 6 | - | 5.5 | - | 5 | - | 5.5 | - | 3 | - | North | 2.5 | - | M | Weak fork at 3m. | Medium | Medium | 20+ | B1 | 5.4 | 91.6 |
| T297 | Maple (Norway) | 12 | - | 600 | - | 6 | - | 6 | - | 7 | - | 7 | - | N/A | - | N/A | 1 | - | M | Forks at 2m. Raise canopy to 2m. Minor deadwood. Cable through canopy. Good tree. Kerb and Tarmac to east. | High | High | 40+ | A1 | 7.2 | 162.9 |
| T298 | Cherry (Wild) | 10 | - | 600 | - | 7 | - | 6 | - | 6 | - | 6 | - | N/A | - | N/A | 0 | - | M | Crown thin recommended. Recommend aerial inspection. Clematis growing into canopy. Needs cleaning through. | Low | Medium | 10+ | C1 | 7.2 | 162.9 |
| T299 | Cherry (Wild) | 6 | - | 100 | - | 3 | - | 2 | - | 1 | - | 3.5 | - | 1.5 | - | North | 1 | - | SM | Brambles into canopy. Growing adjacent fencing and concrete pad. Branches hacked back. | Medium | Medium | 10+ | C1 | 1.2 | 4.5 |
| G300 | Chestnut (Horse) | 13 | - | 450 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | 3 trees. Eastern tree remove due to decline and structural weaknesses caused by bleeding canker. Middle tree showing | Medium | Medium | 10+ | C2 | 5.4 | 91.6 |
| T301 | Cypress (Lawson) | 15 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 6 trees. Kerb to south. | High | High | 20+ | C2 | 4.8 | 72.4 |
| G302 | Sycamore | 8 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | SM | 2 trees in courtyard, locked an unable to access. Growing from base of buildings. Impractical to retain. | Medium | Medium | 10+ | C2 | 3.0 | 28.3 |
| G303 | Cypress | 15 | - | 450 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | 2 trees. Kerb and road to south. Close to building. Good shape. | High | High | 20+ | B2 | 5.4 | 91.6 |
| T304 | Cypress | 15 | - | 450 | - | 4.5 | - | 3 | - | 4 | - | 5 | - | N/A | - | N/A | 2.5 | - | M | Kerb and road to south. Slight lean to north. | Medium | High | 20+ | B1 | 5.4 | 91.6 |
| T305 | Whitebeam | 6 | - | 300 | - | 3.5 | - | 2.5 | - | 4 | - | 2 | - | 2.5 | - | South east | 2 | - | M | Remove suckers at base. Weak fork with included bark at 2.5m. | Medium | Medium | 20+ | C1 | 3.6 | 40.7 |
| T306 | Whitebeam | 8 | - | 541 | - | 5 | - | 4 | - | 4 | - | 4 | - | 2 | - | East | 2 | - | M | Multiple cavities 1.8m north east. Poor forking structure. | Medium | High | 10+ | C1 | 6.5 | 132.3 |
| T307 | Whitebeam | 9 | - | 600 | - | 5 | - | 5 | - | 6 | - | 5.5 | - | N/A | - | N/A | 2 | - | M | Forks at 2m. Minor deadwood. Good tree. | High | High | 20+ | B1 | 7.2 | 162.9 |
| G308 | Maple | 6 | - | 200 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | 5 trees. Located in parking court island bed. Suckering from base. Poor shape. | Medium | Low | 10+ | C2 | 2.4 | 18.1 |
| T309 | Maple | 8 | - | 350 | - | 4.5 | - | 4.5 | - | 4 | - | 4.5 | - | N/A | - | N/A | 0.5 | - | M | Remove suckers. Poor shape. In parking court island bed. | Medium | Medium | 10+ | C1 | 4.2 | 55.4 |
| T310 | Maple | 8 | - | 350 | - | 4 | - | 4 | - | 5 | - | 4.5 | - | N/A | - | N/A | 0.5 | - | M | In parking court island bed. Weak forks observed. Poor shape. | Medium | Medium | 10+ | C1 | 4.2 | 55.4 |
| G311 | 7 Poplars, 1 Maple | 12 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | 8 trees. Poor generally. Severe bark damage. Several cut down. | Medium | Medium | 10+ | C2 | 3.0 | 28.3 |
| T312 | Chestnut (Horse) | 14 | - | 750 | - | 7 | - | 6 | - | 6 | - | 7 | - | 3 | - | South | 0.5 | - | M | Bark necrosis. Hazard beam at 3m south, 3m north. Main leader cambium split and bark damage. Early signs of | Low | Medium | 10+ | C1 | 9.0 | 254.5 |
| G313 | Poplar stumps | 2 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | N/A | - | M | Poplar stumps regrowth from stumps set in Tarmac. | Low | Low | <10 | U | 3.6 | 40.7 |
| T314 | Sycamore | 9 | - | 283 | - | 3.5 | - | 4 | - | 3 | - | 3 | - | 1.5 | - | East | 1.5 | - | M | Growing from concrete steps, adjacent building. Impractical to retain. | Medium | Medium | 10+ | C1 | 3.4 | 36.2 |
| T315 | Maple | 7 | - | 200 | - | 3 | - | 3 | - | 3 | - | 3 | - | 2 | - | North | 1.5 | - | M | Suckers at base. Large pruning wound at base. | Medium | Medium | 10+ | C1 | 2.4 | 18.1 |
| T316 | Pear | 6.5 | - | 100 | - | 1.5 | - | 2.5 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Create clear stem to 2m. Remove ivy. Growing adjacent steps to building. | Medium | Medium | 10+ | C1 | 1.2 | 4.5 |
| T317 | Maple | 12 | - | 400 | - | 4.5 | - | 5 | - | 4 | - | 5 | - | 2 | - | South | 2 | - | M | Minor deadwood. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|-----------------------------|----|---|------|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|---|------------|-----|---|----|--|--------|--------|-----|----|------|-------|
| G318 | Maple | 6 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Historically topped at 3m with regrowth. Dieback, pruning wounds. Three trees. Middle tree woodpecker holes and | Medium | Low | <10 | U | 3.6 | 40.7 |
| T319 | Chestnut stump | 4 | - | 600 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | N/A | - | M | Dead stump with ganoderma at base. | Low | Low | <10 | U | 7.2 | 162.9 |
| G320 | Maple | 9 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Three trees. Minor deadwood. Major bark damage to southern tree, heartwood exposed. | Medium | Medium | 20+ | B2 | 3.6 | 40.7 |
| G321 | Maple | 8 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 6 trees. In parking court island bed. Minor deadwood. Minor bark damage to tree 4 (middle tree). | Medium | Medium | 20+ | B2 | 3.6 | 40.7 |
| G322 | Maple | 8 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 3 trees. Mutual suppression. Minor deadwood. Several broken branches need tidying. Eastern tree split branch at | Medium | Medium | 20+ | C2 | 3.6 | 40.7 |
| T323 | Sycamore | 9 | - | 350 | - | 4 | - | 4 | - | 4 | - | 3.5 | - | N/A | - | N/A | - | N/A | 0.5 | - | M | Coppiced regrowth. Growing from concrete pad, close to adjacent building. Parking court to north. | Medium | Medium | 10+ | C2 | 4.2 | 55.4 |
| G324 | Maple | 8 | - | 250 | - | 4 | - | 6 | - | 4 | - | 4 | - | N/A | - | N/A | - | N/A | 2.5 | - | M | 2 trees. Growing in parking court island bed. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 |
| G325 | Maple | 8 | - | 250 | - | 4 | - | 5 | - | 2 | - | 2 | - | N/A | - | N/A | - | N/A | 1.5 | - | M | 2 trees. In parking court island bed. Lopped at 4m. Dieback from pruning wounds in upper canopy. Poor shape. | Medium | Low | 10+ | C2 | 3.0 | 28.3 |
| G326 | Sycamore | 8 | - | 346 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | - | N/A | 1 | - | M | Growing adjacent building, growing from areas of concrete. Pruning wounds, poor shape, debris at base. Impractical to | Medium | Medium | 10+ | C2 | 4.2 | 54.3 |
| G327 | Sycamore | 9 | - | 354 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | - | N/A | 2 | - | M | 2 trees. western tree poor shape adjacent building. Growing into building to north. Risings embedded into trunk. Hanging | Low | Low | 10+ | C2 | 4.2 | 56.6 |
| T328 | Cryptomeria ? | 9 | - | 361 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | - | N/A | 0 | - | M | Poor suppressed form. Deadwood and dead foliage to east. Growing adjacent building. Impractical to retain. | Medium | Low | 10+ | C2 | 4.3 | 58.8 |
| G329 | Cypress x 4 | 9 | - | 200 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | - | N/A | 0 | - | M | Growing adjacent building. Dead foliage, suppressed to west by building. Elder bush growing through group. Impractical to | Medium | Low | 10+ | C2 | 2.4 | 18.1 |
| T330 | Chestnut (Horse) | 11 | - | 450 | - | 6.5 | - | 6 | - | 6 | - | 7 | - | 2.5 | - | West | - | West | 2 | - | M | Lower branches pruned and moderate deadwood. Few stains, monitor for bleeding canker. Clean through canopy. | Medium | Medium | 20+ | C1 | 5.4 | 91.6 |
| T331 | Beech (Common) | 12 | - | 500 | - | 5 | - | 5 | - | 5 | - | 7 | - | N/A | - | N/A | - | N/A | 1.5 | - | M | Growing in confined circular planter with girdled roots. Suppressed to east by conifers. Minor deadwood. | Low | Medium | 20+ | C1 | 6.0 | 113.1 |
| T332 | Chestnut (Horse) | 12 | - | 500 | - | 5 | - | 3 | - | 5 | - | 5.5 | - | 2.5 | - | South | - | South | 2 | - | M | Cavity at 3m east. Brown/black staining indication of bleeding canker. Growing into bank of air raid shelter. In decline and | Low | Low | 10+ | C1 | 6.0 | 113.1 |
| G333 | Beech x1, horse chestnut x2 | 12 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | - | N/A | 2 | - | M | Chestnuts generally poor and in decline. Southern chestnut showing signs of bleeding canker with brown/black stains. | Low | Low | 10+ | C2 | 6.0 | 113.1 |
| G334 | Ash (Common) | 14 | - | 400 | - | 6 | - | 8 | - | 9 | - | 9 | - | N/A | - | N/A | - | N/A | 2 | - | M | 3 trees in bed planting with ornamental shrubs. Ivy on middle tree. Trees to east and west suppressed. | Medium | Medium | 20+ | B2 | 4.8 | 72.4 |
| H335 | Laurel (Cherry) | 1 | - | 50 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | - | N/A | 0 | - | M | 0.5m wide. Encloses parking court. | N/A | N/A | 10+ | C2 | 0.6 | 1.1 |
| T336 | Hornbeam | 16 | - | 600 | - | 7 | - | 7 | - | 6 | - | 6 | - | N/A | - | N/A | - | N/A | 2.5 | - | M | Forks at 2m. Fallen branch ripped out from stem on northern side. Good shape. Minor deadwood. | High | High | 40+ | A1 | 7.2 | 162.9 |
| T337 | Beech (Common) | 18 | - | 750 | - | 9 | - | 8.5 | - | 9 | - | 6 | - | N/A | - | N/A | - | N/A | 2.5 | - | M | Cherry tree growing in possible cavity at 2.5m. Multiple pruning wounds, well occluded. | High | High | 40+ | A1 | 9.0 | 254.5 |
| T338 | Whitebeam | 11 | - | 750 | - | 5 | - | 5 | - | 5 | - | 5.5 | - | N/A | - | N/A | - | N/A | 2 | - | OM | Dead with fungal fruiting bodies high into tree, looks to be saprophyte. Tree looks to be dead, cavities, splits and cracks. | Low | Low | <10 | U | 9.0 | 254.5 |
| T339 | Whitebeam | 10 | - | 600 | - | 6 | - | 5.5 | - | 5 | - | 5 | - | N/A | - | N/A | - | N/A | 2 | - | OM | Most easterly stem extensive damaged bark and decay at 2m east. Plant growing from decaying wood. Pruning wounds, | Low | Low | 10+ | C1 | 7.2 | 162.9 |
| G340 | Cypress sp | 4 | - | 150 | - | 1.5 | - | 1.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | - | N/A | 0 | - | M | Adjacent education health centre. | Medium | Medium | 20+ | C2 | 1.8 | 10.2 |
| G341 | Birch (Silver) | 12 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | - | N/A | 0.5 | - | M | 8 Birch. Exposed roots. Sixth tree from west poor condition. | Medium | Medium | 20+ | B2 | 3.6 | 40.7 |
| T342 | Cherry plum | 6 | - | 210 | - | 3 | - | 3 | - | 4 | - | 1.5 | - | 2 | - | South east | - | South east | 0.5 | - | M | Decay in trunk at 0.5m west. Lean to east. | Medium | Medium | 10+ | C1 | 2.5 | 20.0 |
| T343 | Birch (Silver) | 11 | - | 400 | - | 5 | - | 4 | - | 5 | - | 6 | - | 3 | - | South west | - | South west | 1.5 | - | M | Lean to north east. | Medium | High | 20+ | B1 | 4.8 | 72.4 |
| T344 | Cherry plum | 4 | - | 190 | - | 4 | - | 3 | - | 3 | - | 2.5 | - | 1.5 | - | East | - | East | 1 | - | M | Lean to north east. Decay in trunk at base. | Low | Medium | 10+ | C1 | 2.3 | 16.3 |
| T345 | Birch (Silver) | 11 | - | 500 | - | 6 | - | 5 | - | 3 | - | 5 | - | 4 | - | North west | - | North west | 0.5 | - | M | Slight lean to north west. | Medium | Medium | 20+ | B1 | 6.0 | 113.1 |
| T346 | Birch (Silver) | 11 | - | 250 | - | 3 | - | 2.5 | - | 3 | - | 3 | - | N/A | - | N/A | - | N/A | 0.5 | - | M | Bark damage at base. Limb ripped out 2.5m east, decay. Twisted form. | Medium | Medium | 20+ | C1 | 3.0 | 28.3 |
| T347 | Birch (Silver) | 11 | - | 340 | - | 4 | - | 4.5 | - | 4 | - | 3.5 | - | 3.5 | - | North west | - | North west | 0.5 | - | M | Pointy nosed ribs observed, indication of internal cracks. Exposed roots. | Medium | Medium | 20+ | C1 | 4.1 | 52.3 |
| T348 | Sycamore | 18 | - | 1000 | - | 9 | - | 9 | - | 9 | - | 9 | - | N/A | - | N/A | - | N/A | 4 | - | M | Forks at 3m. Minor pruning wounds. Minor deadwood. Typical of species and age. | High | High | 40+ | A1 | 12.0 | 452.4 |
| T349 | Birch (Silver) | 9 | - | 330 | - | 7 | - | 2 | - | 6 | - | 4 | - | 3 | - | West | - | West | 0.5 | - | M | Lean to east. Poor shape. | Medium | Medium | 20+ | C1 | 4.0 | 49.3 |
| T350 | Birch (Silver) | 8 | - | 270 | - | 2.5 | - | 4.5 | - | 5 | - | 6 | - | 2.5 | - | West | - | West | 0.5 | - | M | Minor bark damage at base. Minor deadwood. | Medium | Medium | 20+ | C1 | 3.2 | 33.0 |
| T351 | Birch (Silver) | 12 | - | 367 | - | 5 | - | 4 | - | 5 | - | 4.5 | - | N/A | - | N/A | - | N/A | 1.5 | - | M | Exposed roots. Minor hanging deadwood. | Medium | High | 20+ | C1 | 4.4 | 61.1 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|---------------------|----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|-----|-------|
| T352 | Oak (English) | 10 | - | 180 | - | 3 | - | 3 | - | 3 | - | 2.5 | - | 1.5 | - | South | 1.5 | - | Y | Uniform shape. Good tree. | High | High | 40+ | A1 | 2.2 | 14.7 |
| G353 | Whitebeam | 5 | - | 250 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 2 | - | M | 15 trees in a line within island in car park. | High | High | 20+ | B2 | 3.0 | 28.3 |
| T354 | Birch (Silver) | 8 | - | 331 | - | 5 | - | 3 | - | 6 | - | 5 | - | 3 | - | North | 1.5 | - | M | Ivy on trunk. In raised bed adjacent building. Touching building to west. | High | High | 20+ | B1 | 4.0 | 49.6 |
| T355 | Apple | 5 | - | 150 | - | 2.5 | - | 1.5 | - | 5 | - | 3 | - | 2 | - | South | 0.5 | - | M | Heavily suppressed by building. Remove to benefit birch. | Medium | Medium | 10+ | C1 | 1.8 | 10.2 |
| T356 | Whitebeam | 6 | - | 250 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 2 | - | M | 12 trees in a line. In grass island within parking area. | Medium | Medium | 10+ | C2 | 3.0 | 28.3 |
| G357 | Cypress sp. | 14 | - | 660 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Combination of single and multi stem. Road to east. | High | High | 10+ | C2 | 7.9 | 197.1 |
| G358 | Cypress sp. | 5 | - | 200 | - | 3 | - | 1.5 | - | 2 | - | 3 | - | N/A | - | N/A | 0.5 | - | M | Poor. Previously suppressed to south. Sparse foliage. Paving and kerbs at base. | Medium | Low | 10+ | C2 | 2.4 | 18.1 |
| G359 | Maple (Norway) | 10 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | 2 trees. New pruning wounds, girdled roots. | High | Medium | 20+ | C2 | 4.2 | 55.4 |
| G360 | Maple (Norway) | 10 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | 4 trees. New pruning wounds, girdled roots. Trees 1 and 3 physiologically poor, poor structure and sparse foliage. | High | Medium | 20+ | C2 | 4.2 | 55.4 |
| G361 | Maple (Norway) | 10 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | 8 trees. Recent pruning observed. Girdled roots, some bark damage throughout group. | High | Medium | 20+ | C2 | 4.2 | 55.4 |
| G362 | Maple (Norway) | 8 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 6 trees. All have minor pruning wounds, some with minor bark damage at base. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 |
| T363 | Maple (Norway) | 8 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | 5 trees. Minor deadwood throughout. Three trees very sparse canopy. | High | Medium | 20+ | C2 | 4.2 | 55.4 |
| T364 | Maple sp. (sugar) | 8 | - | 300 | - | 4 | - | 4 | - | 4 | - | 4 | - | 2 | - | West | 1.5 | - | M | In a raised planter within parking area. Splitting bark, epicormic growth removed from base. Black exudate on bark. | Medium | Low | 10+ | C1 | 3.6 | 40.7 |
| T365 | Maple sp. (sugar) | 6 | - | 150 | - | 3 | - | 3 | - | 2 | - | 3 | - | 2 | - | South west | 2 | - | M | In raised planter. Poor shape. Leans to east, branch removed. | Medium | Medium | 10+ | C1 | 1.8 | 10.2 |
| T366 | Sycamore | 8 | - | 257 | - | 4 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 0 | - | M | Self seeded into brick car park, located at edge of raised planter. Poor. | Medium | Medium | 10+ | C1 | 3.1 | 30.0 |
| G367 | Maple (Norway) | 12 | - | 420 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 4 trees. On grass bank. Minor pruning wounds, exposed roots. Southern tree deadwood, poor shape, poor crown | Medium | Medium | 20+ | C2 | 5.0 | 79.8 |
| G368 | Maple (Norway) | 9 | - | 300 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | 3 trees. Central re really poor, suppressed - remove. All in parking area. | Medium | Medium | 20+ | C2 | 3.6 | 40.7 |
| T369 | Maple (Cappadocian) | 9 | - | 310 | - | 3.5 | - | 4 | - | 4 | - | 4 | - | 1.5 | - | East | 2 | - | M | In parking area. Fair. | Medium | Medium | 20+ | C1 | 3.7 | 43.5 |
| T370 | Maple (Cappadocian) | 10 | - | 310 | - | 4 | - | 4 | - | 3 | - | 3 | - | 2 | - | South west | 2 | - | M | In raised planter. Weak fork at 2m. Minor bark damage. | Medium | Medium | 20+ | C1 | 3.7 | 43.5 |
| G371 | Cypress (Leyland) | 12 | - | 427 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | 3 trees. Foliage sparse on south east side. | High | Medium | 20+ | C2 | 5.1 | 82.6 |
| G372 | Cedar (Western Red) | 8 | - | 175 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | 2 trees, growing on mound. Good shape. | High | High | 20+ | B2 | 2.1 | 13.9 |
| T373 | Cherry (Wild) | 10 | - | 186 | - | 4 | - | 4 | - | 4 | - | 2 | - | 2 | - | East | 1.5 | - | M | Suppressed by building to west. Touching building. Weak fork at base. | Medium | Medium | 20+ | C1 | 2.2 | 15.7 |
| T374 | Maple sp. (sugar) | 6 | - | 200 | - | 3 | - | 3 | - | 3 | - | 3 | - | 2 | - | East | 1.5 | - | M | In raised planter. Poor. Minor bark damage. | Medium | Low | 10+ | C1 | 2.4 | 18.1 |
| T375 | Maple sp. (sugar) | 6 | - | 200 | - | 3 | - | 3 | - | 3 | - | 3 | - | 1.5 | - | East | 1.5 | - | M | In raised planter. Poor. Minor bark damage. | Medium | Low | 10+ | C1 | 2.4 | 18.1 |
| T376 | Maple sp. (sugar) | 6 | - | 200 | - | 3 | - | 3 | - | 4 | - | 3 | - | 1.5 | - | South | 1.5 | - | M | In raised planter. Poor. Minor bark damage. Slight lean to east. | Medium | Low | 10+ | C1 | 2.4 | 18.1 |
| G377 | Cedar (Western Red) | 10 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | On slight grass bank. Good shape. | High | High | 40+ | B2 | 3.0 | 28.3 |
| G378 | Cypress (Leyland) | 12 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | On slight grass bank. Good shape. | High | High | 20+ | C2 | 6.0 | 113.1 |
| G379 | Sycamore, maple | 12 | - | 375 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | Recent pruning works observed. Northern maple suppressed and leaning north, recommend remove. Cohesive group. | Medium | Medium | 20+ | B2 | 4.5 | 63.6 |
| G380 | Maple (Norway) | 12 | - | 330 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 3 trees. Remove central tree to better others. Deadwood on western tree. Poor pruning techniques. Crossing branches | Medium | Medium | 20+ | C2 | 4.0 | 49.3 |
| T381 | Maple (Norway) | 10 | - | 245 | - | 3.5 | - | 4 | - | 2 | - | 2.5 | - | N/A | - | N/A | 0.5 | - | M | Remove to benefit other trees. Suppressed, bark damage. | Medium | Medium | 10+ | C1 | 2.9 | 27.1 |
| T382 | Maple (Norway) | 14 | - | 480 | - | 5 | - | 5 | - | 5 | - | 6 | - | 2 | - | South | 0.5 | - | M | Nice tree. Minor deadwood. | Medium | Medium | 20+ | B1 | 5.8 | 104.2 |
| G383 | Maple (Norway) | 10 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | 4 trees. Northern trees heavily infested with ivy. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 |
| G384 | Maple (Norway) | 7 | - | 150 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | SM | Ivy into canopy. Deadwood. Leans east. Bark damage. Poor. | Medium | Medium | 20+ | C2 | 1.8 | 10.2 |
| T385 | Maple sp. (sugar) | 7 | - | 150 | - | 2.5 | - | 4 | - | 3 | - | 2.5 | - | 2 | - | South | 2 | - | SM | Lost its leader. Rose growing into canopy. Suckers at base. | Medium | Medium | 10+ | C1 | 1.8 | 10.2 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|-------|---|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|-----|-----|-----|------------|---|--------|--|--|--------|--------|------|-----|-------|------|
| T386 | Hawthorn | 4 | - | 200 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Growing adjacent building. Fair. | Medium | Medium | 10+ | C1 | 2.4 | 18.1 | | | |
| T387 | Apple | 4 | - | 200 | - | 3 | - | 2.5 | - | 3 | - | N/A | - | N/A | 0.5 | - | M | Growing adjacent building. Fair. Low branching. | Medium | Medium | 10+ | C1 | 2.4 | 18.1 | | | |
| T388 | Maple (Norway) | 12 | - | 360 | - | 4.5 | - | 4.5 | - | 4 | - | 4 | - | 2.5 | - | M | North | 2 | - | M | Minor deadwood. Recent pruning. | Medium | Medium | 20+ | B1 | 4.3 | 58.6 |
| G389 | Maple (Norway) | 10 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Epicormic growth removed at base. Minor deadwood. Poor pruning techniques. 5 trees. | Medium | Medium | 20+ | C2 | 4.2 | 55.4 | |
| G390 | Mixed maples | 12 | - | 360 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Slightly suppressing each other. Bark damage at base. | Medium | Medium | 20+ | C2 | 4.3 | 58.6 | |
| T391 | Maple sp. (sugar) | 13 | - | 520 | - | 7 | - | 6 | - | 5 | - | 7 | - | N/A | - | N/A | 3 | - | M | Suppressed to east. Minor deadwood. Forks at 2m. Epicormic growth at base. | Medium | Medium | 20+ | C1 | 6.2 | 122.3 | |
| G392 | Maple (Norway) | 11 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | 3 trees. Pruning wounds. Potential hazard beam at 2m east on southern tree, crossing branches. | Medium | Medium | 20+ | C2 | 4.8 | 72.4 | |
| T393 | Maple (Norway) | 11 | - | 350 | - | 4 | - | 5 | - | 4 | - | 4 | - | 2.5 | - | M | South | 2 | - | M | Good shape. | High | High | 20+ | B1 | 4.2 | 55.4 |
| T394 | Maple (Norway) | 12 | - | 440 | - | 5 | - | 5 | - | 5 | - | 4 | - | N/A | - | N/A | 2 | - | M | Good shape. Slightly suppressed to west by adjacent tree. | High | High | 20+ | B1 | 5.3 | 87.6 | |
| G395 | Maple (Norway) | 11 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 3 trees. Trees 1 and 2 from east poor, cambium stripped by squirrels. Poor. Monitor for decay, potentially remove. | Medium | Medium | 20+ | C2 | 4.2 | 55.4 | |
| G396 | Maple (Norway) | 13 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | 6 trees. Southern tree has a weak fork at 2m, and bark damage in upper canopy. Pruning wounds and deadwood | Medium | Medium | 20+ | B2 | 4.2 | 55.4 | |
| G397 | Sycamore | 12 | - | 350 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Majority have girdled roots, some with bark damage at base. 21 trees. Raise canopy to 2m to allow pedestrian access. | Medium | Medium | 20+ | B2 | 4.2 | 55.4 | |
| T398 | Sycamore | 9 | - | 230 | - | 3 | - | 3 | - | 3 | - | 3 | - | 2 | - | M | South | 1.5 | - | M | Minor deadwood. Crowded canopy. | Medium | Medium | 20+ | C1 | 2.8 | 23.9 |
| G399 | Cypress (Leyland) | 12 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Major bark damage and stripped cambium on eastern tree from base to 1.8m. | High | Medium | 20+ | C2 | 4.8 | 72.4 | |
| G400 | Sycamore | 11 | - | 320 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Central tree thin canopy. Girdled roots and bark damage at base observed. | Medium | Medium | 20+ | C2 | 3.8 | 46.3 | |
| G401 | Rowan | 6 | - | 150 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | In berberis shrub bed. | High | High | 20+ | C2 | 1.8 | 10.2 | |
| T402 | Lime (Common) | 11 | - | 400 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | In garden, unable to access. Pruning evident. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 | |
| T403 | Lime (Common) | 10 | - | 450 | - | 4 | - | 4 | - | 4 | - | 4 | - | N/A | - | N/A | 3 | - | M | In garden, unable to access. Pruning evident. Recently lopped and topped. | High | High | 20+ | B1 | 5.4 | 91.6 | |
| G404 | Rowan, hawthorn | 10 | - | 250 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 0 | - | M | Hawthorn growing at base. Multi stemmed. In front garden. | Medium | Medium | 20+ | B1 | 3.0 | 28.3 | |
| T405 | Rowan | 6 | - | 200 | - | 2 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 0.5 | - | M | Suckering from base, slightly suppressed to west. Fair. | Medium | Medium | 20+ | C1 | 2.4 | 18.1 | |
| T406 | Cherry (Ornamental flowering) | 7 | - | 300 | - | 3 | - | 4 | - | 3 | - | 3 | - | N/A | - | N/A | 2 | - | M | Evidence of cherry dieback. | Medium | Medium | 10+ | C1 | 3.6 | 40.7 | |
| T407 | Rowan | 8 | - | 200 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 2.5 | - | M | Good shape. | Medium | Medium | 20+ | C1 | 2.4 | 18.1 | |
| T408 | Eucalyptus | 16 | - | 532 | - | 4 | - | 4 | - | 7 | - | 3 | - | N/A | - | N/A | 2 | - | M | Lean to north east. Weak fork at base. | Low | Medium | 10+ | C1 | 6.4 | 127.8 | |
| T409 | Sycamore | 12 | - | 450 | - | 7 | - | 7 | - | 7 | - | 7 | - | 2 | - | M | North | 2 | - | M | Dense ivy into canopy. Sever ivy and re inspect when dead. | Medium | Medium | 20+ | C1 | 5.4 | 91.6 |
| G410 | Ash (Common) | 14 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Suppressed to south by sycamore. Ivy on trunks needs removing. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 | |
| H411 | Elder, sycamore, hawthorn, privet, rose, | 3 | - | 100 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | - | M | 0 | - | M | Good hedge, screening value. | - | - | 20+ | B2 | 1.2 | 4.5 | |
| G412 | Laurel (Cherry) | 3 | - | 100 | - | 1.5 | - | 1.5 | - | 2 | - | 1.5 | - | N/A | - | N/A | 0 | - | M | Laurel bushes with elder. | N/A | N/A | 20+ | C2 | 1.2 | 4.5 | |
| SM413 | Dogwood, blackthorn, elder, rose, sycamore, | 1.5 | - | | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | - | Regenerating shrubs along building edge. | - | - | 10+ | C2 | 0.0 | 0.0 | |
| G414 | Cypress sp. | 13 | - | 370 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | Screening value. Good group. | High | High | 40+ | B2 | 4.4 | 61.9 | |
| G415 | Sycamore | 10 | - | 250 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | Suppressed to south by cypress. ivy on eastern tree. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 | |
| G416 | Rowan | 8 | - | 100 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | SM | Poor group, western tree dead. Rude rail vegetation at base. | Medium | Medium | 20+ | C2 | 1.2 | 4.5 | |
| T417 | Cypress sp. | 13 | - | 602 | - | 0.5 | - | 3 | - | 4 | - | 3 | - | N/A | - | N/A | 0 | - | M | Suppressed to north by building. Edge of parking court. | High | High | 20+ | C2 | 7.2 | 164.0 | |
| T418 | Cypress sp. | 12 | - | 700 | - | 4 | - | 4 | - | 3 | - | 4 | - | N/A | - | N/A | 2.5 | - | M | Suppressed to east by building. Longitudinal crack observed. | Medium | Medium | 20+ | C1 | 8.4 | 221.7 | |
| T419 | Maple (Norway) | 7 | - | 400 | - | 4 | - | 4 | - | 5 | - | 5 | - | 2.5 | - | M | South west | 2 | - | M | Minor deadwood, good shape. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|---------------------|-----|---|------|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|----|--|--------|--------|-----|----|------|-------|
| T420 | Cypress sp. | 12 | - | 1000 | - | 3 | - | 5 | - | 4 | - | 3 | - | N/A | - | N/A | 0.5 | - | M | Edge of parking court. Slight discolouration on leaves. | Medium | Medium | 20+ | B1 | 12.0 | 452.4 |
| T421 | Maple (Norway) | 11 | - | 330 | - | 4.5 | - | 3 | - | 3 | - | 5 | - | 3 | - | North | 1.5 | - | M | Suppressed to south east. Weak fork 2.5m. Minor deadwood. | Medium | High | 20+ | B1 | 4.0 | 49.3 |
| T422 | Plane (Oriental) | 13 | - | 500 | - | 3 | - | 7 | - | 9 | - | 7 | - | 2 | - | East | 2 | - | M | Suppressed to north. In planting area within parking court. Minor hanging deadwood. | Medium | Medium | 20+ | B1 | 6.0 | 113.1 |
| T423 | Cypress sp. | 15 | - | 860 | - | 3 | - | 3.5 | - | 4 | - | 3.5 | - | N/A | - | N/A | 0.5 | - | M | Minor discolouration. In planting bed in parking court. | Medium | Medium | 20+ | C1 | 10.3 | 334.8 |
| T424 | Maple (Norway) | 8 | - | 210 | - | 2 | - | 3 | - | 3 | - | 4 | - | 1.5 | - | North | 2 | - | EM | Suppressed to north by cypress. Dieback in crown, leaf discolouration. | Medium | Low | 20+ | C1 | 2.5 | 20.0 |
| T425 | Hornbeam | 8 | - | 460 | - | 4.5 | - | 2.5 | - | 4 | - | 3.5 | - | 2 | - | North | 2 | - | M | Lamppost in canopy to south. Minor deadwood. Bark inclusions. | Medium | Medium | 20+ | C1 | 5.5 | 95.7 |
| G426 | Hawthorn | 6 | - | 150 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Deadwood, growing from heading standing. In courtyard area. Poor. | Low | Low | 10+ | C2 | 1.8 | 10.2 |
| G427 | Maple, goat willow | 7 | - | 216 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1 | - | M | Goat willow poor, growing from bricks under canopy structure. Maples poor, in area of hard standing. | Medium | Medium | 20+ | C2 | 2.6 | 21.1 |
| T428 | Ash (Common) | 13 | - | 490 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Offsite ash. Ivy into canopy. Hawthorn in canopy. | Medium | Medium | 20+ | B1 | 5.9 | 108.6 |
| T429 | Cypress sp. | 12 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0.5 | - | M | Suppressed by fencing. | Medium | Medium | 20+ | C1 | 6.0 | 113.1 |
| T430 | Lime (Small-leafed) | 15 | - | 600 | - | 5 | - | 6 | - | 6 | - | 7 | - | 2 | - | South | 0 | - | M | Suppressed by building to north and east. Minor deadwood. | Medium | Medium | 40+ | B1 | 7.2 | 162.9 |
| T431 | Lime (Small-leafed) | 11 | - | 380 | - | 5.5 | - | 4.5 | - | 5 | - | 5 | - | 3 | - | North | 1.5 | - | M | Edge of parking court, pushed up paving to north. Good tree. | High | High | 40+ | B1 | 4.6 | 65.3 |
| G432 | Whitebeam | 10 | - | 200 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Minor bark damage at base, mower damage. Minor deadwood. Western tree leans east. | Medium | Medium | 20+ | C2 | 2.4 | 18.1 |
| T433 | Sycamore | 8 | - | 400 | - | 6 | - | 5 | - | 5 | - | 5 | - | 2 | - | South west | 2 | - | M | Longitudinal crack 1m long to east. Minor deadwood. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 |
| T434 | Sycamore | 8 | - | 284 | - | 4.5 | - | 4 | - | 4 | - | 3.5 | - | 1.5 | - | East | 1.5 | - | M | Suppressed by building to west. Included bark at fork to 0.5m. Touching building. | Low | Medium | 20+ | C1 | 3.4 | 36.6 |
| G435 | Hawthorn | 6.5 | - | 160 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Deadwood throughout. Adjacent canopy structure. Poor shape. | Medium | Medium | 10+ | C2 | 1.9 | 11.6 |
| T436 | Sycamore | 8 | - | 150 | - | 3 | - | 2 | - | 3 | - | 1 | - | 4 | - | West | 1.5 | - | M | Suppressed by building to south. | Medium | Medium | 20+ | C1 | 1.8 | 10.2 |
| G437 | Maple (Norway) | 8 | - | 260 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Two trees. Northern tree dieback in canopy, minor deadwood. In planting area within parking court. | Medium | Medium | 20+ | C1 | 3.1 | 30.6 |
| T438 | Maple (Norway) | 12 | - | 430 | - | 4 | - | 5 | - | 7 | - | 5 | - | 3 | - | East | 1.5 | - | M | Deadwood, touching building to south. Poor shape. | Medium | Medium | 20+ | C1 | 5.2 | 83.7 |
| T439 | Sycamore | 15 | - | 440 | - | 6 | - | 6 | - | 7 | - | 5.5 | - | 2.5 | - | West | 0.5 | - | M | Weak fork at 3m including branch coalescence. Potential fibre buckling. | Medium | Medium | 20+ | C1 | 5.3 | 87.6 |
| T440 | Sycamore | 12 | - | 430 | - | 7 | - | 5 | - | 6 | - | 5 | - | 2 | - | North west | 1.5 | - | M | Black exudate on eastern base of stem, bacterial canker? Crossing branches, potential hazard beam 2.5m north east. | Medium | Medium | 10+ | C1 | 5.2 | 83.7 |
| T441 | Maple (Norway) | 15 | - | 440 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Three trees. Middle tree forks at 2m, included bark. Southern tree branches ripped off. Northern tree root girdling. | Medium | Medium | 20+ | C2 | 5.3 | 87.6 |
| T442 | Whitebeam | 7 | - | 380 | - | 5 | - | 5 | - | 6 | - | 4.5 | - | 1.5 | - | East | 1 | - | M | Helical growth, multiple pruning wounds not occluded, minor deadwood. Minor branch rubbing at 3m. Good shape. | Medium | Medium | 20+ | B1 | 4.6 | 65.3 |
| T443 | Sycamore | 12 | - | 350 | - | 6 | - | 6 | - | 7 | - | 5.5 | - | 2 | - | East | 0.5 | - | M | Multiple pruned branches to north west. Minor deadwood. | Medium | Medium | 20+ | C1 | 4.2 | 55.4 |
| T444 | Cypress sp. | 15 | - | 800 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 0 | - | M | Sycamore and elder growing from base. Suppressed to south. | Medium | Medium | 20+ | C1 | 9.6 | 289.6 |
| T445 | Cypress sp. | 15 | - | 900 | - | 4 | - | 3 | - | 4 | - | 3 | - | N/A | - | N/A | 1.5 | - | M | Rounded shape, screening value. | Medium | Medium | 20+ | C1 | 10.8 | 366.5 |
| T446 | Sycamore | 7 | - | 350 | - | 3.5 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 0.5 | - | EM | Offsite, growing through fence. | Medium | Medium | 40+ | C2 | 4.2 | 55.4 |
| T447 | Cypress sp. | 15 | - | 700 | - | 4 | - | 4 | - | 4 | - | 4 | - | N/A | - | N/A | 2 | - | M | Screening value | Medium | Medium | 20+ | B2 | 8.4 | 221.7 |
| G448 | Cypress sp. | 15 | - | 700 | - | 4 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Screening value. Seventeen trees. | Medium | Medium | 20+ | B2 | 8.4 | 221.7 |
| G449 | Maple (Norway) | 15 | - | 550 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Three trees. Exposed roots, root girdling. Pruning wounds observed. Middle tree bark damage not occluded, potential | Medium | Medium | 20+ | B2 | 6.6 | 136.9 |
| G450 | Sycamore | 11 | - | 370 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Southern, 1st tree, bark damage at 1m west, not occluded. Generally, exposed roots observed, third tree basal decay | Medium | Medium | 20+ | B2 | 4.4 | 61.9 |
| T451 | Cypress (Lawson) | 15 | - | 400 | - | 3 | - | 3 | - | 3 | - | 3 | - | N/A | - | N/A | 0 | - | M | Stone plaque at base to west. | High | High | 20+ | B1 | 4.8 | 72.4 |
| G452 | Whitebeam | 13 | - | 550 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Three trees. Southern tree pruning wound with decay and deadwood at 1.5m south. Middle tree wet cavity at 1.5m east. | Medium | Low | 10+ | C2 | 6.6 | 136.9 |
| T453 | Birch (Silver) | 12 | - | 250 | - | 2 | - | 3.5 | - | 2 | - | 2.5 | - | 2.5 | - | West | 1 | - | M | Poor form. Suppressed to north east. Moderate deadwood, crown dieback. | Medium | Low | 10+ | C1 | 3.0 | 28.3 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|----------------------------------|----|---|-----|---|-----|---|-----|---|----|---|---|---|-----|---|-------|-----|---|----|--|--------|--------|-----|----|-----|-------|
| T454 | Birch (Silver) | 12 | - | 520 | - | 7 | - | 4 | - | 2 | - | 5 | - | 3 | - | North | 2 | - | M | Exposed roots, pruning evident. Minor deadwood. | Medium | Medium | 20+ | B1 | 6.2 | 122.3 |
| T455 | Hawthorn | 7 | - | 342 | - | 2.5 | - | 3.5 | - | 2 | - | 4 | - | N/A | - | N/A | 2 | - | M | Under canopy of adjacent birches. Crossing branches, deadwood. | Medium | Medium | 20+ | C1 | 4.1 | 52.8 |
| T456 | Hawthorn (Midland) | 6 | - | 170 | - | 2.5 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 1 | - | M | Exposed roots. Sycamore growing from base. | Medium | Medium | 20+ | C1 | 2.0 | 13.1 |
| T457 | Hawthorn | 5 | - | 160 | - | 2.5 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 1.5 | - | M | Sycamore and ribes growing from base. | Medium | Medium | 20+ | C1 | 1.9 | 11.6 |
| G458 | Cherry (Bird) | 4 | - | 80 | - | 2 | - | 2 | - | 1 | - | 1 | - | N/A | - | N/A | 1.5 | - | SM | Damage at base. Evidence of gummosis. Rose and sycamore at base. Poor. | Low | Medium | 10+ | C1 | 1.0 | 2.9 |
| T459 | Sycamore | 12 | - | 290 | - | 6 | - | 3 | - | 4 | - | 4 | - | 2 | - | South | 2 | - | M | Rose growing from base. Good tree. | High | Medium | 20+ | B1 | 3.5 | 38.1 |
| T460 | Cherry (Wild) | 10 | - | 530 | - | 5.5 | - | 6.5 | - | 4 | - | 5 | - | 2.5 | - | East | 3 | - | M | Exposed roots. Recent pruning wounds. Helical growth. Maple growing between stems at 2m. Typical of age and | Medium | Medium | 20+ | B1 | 6.4 | 127.1 |
| T461 | Cherry (Wild) | 11 | - | 340 | - | 3 | - | 6 | - | 4 | - | 4 | - | 5 | - | West | 2 | - | M | Exposed roots. Recent pruning wounds. Weak low fork at base. Twin stem, southern stem leans south. Suppressed to | Low | Medium | 10+ | C1 | 4.1 | 52.2 |
| T462 | Birch (Silver) | 13 | - | 520 | - | 6 | - | 4 | - | 4 | - | 5 | - | 4 | - | West | 0.5 | - | M | Cavity south at 2m. Typical of age and species. Good tree. | Medium | Medium | 20+ | B1 | 6.2 | 122.3 |
| T463 | Whitebeam | 10 | - | 560 | - | 4 | - | 4 | - | 5 | - | 4 | - | 2 | - | East | 1.5 | - | M | Minor pruning wounds, partial occlusion. Girdling roots. Good tree. Adjacent path to west. | Medium | Medium | 20+ | B1 | 6.7 | 141.9 |
| T464 | Hawthorn | 4 | - | 100 | - | 1.5 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 2 | - | M | Heavily suppressed by whitebeam. Poor | Medium | Low | 20+ | C1 | 1.2 | 4.5 |
| G465 | Whitebeam | 10 | - | 625 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Western tree dead leader with fungal fruiting bodies, saprophytic. Minor deadwood. Maple growing from decayed | Medium | Medium | 20+ | B2 | 7.5 | 176.7 |
| G466 | Hawthorn | 5 | - | 180 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Poor group three trees. Western tree suppressed, very stunted and poor form. Generally poor. | Medium | Medium | 20+ | C2 | 2.2 | 14.7 |
| T467 | Birch (Silver) | 12 | - | 500 | - | 5 | - | 4 | - | 10 | - | 3 | - | 5 | - | East | 0.5 | - | M | Remove epicormic growth at base. Leans east. Good tree. | Medium | Medium | 20+ | B1 | 6.0 | 113.1 |
| T468 | Whitebeam | 9 | - | 460 | - | 4 | - | 5 | - | 3 | - | 3 | - | 2 | - | East | 1.5 | - | M | Pruning wounds, minor, some with cavities. Signs screwed to trunk on east. Minor deadwood. | Medium | Medium | 20+ | C1 | 5.5 | 95.7 |
| G469 | Whitebeam | 11 | - | 600 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Southern tree, several cavities observed on eastern limb, woodpecker damage, sign of decay. Northern tree lost major | Medium | Medium | 10+ | C2 | 7.2 | 162.9 |
| T470 | Sycamore | 14 | - | 530 | - | 0 | - | 0 | - | 0 | - | 0 | - | 6 | - | North | 5 | - | M | Exposed roots, minor bark damage. Minor deadwood. | Medium | Medium | 20+ | B1 | 6.4 | 127.1 |
| T471 | Beech (Common) | 16 | - | 620 | - | 0 | - | 0 | - | 0 | - | 0 | - | 7 | - | East | 4 | - | M | Exposed roots. Good tree. | High | High | 40+ | A1 | 7.4 | 173.9 |
| T472 | Chestnut (Horse) | 14 | - | 650 | - | 0 | - | 0 | - | 0 | - | 0 | - | 3 | - | North | 2 | - | M | Helical growth, remove adventitious shoots. | Medium | Medium | 20+ | B1 | 7.8 | 191.2 |
| T473 | Beech (purple) | 15 | - | 590 | - | 0 | - | 0 | - | 0 | - | 0 | - | 4 | - | South | 1.5 | - | M | Exposed roots. Good tree. | High | High | 40+ | A1 | 7.1 | 157.5 |
| T474 | Chestnut (Horse) | 15 | - | 590 | - | 0 | - | 0 | - | 0 | - | 0 | - | 4 | - | South | 2 | - | M | Minor deadwood. Good tree. | Medium | Medium | 20+ | B1 | 7.1 | 157.5 |
| G475 | Mixed group, hawthorn, sycamore, | 12 | - | 200 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | N/A | - | M | Trees regenerating within fenced area. Unable to access. | Medium | Medium | 10+ | C2 | 2.4 | 18.1 |
| T476 | Hawthorn | 6 | - | 394 | - | 2 | - | 2 | - | 2 | - | 2 | - | N/A | - | N/A | 1.5 | - | M | Crossing branches. Minor deadwood. | Medium | Medium | 20+ | C1 | 4.7 | 70.3 |
| T477 | Birch (Silver) | 10 | - | 270 | - | 1 | - | 5 | - | 2 | - | 2 | - | 2 | - | South | 2 | - | M | Suppressed to north. Poor shape. | Medium | Low | 10+ | C1 | 3.2 | 33.0 |
| T478 | Chestnut (Horse) | 13 | - | 470 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Forks at 2m, lots of knuckles. | Medium | Medium | 20+ | B1 | 5.6 | 99.9 |
| T479 | Beech (Common) | 16 | - | 700 | - | 0 | - | 0 | - | 0 | - | 0 | - | 4 | - | East | 1.5 | - | M | Typical of age and species. Minor deadwood. Good tree. | Medium | Medium | 40+ | A1 | 8.4 | 221.7 |
| T480 | Sycamore | 14 | - | 450 | - | 0 | - | 0 | - | 0 | - | 0 | - | 3 | - | North | 2 | - | M | Exposed roots. Branches shaded out, allot of deadwood and abscised branches. | Medium | Medium | 10+ | C1 | 5.4 | 91.6 |
| T481 | Beech (purple) | 14 | - | 520 | - | 0 | - | 0 | - | 0 | - | 0 | - | 6 | - | South | 2 | - | M | Typical of age and species. Good tree. | High | High | 40+ | A1 | 6.2 | 122.3 |
| T482 | Chestnut (Horse) | 15 | - | 520 | - | 0 | - | 0 | - | 0 | - | 0 | - | 3 | - | South | 1.5 | - | M | Minor deadwood. Several small cavities with decay. | Medium | Medium | 20+ | B1 | 6.2 | 122.3 |
| T483 | Sycamore | 15 | - | 560 | - | 0 | - | 0 | - | 0 | - | 0 | - | 6 | - | South | 1.5 | - | M | Touching partially demolished cabins to south. Open crown, minor deadwood. Exposed roots. | Medium | Medium | 20+ | B1 | 6.7 | 141.9 |
| T484 | Beech (Common) | 16 | - | 720 | - | 0 | - | 0 | - | 0 | - | 0 | - | 6 | - | South | 1.5 | - | M | Random metal post in trunk at 1m north, tree grown around it. Moderate deadwood in shaded crown. Bark damage at 2.5m | Medium | Medium | 40+ | A1 | 8.6 | 234.5 |
| G485 | Chestnut (Horse) | 16 | - | 690 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Three trees. Northern tree black exudate, onset of bacterial wetwood? Minor deadwood, crossing branches and exposed | Medium | Medium | 20+ | B2 | 8.3 | 215.4 |
| G486 | Sycamore | 16 | - | 620 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 3 | - | M | Two trees. Either side of road. Deadwood, telephone pole in canopy of western tree. | Medium | Medium | 20+ | C2 | 7.4 | 173.9 |
| T487 | Birch (Silver) | 7 | - | 250 | - | 3 | - | 3 | - | 3 | - | 3 | - | 3 | - | South | 1.5 | - | EM | Small tree adjacent building. | Medium | Medium | 20+ | C1 | 3.0 | 28.3 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|------------------|----|---|------|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|---|---|--------|--------|-----|----|------|-------|
| T488 | Birch (Silver) | 14 | - | 390 | - | 4 | - | 3 | - | 6 | - | 1 | - | 7 | - | West | 2 | - | M | Slight lean to north,adjacent building. | Medium | Medium | 20+ | B1 | 4.7 | 68.8 |
| T489 | Birch (Silver) | 11 | - | 330 | - | 0.5 | - | 7 | - | 5 | - | 0.5 | - | 2.5 | - | South west | 1.5 | - | M | Helical growth. Suppressed to north by cherry. Lean to south east. | Medium | Medium | 20+ | C1 | 4.0 | 49.3 |
| T490 | Cherry (Wild) | 10 | - | 460 | - | 3 | - | 5 | - | 3 | - | 7.5 | - | 2 | - | West | 0.5 | - | M | Root girdling. Evidence of woodpeckers, holes potentially indicate internal decay. Cavities 3m south east on main limb. | Medium | Medium | 20+ | B1 | 5.5 | 95.7 |
| T491 | Birch (Silver) | 12 | - | 450 | - | 4 | - | 6 | - | 5 | - | 3 | - | 3 | - | South | 0.5 | - | M | Kink in stem. Good tree. | Medium | Medium | 20+ | B1 | 5.4 | 91.6 |
| T492 | Maple (Norway) | 14 | - | 520 | - | 0 | - | 0 | - | 0 | - | 0 | - | 4 | - | North west | 4 | - | M | Exposed roots. Adjacent over ground pipes and paving at base to east. Suppressed to south.m | Medium | Medium | 20+ | B1 | 6.2 | 122.3 |
| T493 | Sycamore | 16 | - | 580 | - | 0 | - | 0 | - | 0 | - | 0 | - | 3 | - | West | 2.5 | - | M | Exposed roots. Minor deadwood. Good tree. | Medium | Medium | 20+ | B2 | 7.0 | 152.2 |
| G494 | Sycamore | 14 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 1.5 | - | M | Suppressed to north and south. Exposed roots. Southern tree better than northern tree. Consider removing northern tree to | Medium | Medium | 20+ | B2 | 6.0 | 113.1 |
| T495 | Apple | 6 | - | 210 | - | 5 | - | 4 | - | 2 | - | 5 | - | 2.5 | - | North | 2 | - | M | Grafted onto hawthorn Woodstock. Apple? Good small tree. | Medium | Medium | 20+ | B1 | 2.5 | 20.0 |
| T496 | Birch (Silver) | 11 | - | 360 | - | 4 | - | 5 | - | 4 | - | 3 | - | N/A | - | N/A | 2 | - | M | Forks at 1.8m. Black exudate and holes on south eastern limb at 3.5m. | Medium | Medium | 20+ | C1 | 4.3 | 58.6 |
| T497 | Hawthorn | 6 | - | 340 | - | 2.5 | - | 4 | - | 3 | - | 4 | - | 2 | - | South | 2 | - | M | Bent stem, minor deadwood. | Medium | Medium | 20+ | C1 | 4.1 | 52.3 |
| G498 | Birch (Silver) | 11 | - | 370 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Two trees. Southern tree, cavity at 3m. Pruning wounds. Good group. | Medium | Medium | 20+ | B2 | 4.4 | 61.9 |
| T499 | Cherry (Wild) | 7 | - | 360 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Cavity at 1.5 south, dry decay exposed decayed heartwood. Split branch to north with decay. Multiple recent large pruning | Low | Low | 10+ | C1 | 4.3 | 58.6 |
| T500 | Sycamore | 13 | - | 330 | - | 6 | - | 6.5 | - | 2 | - | 5 | - | 3 | - | South | 4 | - | M | Suppressed to east and west. Multiple pruning wounds, not occluded. Cavity at 2m west. | Medium | Medium | 10+ | C1 | 4.0 | 49.3 |
| G501 | Pine | 15 | - | 280 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 9 | - | M | Heavily suppressed by Beech. Recommended remove to better Beech. | Medium | Low | 20+ | C2 | 3.4 | 35.5 |
| G502 | Beech (Common) | 17 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Good group. Remove pine. Exposed roots. | Medium | Medium | 20+ | B2 | 6.0 | 113.1 |
| G503 | Sycamore | 17 | - | 410 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2 | - | M | Two trees. Cavity on eastern tree, to north at 3m. Limb loss at 2m. Generally suppressed to north by beech. | Medium | Medium | 20+ | C2 | 4.9 | 76.1 |
| T504 | Beech (Common) | 17 | - | 650 | - | 6 | - | 7 | - | 9 | - | 5 | - | 4.5 | - | South | 3.5 | - | M | Adjacent fencing. Pruning wounds. Typical for age and species. Good tree. | Medium | Medium | 40+ | A1 | 7.8 | 191.2 |
| G505 | Pine | 13 | - | 380 | - | 0 | - | 0 | - | 0 | - | 0 | - | N/A | - | N/A | 2.5 | - | M | Recommend remove pines to better sycamores. | Medium | Medium | 20+ | B2 | 4.6 | 65.3 |
| G506 | Sycamore | 17 | # | 540 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 2 | # | M | Tall tapering stems, drawn up form. | Medium | Medium | 20+ | C2 | 6.5 | 131.9 |
| G507 | Pine | 14 | # | 550 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 3 | # | M | Multiple running wounds. Drawn up form. Woodpecker holes. | Medium | Medium | 20+ | C2 | 6.6 | 136.9 |
| T508 | Hazel (Common) | 8 | # | 1300 | # | 5 | # | 5 | # | 5 | # | 5 | # | N/A | # | N/A | 2 | # | M | Previously coppiced, lapsed long time ago. Ivy into canopy. | Medium | Medium | 40+ | A1 | 15.6 | 764.6 |
| T509 | Hawthorn | 7 | # | 420 | # | 3 | # | 3 | # | 3 | # | 3 | # | N/A | # | N/A | 2 | # | M | Disturbed ground at base, possible compaction. | Medium | Medium | 20+ | C1 | 5.0 | 79.8 |
| T510 | Hawthorn | 5 | # | 250 | # | 2 | # | 2 | # | 2 | # | 2 | # | N/A | # | N/A | 2 | # | M | Disturbed ground at base, possible compaction.dieback at extremities. | Medium | Low | 10+ | C1 | 3.0 | 28.3 |
| T511 | Pine? | 18 | # | 790 | # | 6 | # | 4.5 | # | 4 | # | 4 | # | 8 | # | West | 4 | # | M | Multiple pruning wounds. Dried sap exudate. Cavity on stem 1m south. | Medium | Medium | 20+ | B1 | 9.5 | 282.4 |
| T512 | Sycamore | 15 | # | 660 | # | 4 | # | 7 | # | 6 | # | 4 | # | 2 | # | North | 2 | # | M | On slight mound. Dry rot at base to south. Tapping sounds hollow. Recommend detailed inspection undertaken ASAP. | Low | Medium | 20+ | C1 | 7.9 | 197.1 |
| T513 | Sycamore | 15 | # | 440 | # | 6 | # | 2.5 | # | 7 | # | 4 | # | 5 | # | North | 2 | # | M | Moderate major deadwood. Poor shape. | Medium | Medium | 20+ | C1 | 5.3 | 87.6 |
| T514 | Ash (Common) | 14 | # | 660 | # | 8 | # | 7 | # | 7 | # | 8 | # | 4 | # | North | 2 | # | M | Elms growing at base. Set in small planting area within Tarmac. Minor deadwood. | Medium | Medium | 20+ | C1 | 7.9 | 197.1 |
| T515 | Sycamore | 15 | # | 400 | # | 5 | # | 5 | # | 2 | # | 4.5 | # | 4 | # | South west | 2 | # | M | Dense ivy into crown. Minor deadwood. Remove ivy and re inspect. | Medium | Medium | 20+ | C1 | 4.8 | 72.4 |
| T516 | Oak (Holm) | 14 | # | 714 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | Tyres stacked around base. Longitudinal crack on western limb, and centre western limb. Low fork. Central limb has | Low | Medium | 20+ | C1 | 8.6 | 230.9 |
| G517 | Sycamore | 16 | # | 690 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | M | Two trees. Southern tree elongated wound, partial occlusion, heartwood exposed -3m east. Helical growth observed. Minor | Medium | Medium | 20+ | B2 | 8.3 | 215.4 |
| T518 | Chestnut (Horse) | 13 | # | 820 | # | 0 | # | 0 | # | 0 | # | 0 | # | 4 | # | South | 0 | # | M | Canopy touching ground, overground pipes under canopy. Adjacent fencing. Longitudinal cracks observed. Huge | Medium | Medium | 20+ | B1 | 9.8 | 304.2 |
| T519 | Hawthorn | 7 | # | 600 | # | 6 | # | 3 | # | 2 | # | 5 | # | N/A | # | N/A | 0.5 | # | M | Close to fencing. Minor deadwood, branches crossing. | Medium | Medium | 20+ | C1 | 7.2 | 162.9 |
| G520 | Sycamore | 16 | # | 560 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 4 | # | M | Two trees. Eastern tree weak fork at 4m. Pruning wounds, lean to south east. Suppressed to west and north west. | Medium | Medium | 20+ | C2 | 6.7 | 141.9 |
| T521 | Pine | 16 | # | 330 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 15 | # | M | Drawn up, lions tail canopy. Suppressed. Recommend remove to better other trees. | Medium | Low | 10+ | C1 | 4.0 | 49.3 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|---------------------------------------|----|---|------|---|-----|---|-----|---|---|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|------|-------|
| T522 | Beech (Common) | 18 | # | 1100 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 3.5 | # | M | Fused branches, weak fork from base to 1.5m, fused to form natural brace. Touching adjacent building and telephone pole. | Medium | Medium | 20+ | B1 | 13.2 | 547.5 |
| T523 | Sycamore | 15 | # | 430 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | M | Suppressed, pruning wounds not occluded. Lean to east. | Medium | Medium | 20+ | C1 | 5.2 | 83.7 |
| G524 | Pine | 15 | # | 430 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 6 | # | M | Suppressed by sycamore to north. Drawn up form. | Medium | Medium | 20+ | B2 | 5.2 | 83.7 |
| G525 | Pine, beech, sycamore | 15 | # | 580 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 3 | # | M | Minor bark damage observers and exposed roots. Sycamore has a weak fork. Minor pruning wounds. | Medium | Medium | 20+ | B2 | 7.0 | 152.2 |
| G526 | Cypress (Lawson) | 11 | # | 400 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0 | # | M | Group of cypress, 1 dead tree, sycamore regen. Couldn't access base, prevented basal inspection. Recommend | Medium | Medium | 20+ | B2 | 4.8 | 72.4 |
| T527 | Birch (Silver) | 13 | # | 480 | # | 5 | # | 5 | # | 5 | # | 5 | # | 3 | # | South east | 3 | # | M | Close to buildings. Adjacent hardstanding. Minor deadwood. Minor rounding wounds. | Medium | Medium | 20+ | B1 | 5.8 | 104.2 |
| G528 | Birch (Silver) | 12 | # | 390 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | M | Exposed roots, pruning wounds not occluded. Minor bark damage. | Medium | Medium | 20+ | B2 | 4.7 | 68.8 |
| G529 | Hawthorn | 7 | # | 240 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | M | Exposed roots, deadwood and broken branches. Helical growth. | Medium | Medium | 20+ | C2 | 2.9 | 26.1 |
| T530 | Birch (Silver) | 12 | # | 230 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | M | Exposed roots, suppressed to south. Minor bark damage. Dieback at extremities. | Medium | Medium | 20+ | C1 | 2.8 | 23.9 |
| G531 | Plum (Purple) | 9 | # | 350 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | M | Two trees, western tree weak fork at base. Phellinus fruiting body observed. Cavities observed. | Medium | Medium | 10+ | C2 | 4.2 | 55.4 |
| T532 | Birch (Silver) | 13 | # | 350 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 2 | # | M | Minor pruning wounds. Minor dieback at extremities. | Medium | Medium | 20+ | C1 | 4.2 | 55.4 |
| T533 | Rowan | 4 | # | 90 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | Y | Young tree, cavity at base with decay. Poor form. | Low | Low | 20+ | C1 | 1.1 | 3.7 |
| T534 | Birch (Silver) | 13 | # | 422 | # | 5 | # | 0 | # | 5 | # | 5 | # | 5 | # | North west | 7 | # | M | Forks at 1.5m. Potential cavity 0.5m north. Suppressed by adjacent sycamores. | Medium | Medium | 10+ | C1 | 5.1 | 80.6 |
| G535 | Sycamore | 15 | # | 380 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 3 | # | M | 7 trees. Pruning wounds observed, partial occlusion. Several cavities, exposed roots. Most northern tree cavity at 2.5m | Medium | Medium | 20+ | B2 | 4.6 | 65.3 |
| T536 | Hawthorn | 7 | # | 310 | # | 3 | # | 3 | # | 3 | # | 2 | # | N/A | # | N/A | 2 | # | M | Adjacent kerb edge, close to buildings. Minor deadwood, thin crown-reduced leaf bearing structure. | Medium | Low | 20+ | C1 | 3.7 | 43.5 |
| G537 | Sycamore | 15 | # | 560 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 3 | # | M | 6 trees. Pruning wounds observed, partial occlusion. Several cavities, exposed roots. Tree 2 - longitudinal crack at 1.5m | Medium | Medium | 20+ | B2 | 6.7 | 141.9 |
| G538 | Sycamore | 15 | # | 580 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 3 | # | M | 4 trees. Exposed roots, minor pruning wounds. Typical of age and species. Good group. Tree 4 close to water tower, | Medium | Medium | 20+ | B2 | 7.0 | 152.2 |
| G539 | Maple | 8 | # | 310 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1.5 | # | M | 5 trees. Typical of age and species. Recommend remove outer trees to better eastern tree. | Medium | Medium | 20+ | B2 | 3.7 | 43.5 |
| G540 | Cherry (Wild) | 10 | # | 420 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | 3 trees. Remove central suppressed tree to better adjacent trees. Consider raising canopy. Exposed large roots. | Medium | Medium | 20+ | B2 | 5.0 | 79.8 |
| T541 | Lime (Common) | 3 | # | 130 | # | 1 | # | 2 | # | 1 | # | 1 | # | N/A | # | N/A | 1.5 | # | SM | Small tree, stunted form, major deadwood. Poor. | Low | Low | 10+ | C1 | 1.6 | 7.6 |
| G542 | Ash, sycamore, Lawson cypress, willow | 15 | # | 610 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | Mixed line of trees aligning fence. Screening value. Concrete posts and barbed wire into canopies. | Medium | Medium | 20+ | B2 | 7.3 | 168.4 |
| G543 | Cypress (Lawson) | 15 | # | 580 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 2.5 | # | M | Tall line of cypress aligning wooden fence. Tightly grown, several suppressed and dying. Poor. | Medium | Low | 20+ | C2 | 7.0 | 152.2 |
| T544 | Ash (Common) | 6 | # | 250 | # | 2.5 | # | 2.5 | # | 3 | # | 2.5 | # | N/A | # | N/A | 3 | # | EM | Growing through wire fence. Tree grown around and eaten fencing. Concrete post at base | Low | Low | 10+ | C1 | 3.0 | 28.3 |
| T545 | Pine | 18 | # | 730 | # | 4 | # | 5.5 | # | 8 | # | 5 | # | 11 | # | South east | 8 | # | M | Very large tree. Drawn up. Typical of age and species. | Medium | Medium | 20+ | B1 | 8.8 | 241.1 |
| G546 | Pine, sycamore, ash | 15 | # | | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | N/A | # | M | Mixed group within derelict parking area overgrown with ruderal and regenerating vegetation. | Medium | Medium | 20+ | C2 | 0.0 | 0.0 |
| T547 | Pine | 15 | # | 500 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0 | # | M | Dense ivy on stem. | Medium | Medium | 20+ | C1 | 6.0 | 113.1 |
| T548 | Ash (Common) | 15 | # | 450 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0 | # | M | Dense ivy on stem. | Medium | Medium | 20+ | C1 | 5.4 | 91.6 |
| T549 | Sycamore | 15 | # | 550 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | Dense ivy on stem. Remove epicormic growth from base. | Medium | Medium | 20+ | B1 | 6.6 | 136.9 |
| T550 | Ash (Common) | 15 | # | 316 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | Multi stem, hawthorn near base. Poor. | Medium | Medium | 10+ | C1 | 3.8 | 45.2 |
| T551 | Pine | 15 | # | 700 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | Dense ivy on stem. | Medium | Medium | 20+ | B1 | 8.4 | 221.7 |
| T552 | Pine | 15 | # | 900 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 10 | # | M | Dense ivy on stem. | Medium | Medium | 20+ | C1 | 10.8 | 366.5 |
| T553 | Ash (Common) | 15 | # | 420 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 6 | # | M | Dense ivy on stem. | Medium | Medium | 20+ | C1 | 5.0 | 79.8 |
| T554 | Pine | 15 | # | 700 | # | 0 | # | 0 | # | 0 | # | 0 | # | 1 | # | South | 4 | # | M | Dense ivy in stem. Elder at base. Growing in derelict and overgrown parking area. Major limb growing south at 1m. | Medium | Medium | 20+ | B1 | 8.4 | 221.7 |
| G555 | Ash, sycamore, elder, hawthorn | 8 | # | 250 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | EM | Regenerating mixed group. | Medium | Medium | 20+ | C2 | 3.0 | 28.3 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|----------------------------------|----|---|------|---|-----|---|-----|---|----|---|-----|---|-----|---|------------|-----|---|----|---|--------|--------|-----|----|------|-------|
| G556 | Cypress (Leyland) | 5 | # | 200 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0 | # | EM | Small group adjacent buildings. Nice group. | High | High | 40+ | A2 | 2.4 | 18.1 |
| T557 | Apple | 4 | # | 120 | # | 2 | # | 2.5 | # | 2 | # | 2 | # | N/A | # | N/A | 1 | # | M | Small tree adjacent buildings. | Medium | Medium | 10+ | C1 | 1.4 | 6.5 |
| G558 | Sycamore | 17 | # | 651 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1 | # | M | Group of trees with concrete path dissecting group. All slightly suppressing each other. Minor deadwood and shaded out Exposed roots, mower damage to roots. Concrete path to north. Typical for age and species. | Medium | Medium | 20+ | B2 | 7.8 | 191.6 |
| T559 | Sycamore | 17 | # | 660 | # | 7 | # | 7 | # | 6 | # | 5 | # | 4 | # | South west | 1 | # | M | | Medium | Medium | 40+ | A1 | 7.9 | 197.1 |
| T560 | Sycamore | 18 | # | 570 | # | 6 | # | 6 | # | 5 | # | 5 | # | 4 | # | South | 1 | # | M | Typical for age and species. | Medium | Medium | 20+ | B1 | 6.8 | 147.0 |
| T561 | Sycamore | 18 | # | 590 | # | 8 | # | 4 | # | 5 | # | 7 | # | 3.5 | # | North west | 2 | # | M | Irregular canopy to south. Good tree. | Medium | Medium | 20+ | B1 | 7.1 | 157.5 |
| G562 | Maple | 15 | # | 220 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 1 | # | M | 7 trees. Group of maples, some showing signs of reversion, some purple leaved. Minor bark damage, some suppression | Medium | Medium | 20+ | B2 | 2.6 | 21.9 |
| G563 | Sycamore | 17 | # | 560 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | 3 trees. Central tree growing on fence, dense ivy on stems into canopy. Lots of shaded out internal branches. Exposed | Medium | Medium | 20+ | B2 | 6.7 | 141.9 |
| T564 | Sycamore | 8 | # | 300 | # | 0 | # | 0 | # | 0 | # | 0 | # | - | # | - | 1.5 | # | M | Growing against and through fencing. Regeneration. | Medium | Medium | 20+ | C1 | 3.6 | 40.7 |
| T565 | Larch (Common) | 15 | # | 390 | # | 5 | # | 3 | # | 3 | # | 4 | # | 5 | # | North | 1 | # | M | Hanging deadwood, suppressed to south east by ash. Minor deadwood, crossing branches | Medium | Medium | 20+ | C1 | 4.7 | 68.8 |
| T566 | Ash (Common) | 18 | # | 560 | # | 6 | # | 0 | # | 0 | # | 7.5 | # | 3.5 | # | West | 1 | # | M | Thin canopy, abscised branches, cavities observed with decay . Minor deadwood. Recommend climbing inspection. | Medium | Medium | 20+ | B1 | 6.7 | 141.9 |
| T567 | Yew (Common) | 8 | # | 500 | # | 5 | # | 5 | # | 5 | # | 5 | # | N/A | # | N/A | 0.5 | # | M | Recommend raise canopy to 2m. Suppressed by ash to east. | Medium | Medium | 20+ | B1 | 6.0 | 113.1 |
| T568 | Ash (Common) | 18 | # | 600 | # | 3 | # | 9 | # | 1 | # | 6.5 | # | N/A | # | N/A | 0 | # | M | Dense ivy throughout, prevented inspection. Recommend remove ivy and re inspect. In even canopy, pruning wounds, | Medium | Medium | 20+ | C1 | 7.2 | 162.9 |
| T569 | Pine | 18 | # | 700 | # | 3.5 | # | 3.5 | # | 4 | # | 3.5 | # | N/A | # | N/A | 15 | # | M | Dense ivy on stem needs removing, then re inspect. Access limited, couldn't undertake proper inspection due to ivy. | Medium | Medium | 20+ | C1 | 8.4 | 221.7 |
| T570 | Beech (Common) | 18 | # | 1200 | # | 10 | # | 10 | # | 10 | # | 10 | # | 4 | # | North | 0.5 | # | M | Dense ivy on stem needs removing, then re inspect. Access limited, couldn't undertake proper inspection due to ivy. | Medium | Medium | 20+ | B1 | 14.4 | 651.5 |
| T571 | Pine | 18 | # | 570 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 9 | # | M | Slight lean to the east. Sparse canopy. Ivy on stem. | Medium | Low | 20+ | C1 | 6.8 | 147.0 |
| T572 | Pine | 18 | # | 550 | # | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | N/A | # | M | Dense ivy prevented full inspection. Fungal fruiting bodies at base, extensive. Recommend remove ivy and detailed | Medium | Medium | <10 | U | 6.6 | 136.9 |
| T573 | Sycamore | 18 | # | 636 | # | 0 | # | 0 | # | 0 | # | 0 | # | 3 | # | East | 0.5 | # | M | Dense ivy on stem and into crown, needs removing and re inspecting. Twin stem, typical of age and species. | Medium | Medium | 20+ | C1 | 7.6 | 183.2 |
| T574 | Pine | 18 | # | | # | 0 | # | 0 | # | 0 | # | 0 | # | 4.5 | # | North | 0.5 | # | M | Adjacent sycamore branches rubbing stem. Consider removing to better sycamore. | Medium | Medium | 20+ | C1 | 0.0 | 0.0 |
| T575 | Maple (Norway) | 17 | - | 420 | - | 6.5 | - | 5 | - | 4 | # | 7 | - | 4 | - | East | 1 | - | M | Minor deadwood in lower central crown | Medium | High | 20+ | B1 | 5.0 | 79.8 |
| T576 | Whitebeam | 12 | - | 540 | - | 5 | - | 4 | - | 5 | - | 5.5 | - | 1.5 | - | South | 3 | - | M | Hard surfacing adjacent. Thin foliage density. Major deadwood in central lower crown. | Medium | Medium | 10+ | C1 | 6.5 | 131.9 |
| T577 | Whitebeam | 12 | - | 510 | - | 6 | - | 4 | - | 5 | - | 5 | - | 2.5 | - | North | 2 | - | M | Hard surfacing adjacent. Thin foliage density. Major deadwood in central lower crown. | Medium | Medium | 10+ | C1 | 6.1 | 117.7 |
| T578 | No tree | 0 | - | | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | - | - | - | - | - | 0.0 | 0.0 |
| T579 | Birch (Silver) | 14 | - | 320 | - | 2 | # | 4 | # | 4 | # | 3.5 | # | 3 | - | South | 2 | - | M | Bifurcates at 1.5m | Medium | High | 10+ | C1 | 3.8 | 46.3 |
| T580 | Birch (Silver) | 15 | # | 420 | - | 6.5 | - | 6.5 | - | 4 | - | 6.5 | - | 2.5 | - | South | 2 | - | M | Hard surface to north | Medium | High | 10+ | C1 | 5.0 | 79.8 |
| T581 | Chestnut (Horse) | 15 | - | 740 | - | 7.5 | - | 8 | - | 9 | - | 7.5 | - | 3 | - | North | 0.5 | - | M | Nears surfacing on three sides of tree. Leaf miner infestation. Multi stemmed at 2.5m. | Medium | High | 10+ | C1 | 8.9 | 247.8 |
| T582 | Birch (Silver) | 17 | # | 590 | - | 5 | - | 9.5 | - | 5 | - | 9 | - | 2 | - | South | 1 | - | M | Cavity in main branch at 3m height | Medium | High | 10+ | C1 | 7.1 | 157.5 |
| G583 | Birch (Silver) | 17 | - | 400 | # | 8.5 | - | 7.5 | - | 7 | - | 8 | - | 0 | - | - | 0 | - | M | Group consisting of 2 trees | Medium | High | 10+ | C2 | 4.8 | 72.4 |
| T584 | Elder | 3 | - | | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Shrub mass in location of former landscape planting | Low | High | - | - | 0.0 | 0.0 |
| T585 | Sycamore | 14 | - | 500 | - | 5 | - | 6 | - | 5 | - | 5.5 | - | 4 | - | South | 3 | - | M | Cavity with decay at base (E) extending into footplate. Cavity main stem (3m, E) at site of previous flush cut (decay | Low | Medium | <10 | U | 6.0 | 113.1 |
| T586 | Chestnut (Horse) | 12 | # | 570 | - | 3.5 | # | 5 | # | 4 | # | 4 | # | 0 | - | - | 0 | - | M | >50% crown is dead. Previous structural failure in upper crown. Habitat potential. Remove tree. | Low | Low | <10 | U | 6.8 | 147.0 |
| T587 | Chestnut (Horse) | 14 | - | 540 | - | 7 | - | 5 | - | 6 | - | 5 | - | 0 | - | - | 0 | - | M | Previous branch failure (S) at 6m. Evidence of extensive previous bleeding canker damage. Curtailed useful life | Low | Low | <10 | U | 6.5 | 131.9 |
| G588 | Western Red Cedar, Common Beech, | 14 | # | | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Large tree group between built area and road. Collective landscape value. Selected trees surveyed for RPA purposes. | - | - | 20+ | B2 | 0.0 | 0.0 |
| T589 | Cedar (Western Red) | 0 | - | 600 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Surveyed for RPA purposes | High | High | 20+ | B2 | 7.2 | 162.9 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|---------------------------|------|---|-----|---|-----|---|-----|---|----|---|-----|---|-----|---|------------|-----|---|----|--|--------|--------|-----|----|------|-------|
| T590 | Beech (Common) | 0 | - | 500 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Surveyed for RPA purposes | High | High | 20+ | B2 | 6.0 | 113.1 |
| T591 | Beech (Common) | 0 | - | 580 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Surveyed for RPA purposes | High | High | 20+ | B2 | 7.0 | 152.2 |
| T592 | Poplar (Lombardy) | 0 | - | 580 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Surveyed for RPA purposes | High | High | 20+ | B2 | 7.0 | 152.2 |
| T593 | Birch (Silver) | 0 | - | 480 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Surveyed for RPA purposes | High | High | 20+ | B2 | 5.8 | 104.2 |
| T594 | Chestnut (Horse) | 0 | - | 530 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Surveyed for RPA purposes | High | High | 20+ | B2 | 6.4 | 127.1 |
| T595 | Chestnut (Horse) | 0 | - | 560 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Surveyed for RPA purposes | High | High | 20+ | B2 | 6.7 | 141.9 |
| G596 | Cypress (Lawson) | 8 | # | 300 | # | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Screen planting linking two buildings | Medium | High | 10+ | C2 | 3.6 | 40.7 |
| T597 | Whitebeam | 10 | # | 570 | - | 6 | - | 5.5 | - | 5 | - | 5 | - | 2 | - | South | 2 | - | M | Large tree for the species | Medium | Medium | 10+ | C2 | 6.8 | 147.0 |
| T598 | Chestnut (Horse) | 11 | - | 420 | - | 6 | - | 5 | - | 5 | - | 5.5 | - | 3 | - | East | 1 | - | M | Bleeding canker on trunk. | Medium | Medium | 10+ | C2 | 5.0 | 79.8 |
| T599 | Whitebeam | 10 | # | 470 | - | 5 | - | 5 | - | 5 | - | 3 | - | 3 | - | South | 2 | - | M | Slight lean east | Medium | Medium | 10+ | C2 | 5.6 | 99.9 |
| T600 | Whitebeam | 10 | # | 470 | - | 5 | - | 4.5 | - | 5 | - | 5 | - | 2.5 | - | South | 2 | - | M | Woodpecker holes (N). Habitat potential | Medium | Medium | 10+ | C2 | 5.6 | 99.9 |
| G601 | Silver birch. Cherry | 12 | - | 300 | # | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Formerly group of 3 trees. One since removed. | Medium | Medium | 10+ | C2 | 3.6 | 40.7 |
| T602 | Whitebeam | 10 | # | 480 | - | 6 | - | 4 | - | 6 | - | 4 | - | 2 | - | North | 2 | - | M | Slight lean east | Medium | Medium | 10+ | C2 | 5.8 | 104.2 |
| T603 | Whitebeam | 10 | # | 480 | - | 5 | - | 4 | - | 4 | - | 4 | - | 2 | - | North | 2 | - | M | Innonotus hispidus decay fungus bracket at 4m (S) | Medium | Medium | 10+ | C2 | 5.8 | 104.2 |
| T604 | Whitebeam | 10 | # | 550 | - | 4.5 | - | 5 | - | 5 | - | 5 | - | 2.5 | - | South | 2 | - | M | Thin foliage density. Deadwood in central crown. Remove deadwood. | Medium | Medium | 10+ | C2 | 6.6 | 136.9 |
| G605 | Wild cherry, silver birch | 12 | # | 480 | - | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | M | Remove dead wood over path | Medium | Medium | 10+ | C2 | 5.8 | 104.2 |
| T606 | Whitebeam | 10 | - | 600 | - | 5 | - | 5 | - | 5 | - | 5.5 | - | 2 | - | South | 1.5 | - | M | Limb congestion at 2m | Medium | Medium | 10+ | C2 | 7.2 | 162.9 |
| T607 | Whitebeam | 9 | - | 510 | - | 5 | - | 5 | - | 5 | - | 5.5 | - | 2 | - | South | 1.5 | - | M | Innonotus hispidus decay fungal bracket at 2m (E) at point of trifecta ion. Woodpecker hole above. Remove roadside | Low | Medium | 10+ | C2 | 6.1 | 117.7 |
| T608 | Whitebeam | 8.5 | - | 480 | - | 5 | - | 4 | - | 5 | - | 5 | - | 2 | - | South | 2 | - | M | Deadwood in central crown. | Medium | Medium | 10+ | C2 | 5.8 | 104.2 |
| G609 | Birch, hawthorn | 7 | - | 300 | # | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | M | Lower than average height | Medium | Medium | 10+ | C2 | 3.6 | 40.7 |
| G610 | Birch (Silver) | 12 | - | 300 | # | 0 | - | 0 | - | 0 | - | 0 | - | 0 | - | - | 0 | - | - | Compact group of five trees | Medium | Medium | 10+ | C2 | 3.6 | 40.7 |
| T611 | Birch (Silver) | 7 | # | 250 | - | 3 | - | 4.5 | - | 4 | - | 3.5 | - | 3 | - | South | 1 | - | M | Located within planter surrounded by hard surface car park. | Medium | Medium | 10+ | C1 | 3.0 | 28.3 |
| T612 | Birch (Silver) | 9 | # | 250 | # | 3 | # | 5 | # | 4 | # | 4 | # | 3 | - | South | 1.5 | - | M | Located adjacent to hard surface car park | High | Medium | 10+ | C1 | 3.0 | 28.3 |
| T613 | Birch (Silver) | 7 | # | 250 | # | 3 | # | 4 | # | 4 | # | 4 | # | 0.5 | - | South | 0.5 | - | EM | Multi-stemmed at base | Medium | Medium | 10+ | C1 | 3.0 | 28.3 |
| T614 | Beech (Common) | 17 | # | 490 | - | 4 | - | 5.5 | - | 8 | # | 3 | - | 2 | - | West | 0.5 | - | M | Raise canopy to 2m. Crown slightly unpressed by adjacent tree to west. Typical of age and species. | Medium | Medium | 20+ | B2 | 5.9 | 108.6 |
| T615 | Beech (Common) | 18 | # | 570 | - | 8 | # | 2.5 | - | 9 | # | 6.5 | - | 3.5 | - | North west | 0.5 | - | M | Slightly stressed to south by adjacent tree. Raise canopy to 2m. Typical of age and species. | Medium | Medium | 20+ | B2 | 6.8 | 147.0 |
| T616 | Sycamore | 17 | # | 330 | - | 2 | - | 2 | - | 2 | - | 2.5 | - | 3.5 | - | South | 2 | - | M | Poor form, tar spot on leaves, drawn up and suppressed. | Medium | Medium | 10+ | C2 | 4.0 | 49.3 |
| T617 | Sycamore | 18 | # | 475 | - | 7.5 | - | 3 | - | 2 | - | 1.5 | - | N/A | - | N/A | 2 | - | M | Twin stems, poor form with moderate deadwood. Ivy in stems, both stems with cavities and decay. Suppressed and | Low | Medium | 10+ | C2 | 5.7 | 102.1 |
| T618 | Beech (Common) | 18 | # | 660 | - | 7.5 | - | 6 | - | 4 | - | 7 | - | 4 | - | West | 1 | - | M | Twin stems above 1.5m from ground. Snub nosed rib at fusion point of both stems. Moderate deadwood on eastern | Medium | Medium | 20+ | B2 | 7.9 | 197.1 |
| T619 | Beech (Common) | 18 | # | 711 | - | 3 | - | 7 | # | 3 | - | 7.5 | - | N/A | - | N/A | 0.5 | - | M | Twin stems, with further twin stems in southern stem, weak fork. Suppressed to north east. Recommend crown lift to 2m. | Medium | Medium | 20+ | B2 | 8.5 | 228.8 |
| T620 | Beech (Common) | 18 | # | 360 | - | 5 | - | 4 | - | 4 | - | 4.5 | - | 3 | - | West | 2 | - | M | Good form,nice tree. Remove tree to south to better the growing space for this tree. | Medium | Medium | 40+ | A2 | 4.3 | 58.6 |
| T621 | Pine (Scots) | 15 | # | 280 | - | 0.5 | - | 4 | - | 2 | - | 1 | - | N/A | - | N/A | 11 | - | M | Poor form, drawn up and thin stem. Thin canopy, lions tailing. Remove to better tree to north. | Medium | Low | 10+ | C2 | 3.4 | 35.5 |
| T622 | Beech (Common) | 17.5 | # | 943 | - | 6.5 | - | 10 | # | 12 | - | 9 | - | 3 | - | West | 0.5 | - | M | Twin stems at 1.5m, twin stem on southern stem, 3 in total. Concrete above ground pipe at base of stem to north west. | Medium | Medium | 20+ | B2 | 11.3 | 402.4 |
| T623 | Hornbeam | 8 | # | 370 | - | 5 | - | 2.5 | - | 5 | - | 5 | - | 2 | - | West | 0 | - | M | Girdling roots, stunted form, poor shape, cavity at base with decay. Remove epicormic growth from base. Lost main stem | Medium | Medium | 10+ | C1 | 4.4 | 61.9 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|--------------------------|----|---|-----|---|-----|---|-----|---|----|---|-----|---|-----|---|------------|-----|---|---|---|--------|--------|-----|----|------|-------|
| T624 | Pine (Scots) | 11 | # | 360 | - | 0.5 | - | 6 | # | 7 | - | 0.5 | - | 6 | - | South east | 4 | - | M | Looks to have lost its leader, bent form, poor shape, suppressed. | Medium | Medium | 10+ | C2 | 4.3 | 58.6 |
| T625 | Pine (Scots) | 14 | # | 260 | - | 0.5 | - | 0.5 | - | 5 | - | 0.5 | - | N/A | - | N/A | 13 | - | M | Totally suppressed with drawn up form, thin canopy, poor shape. | Medium | Medium | 10+ | C2 | 3.1 | 30.6 |
| T626 | Sycamore | 17 | # | 620 | - | 8 | # | 3 | - | 4 | - | 4 | - | N/A | - | N/A | 2.5 | - | M | Forks at 3m. Overhanging building to north. Remove ivy from stem. Crossing branches. Crowded stems above fork. | Medium | Medium | 20+ | C2 | 7.4 | 173.9 |
| T627 | Pine (Scots) | 15 | # | 320 | - | 6 | # | 0.5 | - | 2 | - | 5 | - | 4 | - | East | 5 | - | M | Poor shape, drawn up form with thin canopy. | Medium | Medium | 10+ | C2 | 3.8 | 46.3 |
| T628 | Beech (Common) | 17 | # | 550 | - | 4 | - | 3.5 | - | 6 | - | 6 | - | 9.5 | - | West | 2.5 | - | M | Two stems, potential weak fork at 2m. Thin canopy, slightly suppressed. | Medium | Medium | 20+ | B2 | 6.6 | 136.9 |
| T629 | Beech (Common) | 17 | # | 640 | - | 3 | - | 7 | # | 7 | - | 6 | - | 3.5 | - | South | 0.5 | - | M | Remove ivy from stem. Clear out minor internal deadwood from canopy. Typical of age and species. | Medium | Medium | 20+ | B2 | 7.7 | 185.3 |
| T630 | Beech (Common) | 17 | # | 830 | - | 6 | - | 7 | # | 8 | - | 6 | - | 3.5 | - | East | 0.5 | - | M | Twin stems, raise canopy to 2m. Typical of age and species. | Medium | Medium | 40+ | A1 | 10.0 | 311.7 |
| T631 | Sycamore | 17 | # | 760 | - | 9 | - | 5.5 | - | 7 | - | 5 | - | N/A | - | N/A | 2 | - | M | Forks at 1.5m. Thin canopy, crossing branches, weak forks. | Medium | Medium | 20+ | B1 | 9.1 | 261.6 |
| T632 | Pine (Scots) | 8 | # | 240 | - | 0.5 | - | 4 | # | 3 | - | 0.5 | - | N/A | - | N/A | 8 | - | M | Poor shape, drawn up form with thin canopy. | Low | Low | 10+ | C1 | 2.9 | 26.1 |
| T633 | Lime (Common) | 11 | # | 530 | - | 7 | - | 3 | - | 4 | - | 6 | - | 2 | - | West | 0.5 | - | M | Remove epicormic growth from base. Suppressed to south, crossing branches. | Medium | Medium | 20+ | C1 | 6.4 | 127.1 |
| T634 | Lime (Common) | 17 | # | 400 | # | 5 | - | 3 | - | 5 | - | 6 | - | N/A | - | N/A | 0.5 | - | M | Fork at 2.5m. Typical of age and species. | Medium | Medium | 20+ | B1 | 4.8 | 72.4 |
| T635 | Sycamore | 15 | # | 552 | - | 1.5 | - | 7 | - | 5 | - | 1.5 | - | N/A | - | N/A | 2 | - | M | Twin stems, thin canopy. Cavity at 1.5m northern stem. Typical of age and species. | Medium | Medium | 20+ | C1 | 6.6 | 138.0 |
| T636 | Sycamore | 16 | # | 500 | - | 3 | - | 8 | # | 2 | - | 7 | - | 2.5 | - | North | 2.5 | - | M | Thin canopy, forks at 1.8m. Slightly suppressed. Typical of age and species. | Medium | Medium | 20+ | C1 | 6.0 | 113.1 |
| T637 | Hornbeam | 15 | # | 330 | - | 4.5 | - | 4.5 | - | 4 | - | 6 | - | N/A | - | N/A | 0.5 | - | M | Nice tree, good shape. Small cavity 1.8m south with minor decay. Raise canopy to 2m. | Medium | Medium | 20+ | B1 | 4.0 | 49.3 |
| T638 | Pine (Scots) | 11 | # | 330 | - | 0.5 | - | 6.5 | # | 1 | - | 3 | - | N/A | - | N/A | 3 | - | M | Drawn up form, poor shape, suppressed. Generally poor. | Medium | Medium | 20+ | C1 | 4.0 | 49.3 |
| T639 | Pine (Scots) | 9 | # | 240 | - | 1 | - | 4.5 | # | 1 | - | 2 | - | N/A | - | N/A | 3 | - | M | Drawn up form, poor shape, suppressed. Generally poor. | Medium | Medium | 20+ | C1 | 2.9 | 26.1 |
| T640 | Sycamore | 16 | # | 566 | - | 6 | - | 4 | - | 6 | - | 4 | - | N/A | - | N/A | 3.5 | - | M | Forks at 0.5m. Suppressed to west. Remove adventitious growth on stem to 2m clear stem. Typical of age and species. | Medium | Medium | 20+ | B1 | 6.8 | 144.8 |
| T641 | Pine (Scots) | 11 | # | 190 | - | 0.5 | - | 0.5 | - | 3 | - | 0.5 | - | N/A | - | N/A | 9 | - | M | Thin drawn up form. Poor shape, suppressed. | Low | Medium | 10+ | C1 | 2.3 | 16.3 |
| T642 | Beech (Common) | 18 | # | 530 | - | 7.5 | - | 3 | - | 5 | - | 4 | - | 3 | - | West | 0.5 | - | M | Good shape, some crossing branches. Typical of age and species. | Medium | Medium | 40+ | A1 | 6.4 | 127.1 |
| T643 | Sycamore | 12 | # | 290 | - | 2 | - | 2 | - | 5 | - | 2 | - | 2 | - | South | 2 | - | M | Remove epicormic growth at base. Poor shape, thin canopy. | Medium | Medium | 10+ | C1 | 3.5 | 38.1 |
| T644 | Sycamore | 17 | # | 533 | - | 5 | - | 6 | # | 6 | - | 1 | - | N/A | - | N/A | 3.5 | - | M | Forks at 0.5m. Slightly suppressed to west. Typical of age and species. Potential weak fork at base. | Medium | Medium | 20+ | B1 | 6.4 | 128.4 |
| T645 | Sycamore | 18 | # | 694 | - | 5 | - | 8 | # | 4 | - | 5 | - | N/A | - | N/A | 2 | - | M | Forks at 0.5m. Twin stem each with twin stems. Minor cavities observed, minor deadwood. | Medium | Medium | 20+ | B1 | 8.3 | 218.1 |
| T646 | Sycamore | 16 | # | 495 | - | 1.5 | - | 6 | # | 1 | - | 6.5 | - | N/A | - | N/A | 2 | - | M | Suppressed to north east. Weak forks observed. Girdling exposed roots. Forks at 1m poor shape. | Medium | Medium | 20+ | B1 | 5.9 | 110.9 |
| T647 | Sycamore | 16 | # | 450 | - | 4 | - | 4 | - | 3 | - | 3 | - | N/A | - | N/A | 3 | - | M | Three stems, fork at 0.5m. Poor shape, thin canopy. | Medium | Medium | 20+ | C1 | 5.4 | 91.8 |
| T648 | Sycamore | 15 | # | 410 | - | 0.5 | - | 8 | - | 2 | - | 0.5 | - | 1.5 | - | East | 3.5 | - | M | Poor form, suppressed canopy. Forks at 2m. | Medium | Medium | 20+ | B1 | 4.9 | 76.1 |
| T649 | Beech (Common) | 17 | - | 500 | - | 3.5 | - | 4.5 | - | 5 | - | 9 | - | 3.5 | - | North east | 0.5 | - | M | Slightly suppressed, good form. Typical of age and species. Recommend crown lift to 2m. | Medium | Medium | 40+ | A1 | 6.0 | 113.1 |
| T650 | Sycamore | 16 | - | 660 | - | 6 | - | 2 | - | 5 | - | 7 | - | 2 | - | South | 2.5 | - | M | Forks at 2m, open canopy. Typical of age and species. Remove epicormic growth from base. | Medium | Medium | 20+ | C1 | 7.9 | 197.1 |
| T651 | Sycamore | 17 | - | 780 | - | 9 | - | 8 | - | 8 | - | 8 | - | 2 | - | South | 2 | - | M | Typical of age and species. Crossing and fused branches. Really good form, dense canopy, great tree. | Medium | Medium | 40+ | A1 | 9.4 | 275.3 |
| T652 | Sycamore | 11 | - | 283 | - | 2.5 | - | 2.5 | - | 3 | - | 2.5 | - | N/A | - | N/A | 0 | - | M | Twin stem, dead. | Low | Low | <10 | U | 3.4 | 36.2 |
| T653 | Beech (Common) | 17 | - | 550 | - | 10 | - | 6 | - | 10 | - | 10 | - | 5 | - | South east | 4.5 | - | M | Good shape, reive abscised branch at 4m east. Minor deadwood. mtypical of age and species. | Medium | Medium | 40+ | A1 | 6.6 | 136.9 |
| T654 | Pine (Scots) | 15 | - | 320 | - | 0.5 | - | 1 | - | 3 | - | 0.5 | - | N/A | - | N/A | 14 | - | M | Poor drawn up form. Thin canopy, poor shape. | Low | Low | 10+ | C1 | 3.8 | 46.3 |
| T655 | Sycamore | 15 | # | 370 | - | 5 | - | 4 | - | 1 | - | 5 | - | 4 | - | North west | 0 | # | M | Fibre buckling on northern base of stem, several partially occluded wounds. Remove adventitious growth from stem | Medium | Medium | 10+ | C1 | 4.4 | 61.9 |
| G656 | Cherry laurel, sycamore. | 10 | # | 500 | - | 0 | # | 0 | # | 0 | # | 0 | # | N/A | # | N/A | 0.5 | # | M | Mature cherry laurel, deadwood, pruning damage, poor group. 1 sycamore could be retained. Location shown on | Medium | Medium | 10+ | C2 | 6.0 | 113.1 |
| G657 | Sycamore, beech | 17 | # | 500 | - | 0 | # | 0 | # | 0 | # | 0 | # | N/A | - | N/A | 2 | # | M | Group of 4 sycamore and 1 beech. Beech has large cavity from base to 1.5m with internal decay. Individually fair, all | Medium | Medium | 10+ | C2 | 6.0 | 113.1 |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|---------|-----|---|-----|---|-----|---|-----|---|---|---|-----|---|------|---|-------------|-----|---|----|--|--------|--------|-----|----|-----|------|
| T658 | Birch | 6 | # | 75 | - | 1.5 | # | 1.5 | # | 2 | # | 1.5 | # | 1.5 | # | North | 1.5 | # | EM | Major bark damage to stem. | Medium | Medium | 20+ | C1 | 0.9 | 2.5 |
| T659 | Cherry | 6.5 | # | 160 | - | 2 | # | 2 | # | 2 | # | 2 | # | 1.5 | # | North-east | 1 | # | EM | Exposed root plate, average condition. | Medium | Medium | 20+ | C1 | 1.9 | 11.6 |
| T660 | Cherry | 6.5 | # | 160 | - | 2 | # | 2 | # | 2 | # | 2 | # | 1.5 | # | North | 1.5 | # | EM | Exposed root plate, average condition | Medium | Medium | 20+ | C1 | 1.9 | 11.6 |
| T661 | Birch | 5 | # | 75 | - | 1.5 | # | 1.5 | # | 2 | # | 1.5 | # | 0.5 | # | North-west- | 0.5 | # | EM | Multi-stemmed tree, no obvious defects | Medium | Medium | 20+ | C1 | 0.9 | 2.5 |
| T662 | Birch | 9 | # | 120 | - | 2 | # | 2 | # | 2 | # | 2 | # | 1.5 | # | North | 1.5 | # | EM | Good form, no obvious defects | Medium | Medium | 20+ | B1 | 1.4 | 6.5 |
| T663 | Rowan | 4 | # | 75 | - | 1 | # | 1 | # | 1 | # | 1 | # | 1.2 | # | North | 1.2 | # | EM | No obvious defects | Medium | Medium | 20+ | C1 | 0.9 | 2.5 |
| T664 | Rowan | 5 | # | 80 | - | 1.5 | # | 1 | # | 2 | # | 1.5 | # | 1 | # | East | 1.5 | # | EM | Suppressed by telecom pole to south | Medium | Medium | 20+ | C1 | 1.0 | 2.9 |
| T665 | Cherry | 9 | # | 250 | - | 3 | # | 3 | # | 3 | # | 3 | # | 3 | # | North-east | 3 | # | EM | Suppressed by neighbouring tree, minor damage to root plate. | Medium | Medium | 20+ | C1 | 3.0 | 28.3 |
| T666 | Cherry | 9 | # | 240 | - | 3 | # | 3 | # | 3 | # | 2.5 | # | 1.85 | # | East | 2 | # | EM | Suppressed by neighbouring tree, minor damage to root plate. | Medium | Medium | 20+ | C1 | 2.9 | 26.1 |
| T667 | Cherry- | 8 | # | 280 | - | 3.5 | # | 3.5 | # | 3 | # | 3 | # | 1.8 | # | East | 1.8 | # | EM | Minor damage to exposed roots, low canopy over highway. | Medium | Medium | 20+ | B1 | 3.4 | 35.5 |

