

L	04.07	.19	Level & Retaining Wall Revisions		
М	20.07.21		Planter adjustment throughout		
Ν	22.09.21		Planter adjustment throughout		
0	21.10.21		Minor Adjustments to comments		
Title:		Hard	l landscape plan		
Project: Client:		Heyford Park Village Centre Dorchester Living			
Date: Scale:		March 17 1:200@ A1			
Drawing No: Rev:		16	19 A7 02 0		

ND aing m	atoriala
cing m	aterials Proposed Chinese Granite in 60% Silver Grey, 20% Pink, 20% Beige; 300mm gauge at random lengths; or similar approved TOTAL: 870m2 (including 340m2 within Link)
	Proposed Charcon Woburn rumbled in Rustic; 134 x 100/134/201 x 80mm; or similar approved TOTAL: 525m2
	Proposed Chinese Granite edging in Dark Grey; 300mm gauge at random lengths; or similar approved TOTAL: 20m2
	Proposed asphalt surfacing TOTAL: 600m2
	Parking bays to be demarcated using thermoplastic in white
	Tactile Paving Charcon Blister paving 400x400x65mm staggered bond colour; Grey TOTAL: 1.5m2
	Tactile Paving Chinese Granite Hazard paving in Beige; or similar approved; staggered bond TOTAL: 6m2
and e	dgings
	Charcon Eco Countryside Classic wide top Kerb in Grey; L914mm x H205mm x W290mm; or similar approved; to be laid flush with paving surface TOTAL: 42m
	Charcon Eco Countryside classic Kerb in Grey; L914mm x H255mm x W125mm; or similar approved. TOTAL: 60m
	Charcon Eco Countryside classic Kerb in Grey; L914mm x H255mm x W125mm; or similar approved; to be laid flush with paving surface TOTAL 15m
	Charcon Eco Countryside Classic crossing Kerb in Grey; L914mm x H255mm x W125mm; or similar approved . TOTAL: 3m
	Charcon Eco Countryside Classic flat top Edging in Grey; L914mm x H150mm x W50mm; or similar approved; to be laid flush with paving surface. TOTAL: 5.5m
	Charcon British Standard Bullnose Edging in Grey; L914mm x H255mm x W50mm; or similar approved . TOTAL: 60m
t furnit	ure
]	Proposed FalcoLinea Seat; or similar approved TOTAL: 12
	Proposed FalcoLinea litter bin; or similar approved TOTAL: 5
	Proposed Bespoke Planter; in Marziale Brick TOTAL: 1
	Proposed Steel Cube Planters; 1400x1400x1000mm by IOTA TOTAL: 10
	Proposed Steel Trough Planter; 500x1500mm; by IOTA TOTAL: 4
	Proposed Bespoke Steel Planters; 4000x600x450mm & 2500x600x450mm; by IOTA TOTAL: 1 & 1
	Falco Sheffield Cycle Stand; or similar approved TOTAL: 22
1	Proposed FalcoSpan Cycle Shelter; or

<u></u>
STEP STEP
1:60
Ε
PUPS

Proposed parking humps Rediweld Coach Stop 220 x 1000 x 115mm; or similar approved TOTAL: 22	
Proposed handrails / guardrails, to be	

specified TOTAL: 20m

Proposed glass balustrade without handrails, to be specified TOTAL: 5m

Proposed drainage to engineers details

Retaining structure - to engineer's specifications

Proposed steps

Proposed ramps, slopes

GRP Utility Cabinet - ET2 TOTAL: 2

PUPS02 5050 TOTAL: 6

Gas Meter Housing - EC3 TOTAL: 1