

PLANTING SCHEDULE

HEDGEROW PLANTING

A mix of 75% thorn hedging plants, 15% holly and 10% viburnum planted in two rows 450 apart and at 450 intervals and staggered each with cane support and rabbit guard.

Mulch ground and cover with tree bark to prevent weed growth.

TREE PLANTING

Trees to be planted as 2.400 bare root stock in tree planting compost with 37mm pipe to root ball for watering. Stake, three ties and rabbit guard to each. Planting to be at 6.000 intervals and staggered.

Mulch ground and cover with tree bark to prevent weed growth.

A mixture of:-

20%	Hawthorn	(Crataegus Monogyna)
10%	English Oak	(Quercus Robur)
20%	Field Maple	(Acer Campestre)
10%	Common Alder	(Alnus Glutinosa)
10%	Hornbeam	(Campinus Betulus)
10%	Common Beech	(Fagus Sylvatica)
5%	Common Hazel	(Corylus Avellana)
5%	Douglas Fir	(Psuedotsuga Menziesii)
5%	Flowering Crab	(Malus Sylvestris)
5%	Wild Cherry	(Prunus Avium)

CAM/2146
MAY 2022