



- NOTES
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS DRAWINGS. ANY DISCREPANCIES FOUND BETWEEN INFORMATION SHOWN ON THIS OR ANY OTHER DRAWING SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY AND PRIOR TO WORKS COMMENCING ON SITE.
 - ALL CONCRETE AT OR BELOW GROUND LEVEL ON SITE SHALL BE ABLE TO WITHSTAND SULPHATE CONCENTRATIONS IN ACCORDANCE WITH BRE SPECIAL DIGEST 1.
 - DOMESTIC DRAINAGE SHALL BE OSMA 'OSMADRAIN', HEPWORTH OR OF SIMILAR APPROVED TYPE, BEDDED STRICTLY IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS.
 - WHERE CONCRETE BED AND SURROUND IS SPECIFIED JOINT FILLER SHOULD BE PROVIDED AT EVERY JOINT. THE FILLER MAY BE EXPANDED POLYSTYRENE 25mm THICK OR FLEXCELL CUT TO THE SHAPE OF THE BED AND SURROUNDED AND SUCH THAT THE INGRESS OF CONCRETE INTO THE PIPE IS PREVENTED.
 - TO ALLOW FOR POSSIBLE DIFFERENTIAL MOVEMENT A FLEXIBLE JOINT MUST BE INCORPORATED IN EACH SECTION OF PIPELINE WITHIN 150mm OF WHERE IT ENTERS A BUILDING OR CONNECTS WITH A MANHOLE, WALL OR OTHER STRUCTURE: - SEE MANUFACTURERS INSTRUCTIONS.
 - ALL PIPEWORK GENERALLY TO BE BEDDED AS FOLLOWS UNLESS SHOWN DIFFERENTLY ON CARRIAGEWAY LONGITUDINAL SECTIONS
 - (i) UNDER VEHICULAR AREAS WHERE COVER IS LESS THAN 900mm UNDER PEDESTRIAN AREAS WHERE COVER IS LESS THAN 600mm. ALL GULLY CONNECTIONS. } CONCRETE BED AND SURROUND.
 - (ii) UNDER VEHICULAR AREAS, PEDESTRIAN AREAS WHERE DEPTHS GIVEN IN (i) ARE EXCEEDED; } CLASS S BEDDING.
 - MANHOLE COVERS SHALL BE INSTALLED PARALLEL TO KERB LINES.
 - MANHOLE COVERS SHALL BE TO BS EN 124 AS FOLLOWS : -
 - ROADS - CLASS D400
 - PARKING AREAS - CLASS C250
 - LANDSCAPED AREAS - CLASS B125




Mini Access Chamber
SCALE 1:20




Typical Section Through Cellular Trench Soakaway in Soft Landscape Area
Scale = 1:20

- NOTES
- OSMA AQUACELL CORE UNITS TO BE INSTALLED STRICTLY IN ACCORDANCE WITH MANUFACTURERS REQUIREMENTS.
 - REFER TO PLANS FOR SOAKAWAY SIZES.




Class S Bedding
SCALE 1:10




Concrete Bed And Surround
SCALE 1:10

NOTE - TRENCH WIDTH (W) = MAXIMUM - EXTERNAL PIPE DIAMETER (E) + 600mm
MINIMUM - EXTERNAL PIPE DIAMETER (E) + 300mm


WHERE COVER TO TOP OF PIPE IS MINIMAL DURING THE CONSTRUCTION PERIOD THE CONTRACTOR SHALL TAKE ALL MEASURES TO AVOID DAMAGE TO THE PIPEWORK. IT IS THE CONTRACTORS RESPONSIBILITY TO MAKE GOOD ANY DAMAGE CAUSED.



Threshold Drainage Channel Detail
SCALE 1:10



External Rodding Eye Detail
SCALE = 1:10



Inspection Chamber Type Q (Backdrop)
SCALE 1:10

THIS DETAIL SHALL BE READ IN CONJUNCTION WITH DETAIL L.

T1	Apr 22	TENDER ISSUE.	AJV	-
REV	DATE	DESCRIPTION	BY	CHK

STATUS
TENDER

This drawing is the property and copyright of the Consulting Engineer and shall not without written consent be communicated to a third party.



SIBFORD FERRIS BANBURY

Domestic Drainage Construction
Details Sheet 2 of 2

SDP CONSULTING ENGINEERS

Head Office, Suite 3, Salar House, Campfield Road, St Albans, Hertfordshire, AL1 5HT.
Tel. 01727 844606. Fax. 01727 830771
Email. mail@sdpce.co.uk

Southern Office, 21a Bargates, Christchurch, Dorset, BH23 1QD.
Tel. 01727 844606. Fax. 01202 490601
Email. sdpsouth@sdpce.co.uk

SCALE AT A1	DRAWN	DATE
See Drg	AJV	Apr 22
CHECKED	PASSED	
DRAWING NO.	REV.	
E21-077-169	T1	