



notes

Key

- Attenuation Basin
- Hardstanding area designed to pond during exceedance event
- Indicative exceedance flow route

- Key Principles of Exceedance Strategy:**
- All flows to be directed towards the existing site discharge in the southeast of the site
 - Levels adjacent to site boundary to be set such that exceedance runoff is contained within the site
 - Levels of large car parking areas to be set to allow shallow ponding in these areas during exceedance events. Indicative areas marked on drawing.
 - Detailed site levels to be set such that runoff generated in exceedance event is conveyed along site roads towards attenuation basins and soft landscaped areas where possible.

A	17.05.22	ISSUED FOR PLANNING.	RM
-	21.04.22	ISSUED FOR INFORMATION	OF

job
**GRAVEN HILL SITE
D1, BICESTER**

title
**FIGURE 08 - OUTLINE SITE
SURFACE WATER
EXCEEDDANCE STRATEGY**

drawn	checked
RM	OF
date	scale (original - A1)
JAN '22	1:2500

Alan Baxter

75 Cowcross Street London EC1M 6EL
tel 020 7250 1555
email aba@alanbaxter.co.uk
www.alanbaxter.co.uk

drg. no.	REV.
1923/01/SK04	A

Alan Baxter Ltd is a limited company registered in England and Wales, number 06002598. Registered office as above.