

Client: Bicester Gateway Ltd

Bicester Gateway, Wendlebury Road, Bicester (shell & core)

BREEAM 2018 New Construction Pre-assessment Report



Date: 29th June 2022

Report Status: Rev 1.1 – For Issue SBL Project No: SBL508 BREEAM Assessor: Phil Garlick





Quality Assurance

This report has been checked in accordance with SBL's internal Quality Assurance procedures.

Issue	Rev	Prepared & checked by	Description	Issued
1	0	Phil Garlick	For Issue	28.05.22
1	1	Phil Garlick	For Issue	29.06.22

Contact Details

Phil Garlick, Director Sustainably Built Ltd Office 15, York Eco Business Centre Amy Johnson Way, Clifton Moor York, YO30 4AG

Tel: 07786 195695 Email: phil.garlick@sustainablybuilt.co.uk



TABLE OF CONTENTS

TABL	E OF CONTENTS	
TA	BLES AND APPENDICES	
1.0	EXECUTIVE SUMMARY	5
2.0	DISCLAIMER	7
3.0	COPYRIGHT	7
4.0	INTRODUCTION	
5.0	PROJECT DESCRIPTION	
6.0	BREEAM ASSESSMENT METHODOLOGY	9
7.0	RESULTS, CONCLUSIONS AND RECOMMENDATIONS	10
8.0	REFERENCES	13

TABLES AND APPENDICES

Tables:

- Table 1 BREEAM Workshop Attendees
- Table 2 Actions required to achieve the cost options
- Table 3 Actions required to resolve the uncertain credits
- Table 4 BREEAM credit assessment

Appendices:

Appendix 1 – Details of the BREEAM methodology



1.0 EXECUTIVE SUMMARY

SBL were commissioned by David Bridges of Goodrich LLP on behalf of Bicester Gateway Ltd as client and developer to provide BREEAM assessment services for the development of a new business park Bicester Gateway on Wendlebury Road in Bicester. The assessment covers the developer's base-build and is being carried out using the BREEAM 2018 New Construction method assuming a 'shell & core' level of fit-out for BREEAM purposes. A BREEAM rating of Excellent is required by Bicester Gateway Ltd.

Fig 1 overleaf shows the current predicted BREEAM score and rating. This shows that 74.7% is achieved subject to the submission of suitable evidence. This achieves the required Excellent rating (minimum 70% required) with a near suitable margin of comfort. All mandatory credits and criterion for an Excellent rating will be achieved.

Further to this, there are:


- 3.4% of cost options available. The actions required to achieve these credits are set out in Table 2 in Section 7.0 of this report.
- 23.0% of credits which are uncertain at this stage of which 17.5% are realistically achievable with some, potentially at little or no cost to the project. The actions required to achieve these credits are set out in Table 3 in Section 7.0 of this report.

A BREEAM rating of Excellent is achievable on this project. The following are recommended at this stage:

- The cost options and uncertain credits in Tables 2 & 3 should be reviewed to confirm how the margin of comfort in achieving Excellent can be increased.
- In order to comfortably achieve a BREEAM Excellent rating, a score of comfort of 75% should be considered as the target minimum at this early stage in the development of the scheme. This is as a contingency to allow for unforeseen issues arising between now and the end of construction and also to allow for BRE's QA check of the final BREEAM report.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)







2.0 DISCLAIMER

This report has been prepared by Sustainably Built Ltd. (SBL) using all reasonable skill, care and diligence on behalf of the consultant. The study to which this report relates has been carried out in accordance with the strict quality requirements prescribed by the Building Research Establishment (BRE).

In order to prepare this report, SBL has made use of evidence supplied by the design team. This has been both physical, e.g. documentation such as reports, drawings, plans, correspondence, etc., and anecdotal, i.e. verbally reported information from meetings, telephone calls, etc. SBL's professional liability is strictly limited to the provision of assessment services against criteria set out by the Building Research Establishment (BRE). The consultant accepts no responsibility for misinformation or inaccurate information supplied by any third party as part of this assessment.

This document has been prepared in accordance with the scope of SBL's appointment with its client and is subject to the terms of that appointment. It is addressed to and for the sole use and reliance of SBL's client. SBL accept no liability for any use of this document other than by SBL's client and only for the purposes, stated in the document, for which it was prepared and provided. No person other than the client may copy (in whole or in part) use or rely on the contents of this document, without the prior written permission of the Company secretary of SBL. Any advice, opinions, or recommendations within this document should be read and relied upon only in the context of the document as a whole. The contents of this document are not to be construed as providing legal, business or tax advice or opinion.

If the reader disagrees with any statement, or finds any information contained within this report to be inaccurate, SBL request that the writer is informed immediately.

3.0 COPYRIGHT

The BREEAM name and logo are registered trademarks of the Building Research Establishment Ltd. Copyright exists on BREEAM and it may not be used or reproduced in any form or for any purpose without prior written consent of BRE.



4.0 INTRODUCTION

SBL were commissioned by David Bridges of Goodrich LLP on behalf of Bicester Gateway Ltd as client and developer to provide BREEAM assessment services for the development of a new business park Bicester Gateway on Wendlebury Road in Bicester. The assessment covers the developer's base-build and is being carried out using the BREEAM 2018 New Construction method assuming a 'shell & core' level of fit-out for BREEAM purposes. A BREEAM rating of Excellent is required by Bicester Gateway Ltd.

5.0 PROJECT DESCRIPTION

The development is located on former agricultural land and comprises a total of 12 No. units in four terraces with unit sizes in the range 817 to 1128m² gross floor area. Total development gross floor area is 11 745m². The buildings will be constructed shell & core with a Cat A fit-out to the offices in the developer's base-build. The buildings have a structural steel portal frame with elevations and roof of built-up and composite metal cladding. There is allowance in the substructure design for the addition of a mezzanine first floor slab and associated structural steelwork by the tenants.

The M&E services in the base-build will comprise the following:

- Space heating and cooling to the offices and reception from VRF system.
- No space heating, cooling, mechanical ventilation or lighting to the warehouse/operational area.
- DHW from point-of-use electric water heaters.
- Full supply & extract mechanical ventilation (14 lit/sec) with heat recovery to the offices.
- Basic BMS specified.
- LZC possibly from air-source heat pumps to the VRF system. Also, possible addition of PV to the roof if required.
- No gas supply to the development.



6.0 BREEAM ASSESSMENT METHODOLOGY

Appendix 1 to this report provides a brief summary of the BREEAM methodology.

A BREEAM Workshop was held on-line on the 23rd May 2022. The following members of the team were present:

Table 1 – BREEAM Workshop Attendees

	Initials
Phil Garlick, SBL - BREEAM assessor	PG
David Bridges, Goodrich LLP - PM & QS	DB
Narinder Bangar, BMP - Civil & Structural Engineer	NB
Simon Poole, AJA Architects	SP
Ritesh Parekh, AJA Architects	RP
Jonathan Bell, Spie - MEP Engineer	JB
Akvile Gecaite, Goodrich LLP - Assistant PM & QS	AG
Jacob Hepworth-Bell, Ecology Solutions	JHB
Bruce Usher, Bloombridge – Client & Developer	BU
Richard Cutler, Bloombridge – Client & Developer	RC

In this assessment, all credits are classified using a simple A, B, C, D and E whereby credits are assessed in terms of the relative ease with which they could be achieved by the developments and are categorised as follows:

- A. Credits that are achieved (and signed off);
- B. Credits that are achieved subject to provision of suitable evidence;
- **C.** Credits that are not achieved but could be achieved with additional cost;
- **D.** Credits that are uncertain at this stage; and
- E. Credits that are not achievable.

The above system provides a simple method for project teams to assess the most cost-effective options for achieving the required BREEAM rating. The BREEAM thresholds given ratings are shown below.



Pass = 30% Good = 45% Very Good = 55% Excellent = 70% Outstanding = 85%

All BREEAM ratings contain mandatory credits which must be achieved for a particular rating band.

Table 4 details the assessment status of the development with details of compliance with BREEAM credit criteria. This BREEAM Report provides a further snapshot of the buildings BREEAM performance under current proposals and sets out viable options to achieve the required BREEAM score and rating.

7.0 RESULTS, CONCLUSIONS AND RECOMMENDATIONS

Fig 1 shows the current predicted BREEAM score and rating. This shows that 74.7% is achieved subject to the submission of suitable evidence. This achieves the required Excellent rating (minimum 70% required) with a near suitable margin of comfort. All mandatory credits and criterion for an Excellent rating will be achieved.

Further to this, there are:

- 3.4% of cost options available. The actions required to achieve these credits are set out in Table 2 below.
- 23.0% of credits which are uncertain at this stage of which 17.5% are realistically achievable with some, potentially at little or no cost to the project. The actions required to achieve these credits are set out in Table 3 below.

A BREEAM rating of Excellent is achievable on this project. The following are recommended at this stage:

• The cost options and uncertain credits in Tables 2 & 3 should be reviewed to confirm how the margin of comfort in achieving Excellent can be increased.



 In order to comfortably achieve a BREEAM Excellent rating, a score of comfort of 75% should be considered as the target minimum at this early stage in the development of the scheme. This is as a contingency to allow for unforeseen issues arising between now and the end of construction and also to allow for BRE's QA check of the final BREEAM report.

Table 2 - Actions required to achieve the cost options

Note: Table 2 only provides 'headline' details of the actions required to achieve the cost options (rated as 'C' in Table 4). Further details of the required actions are given in Table 4.

Credit Ref.	Credit Title	Credit % worth	Actions required (all to meet full BREEAM requirements)				
	Elemental life cycle cost (LCC)	1.22	Undertake an elemental level life-cycle cost plan at Concept Design (RIBA Stage 2).				
Man02	Component level LCC options appraisal	0.61	Undertake a component level life-cycle costing option appraisal during Technical Design (RIBA Stage 4).				
Hea05	Acoustic performance	0.80	Employ an acoustician and confirm that indoor ambient noise levels will meet the design ranges given in Section 7 of BS 8233:2014.				
Wst05	Adaptation to climate change	0.78	Undertake adaptation to climate change study and implement the recommendations.				
	Total %	3.4					



BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)

Table 3 - Actions required to resolve uncertain credits

Note: Table 3 only provides 'headline' details of the actions required to resolve the uncertain credits (rated as 'D' in Table 4). Further details of the required actions are given in Table 4.

Credit Ref.	Credit Title	Credit % worth	Actions required (all to meet full BREEAM requirements)				
Hea01	Daylighting	0.80	Undertake daylight modelling to confirm whether BREEAM criteria is met.				
Hea02	Ventilation	0.80	 Confirm whether fresh air is provided into the building in accordance with the criteria of the following relevant standards for ventilation: BS ISO 17772-1:2017 (mechanically ventilated spaces) CIBSE AM10 (naturally ventilated spaces). 				
Hea06	Security of site and building		Confirm whether the security recommendations of a Security Needs Assessment will be implemented. Any shortfalls in implementation to be agreed with the security specialist.				
Ene01	Reduction of energy use and carbon emissions	Up to 2.67	Confirm whether an EPR _{NC} of up to 0.80 is achieved.				
Wat01	Water consumption	0.78	Confirm whether the sanitary spec achieves a 55% improvement on the BREEAM Wat01 notional baseline.				
Mat01	Life cycle impacts	1.25	Confirm whether LCA study achieves the 6 th credit for comparison with the BREEAM LCA benchmark during Concept & Technical Design stages.				
Mat02	Specification of products with a recognised EPDs.	1.25	Confirm whether sufficient construction products have compliant EPDs to meet BREEAM threshold score.				
Mat03	Measuring responsible sourcing	1.25	Confirm whether a Mat03 Calculator score of at least 30% can be achieved.				
Mat06	Material efficiency	1.25	Confirm whether a material efficiency study and strategy can be demonstrated from RIBA Stage 1.				



BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)

Credit Ref.	Credit Title	Credit % worth	Actions required (all to meet full BREEAM requirements)
LE01	Contaminated land	1.15	Confirm whether there is significant ground contamination requiring remediation.
LE04 (& LE05)	Change and enhancement of ecology		Confirm whether the change in ecological value occurring as a result of the project achieves at least a 75% net gain.
Wst01 Exemp- lary	Construction waste management	1.00	 Confirm whether the following targets are met for non-hazardous waste: Construction waste generated is limited to no more than 1.6m³ of 1.9 tonnes per 100m² GIFA. The following are diverted from landfill: Construction waste – At least 85% by volume or 90% by weight. Excavation waste – At least 95% by volume or weight.
Wst02 Exemp- lary	Use of recycled and sustainably sourced aggregates (inc. Exemplary)	1.00	Aggregate sourcing to achieve a Wst02 Calculator score of at least 6 points.
	Total %	Up to 17.5	

8.0 <u>REFERENCES</u>

The references used in this assessment are listed in a separate document.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Mana	igemer	nt			1	
	Project delivery planning	 Prior to completion of the Concept Design, the project delivery stakeholders (see Definitions on page 37) meet to identify and define for each key phase of project delivery: Roles Reponsibilities Consider each one of the following items when defining roles, responsibilities and contributions for each key phase of the project: End user requirements Almost of the design and design strategy Particular installation and construction requirements or limitations Occupiers' budget and technical expertise in maintaining any proposed systems Maintainability and adaptability of the proposals Operational energy (see Assessment scope on page 121) Requirements for the production of project and end user documentation	1	0.61	в	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. Appointment documentation and DTM minutes will be provided. DAS will show design evolution. SBL emailed brief 29.05.22. REF 1 provides DTM minutes & agendas. REF 5 provides the following from PM: Minutes for DTM Nos 1-4 inc. Development programme with two options for concurrent and consecutive planning and tender processes. DTMO1 para 3.04.1 confirms a discussion re targeting BREEAM Excellent. REF 6 provides the following from PM: Updated development programme with concurrent planning and tender processes. Project Execution Plan which includes a Stage 2 Design Responsibility Matrix in Appendix B. This credit is achieved subject to further evidence. <u>Pre-planning actions/evidence</u> Goodrich to provide Design Responsibility Matrix for Stages 3-6 inc. (email request 29.05.22 & 2.8.06.22. Latest is DB email 29.06.22). AJA to provide a brief narrative in the DAS confirming how the initial brief has been influenced (email request 29.05.22).
	Stakeholder consultation (interested parties)	 Prior to completion of the Concept Design, the design team consult with all interested parties (see Definitions) on matters that cover the minimum consultation content (see Methodology). Demonstrate how the stakeholder contributions and consultation exercise outcomes influence the Initial Project Brief and Concept Design. Prior to completion of the detailed design (RIBA Stage 4, Technical Design or equivalent), all interested parties (see Definitions) give and receive consultation feedback. Not applicable to commercial buildings. 	1	0.61	в	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. There has been consultation with several parties and this wil be documented in the Planning Statement or similar. REF 2 provides a Statement of Community Involvement. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 9 provides written details of the local stakeholder consultation on points 1, 2, 5 & 6 of the contents list. REF 10 provides an updated Planning Statement. Paras 2.1 to 2.5 detail the local community consultation and engagement. This credit is achieved subject to further evidence. Pre-planning actions/evidence BGL to provide and updated SCI/Planning Statement to cover contents list pts 3, 4, 7, 8 (email request 29.06.22.).

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Man 01 Project brief and design	Prerequisite for BREEAM Advisory Professional credits (Concept and Developed Design)	8. The project team, including the client, formally agree strategic performance targets (see Definitions) early in the design process (see Definitions), (with the support of the BREEAM AP where appointed).	0	0.00	N/A	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. BREEAM target is set by Bloombridge as the developer as well as the investor. REF 5 provides the following from PM: Minutes for DTM Nos 1-4 inc. Development programme with two options for concurrent and consecutive planning and tender processes. DTM01 para 3.04.1 confirms a discussion re targeting BREEAM Excellent. REF 6 provides the following from PM: Updated development programme with concurrent planning and tender processes. Project Execution Plan. Page 4 confirms "In line with planning policy the development is being designed and constructed to achieve a BREEAM Excellent." The prerequisite criteria are achieved and signed off at design stage.
	BREEAM AP (Concept Design)	 9. Involve a BREEAM AP in the project at an appropriate time and level to: a. Work with the project team, including the client, to consider the links between BREEAM issues and assist them in maximising the project's overall performance against BREEAM, from their appointment and throughout Concept Design. b. Monitor progress against the performance targets (see Definitions) agreed under criterion 8 above throughout all stages after their appointment where decisions critically impact BREEAM performance. c. Proactively identify risks and opportunities related to the achievement of the targets agreed under criterion 8 on the previous page. d. Provide feedback to the project team as appropriate, to support them in taking corrective actions and achieving their agreed performance targets. e. Monitor and, where relevant, coordinate the generation of appropriate evidence by the project team. 	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. Phil Garlick, SBL is appointed at Stage 2. REF 1 provides BREEAM AP Reports, associated email correspondence and DTM minutes & agendas. SBL emailed appointment letter template 29.05.22. REF 5 provides the following from PM: - Minutes for DTM Nos 1-4 inc. - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. This credit is achieved subject to further evidence. <u>Pre-planning actions/evidence</u> BGL to provide a letter of appointment for BREEAM AP (email request 29.05.22. Latest is DB email 22.06.22). SBL to provide AP Reports - Ongoing.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	BREEAM AP (Developed Design)	 10. Criteria 8 and 9 are achieved. 11. Involve the BREEAM AP in the project at an appropriate time and level to: a. Work with the project team, including the client, to consider the links between BREEAM issues and to assist them in maximising the project's overall performance against BREEAM throughout Developed Design. b. Monitor progress against the performance targets agreed under criterion 8 on the previous page throughout all stages where decisions critically impact the specification and tendering process and the BREEAM performance. c. Proactively identify risks and opportunities related to the achievement of the targets agreed under criterion 8 on the project team as appropriate, to support them in taking corrective actions and achieving their agreed performance targets. e. Monitor and, where relevant, coordinate the generation of appropriate evidence by the project team. 	1	0.61	В	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. Phil Garlick, SBL is appointed at Stage 3. REF 1 provides BREEAM AP Reports, associated email correspondence and DTM minutes & agendas. REF 5 provides the following from PM: Minutes for DTM Nos 1-4 inc. Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. SBL emailed appointment letter template 29.05.22. This credit is achieved subject to further evidence.
Man 02 Life cycle cost and service life planning	Elemental LCC	 A competent person (see Definitions on the facing page) carries out an outline, entire asset LCC plan at Process Stage 2 (equivalent to Concept Design - RIBA Stage 2) together with any design options appraisals in line with 'Standardised method of life cycle costing for construction procurement' PD 156865: 2008. The elemental LCC plan: Provides an indication of future replacement costs over a period of analysis as required by the client (e.g. 20, 30, 50 or 60 years); Includes service life, maintenance and operation cost estimates. The study period should ideally be agreed by the client, in line with the design life expectancy of the building. However, where the life expectancy of the building is not yet formally agreed (due to being at very early design stages), the default design life of 60 years should be used for modelling purposes (in line with the UK default). 	1	0.61	С	BREEAM meeting 23.05.22 - Project team confirmed that an elemental LCC plan could be developed pre-planning as a cost option. SBL emailed LCC contacts and an outline brief 29.05.22. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. Two credits are cost options at this stage.
Man 02		3. Demonstrate, using appropriate examples provided by the design team, how the elemental LCC plan has been used to influence building and systems design and specification to minimise life cycle costs and maximise critical value.		0.61	C	Pre-planning actions/evidence In the first instance, Goodrich to confirm whether these credits will be pursued (G&T quote email 01.06.22 & ADW quote 06.06.22).

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Man 02 Life cycle cost and service life planning	Component level LCC options appraisal	 4. A competent person develops a component level LCC options appraisal by the end of Process Stage 4 (equivalent to Technical Design – RIBA Stage 4) in line with PD 156865: 2008. The component level LCC includes (where present): a. Envelope, e.g. cladding, windows, or roofing b. Services, e.g. heat source, cooling source, or controls c. Finishes, e.g. walls, floors or ceilings d. External spaces, e.g. alternative hard landscaping, boundary protection. The Component level LCC option appraisal should review all of the above component types (where present). However, you do not need to consider every single example cited under each component; only a selection of those most likely to draw valued comparisons. This is to ensure that a wide range of options are considered and help focus the analysis on components which would benefit the most from appraisal. 5. Demonstrate, using appropriate examples provided by the design team, how the component level LCC options appraisal has been used to influence building and systems design and specification to minimise life cycle costs and maximise critical value. Shell & Core Notes - Component level LCC plan must include all component types installed by the developer. 	1	0.61	С	BREEAM meeting 23.05.22 - Project team confirmed that a component LCC could be undertaken at RIBA Stage 4 as a cost option. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. This credit is a cost option at this stage.
Man 02 Lif	Capital cost reporting	6. Report the capital cost for the building in pounds per square metre of gross internal floor area ($\pounds k/m^2$) as part of the submission to BRE. See also Methodology below and Additional information on page 44.	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.
Man 03 Responsible construction practices	Prerequisite - Legally harvested and traded timber	 All timber and timber-based products used during the construction process of the project are legal and sustainable timber (see Definitions). For other materials there are no prerequisite requirements at this stage. 	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The prerequisite criteria are achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
ractices	Environmental management	 3. All parties who at any stage manage the construction site (e.g. the principal contractor, the demolition contractor) operate an EMS covering their main operations. The EMS must: a. Be third party certified, to ISO 14001: 2015, EMAS (EU Eco-Management and Audit Scheme) or equivalent standard; OR b. In compliance with BS 8555: 2016 have: i. Appropriate structure ii. Reached implementation stage phase four 'implementation and operation of the environmental management system' iii. Completed defined phase audits one to four. 4. All parties who at any point manage the construction site (e.g. the principal contractor, the demolition contractor) implement best practice pollution prevention policies and procedures on site in accordance with Working at construction and demolition sites: PPG6, Pollution Prevention Guidelines. 	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. There is a project requirement for the principal contractor to be ISO14001 certified. This credit is achieved subject to evidence.
Man 03 Responsible construction practices	Prerequisite for the BREEAM AP credit	5. The client and the contractor formally agree performance targets.	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The prerequisite criteria are achieved subject to evidence.
Man 03 R	BREEAM AP (site)	 6. Involve a BREEAM AP in the project at an appropriate time and level to: a. Work with the project team, including the client, to consider the links between BREEAM issues and assist them in achieving and if possible going beyond the design intent, to maximise the project's performance against the agreed performance targets throughout the Construction, Handover and Close Out stages. b. Monitor construction progress against the performance targets agreed under criterion 5 above throughout all stages where decisions critically impact BREEAM performance. c. Proactively identify risks and opportunities related to the procurement and construction process and the achievement of the targets agreed under criterion 5 above. d. Provide feedback to the constructors and the project team as appropriate, to support them in taking corrective actions and achieving their agreed performance targets. e. Monitor and, where relevant, coordinate the generation of appropriate evidence by the project team and the provision to the assessor. 	1	0.61	в	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued in order to achieve the required Excellent rating. This credit is achieved subject to evidence .

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
		ONE CREDIT MANDATORY FOR EXCELLENT One credit 7. Achieve items listed as required for one credit in Table 4.1. Two credits	1	0.61	в	BREEAM meeting 23.05.22 - Project team confirmed that these credits will be pursued.
	Responsible construction management	 8. Achieve criterion 7 above. 9. Achieve six additional items in Table 4.1. Note: GN33 confirms that a CCS score of at least 35 (& min. 11 in each section) plus Table 4.1 item g (Ensure clear and safe access in and around the buildings at the point of handover) will achieve two credits. 	1	0.61	В	Two credits are achieved subject to evidence.
Man 03 Responsible construction practices	ş	10. Assign responsibility to an individual for monitoring, recording and reporting energy use, water consumption and transportation data (where measured) resulting from all on-site construction processes (and dedicated off-site manufacturing) throughout the build programme. To ensure the robust collection of information, this individual must have the appropriate authority and responsibility to request and access the data required. Where appointed, the BREEAM AP could perform this role.	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The prerequisite criteria are achieved subject to evidence.
Man 03 Responsib	Monitoring of construction-site impacts	 Energy consumption 11. Achieve criterion 10. 12. Set targets for the site energy consumption in kWh (and where relevant, litres of fuel used) as a result of the use of construction plant, equipment (mobile and fixed) and site accommodation. 13. Monitor and record data for the energy consumption described in criterion 12. 14. Report the total carbon dioxide emissions (total kgCO₂/project value) from the construction process via BREEAM Projects (for the purposes of potential future BREEAM performance benchmarking). Water consumption 15. Achieve criterion 10. 16. Set targets for the potable water consumption (m³) arising from the use of construction plant, equipment (mobile and fixed) and site accommodation. 17. Monitor and record data to report the total net water consumption (m³), i.e. consumption ninus any recycled water use from the construction process via BREEAM Projects (for the purposes via BREEAM Projects (for the purposes via BREEAM Projects). 	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core) ¢

Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Man 03 Responsible construction practices	Monitoring of construction-site impacts	 Transportation of construction materials and waste 19. Achieve criterion 10. 20. Set targets for transportation movements and impacts resulting from delivery of the majority of construction materials to site and construction waste from site. As a minimum cover: a. transportation of materials from the point of supply to the building site, including any transport, intermediate storage and point of supply (see Definitions). Monitor as a minimum: i. Materials used in major building elements (i.e. those defined in BREEAM issue Mat 01 Environmental impacts from construction products - Building life cycle assessment (LCA)). ii. Ground works and landscaping materials. b. Transportation of construction waste from the construction gate to waste disposal processing or recovery centre gate. This monitoring must cover the construction waste groups outlined in the project's resource management plan. 21. Monitor and record data for the transportation movements as described in transport-related carbon dioxide emissions (kgCO₂-eq), plus total distance travelled (km) via BREEAM Projects (for the purposes of potential future BREEAM performance benchmarking). 	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.
Man 04 Commissioning and handover	Commissioning - testing schedule and responsibilities	CREDIT MANDATORY FOR EXCELLENT 1. Prepare a schedule of commissioning and testing. The schedule identifies and includes a suitable timescale for commissioning and re-commissioning of all complex and non-complex building services and control systems and for testing and inspecting building fabric. 2. The schedule identifies the appropriate standards for all commissioning activities to be conducted, where applicable, in accordance with: a. Current Building Regulations. b. BSRIA guidelines. c. CIBSE guidelines. c. CIBSE guidelines. d. Other appropriate standards (see Methodology). Exclude from the assessment any process or manufacture-related equipment specified as part of the project. However, include such equipment in cases where they form an integral part of the building HVAC services, such as some heat recovery systems. 3. Other appropriate standards (see Methodology). Exclude from the assessment any process or manufacture-related equipment specified as part of the project. However, include such equipment in cases where they form an integral part of the building HVAC services, such as some heat recovery systems. 3. Other appropriate standards (see Methodology). C. The BMS or controls installation should be running in auto with satisfactory internal conditions prior to handover. 4. All BMS schematics and graphics (if BMS is present) are fully installed and functional to user interface prior to handover. 4. Appoint an appropriate project team member to monitor and programme pre-commissioning, commissioning and testing when recessary include re-commissioning and testing programme, responsibilities and criteria within ther budget and the main programme of works. Allow the required time to complete all commissioning and testing activities prior to handover. 5. The principal contractor accounts for the commissioning activities on behalf of the client. 5. The principal contractor accounts for the commissioning activities on behalf of the client. 5. The principal contractor accounts for the commissioning activities o	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Man 04 Commissioning and handover	Commissioning - design and preparation	 6. Achieve criteria 1 to 5. 7. During the design stage, the client or the principal contractor appoints an appropriate project team member (see criterion 4), provided they are not involved in the general installation works for the building services systems, with responsibility for: a. Undertaking design reviews and giving advice on suitability for ease of commissioning. b. Providing commissioning management input to construction programming and during installation stages. c. Management of commissioning, performance testing and handover or post-handover stages. For buildings with complex building services and systems, this role needs to be carried out by a specialist commissioning manager (see Definitions on page 58). Shell & Core Notes - Applicable according to the scope of services being specified or installed. 	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.
Man 04 Corr	Testing and inspecting building fabric	 8. Achieve criteria 1 to 5. 9. Complete post-construction testing and inspection to quality-assure the integrity of the building fabric, including continuity of insulation, avoidance of thermal bridging and air leakage paths (this is through airtightness testing and a thermographic survey). A suitably qualified professional (see Definitions) undertakes the survey and testing in accordance with the appropriate standard. 10. Rectify any defects identified during post-construction testing and inspection prior to building handover and close out. Any remedial work must meet the required performance characteristics for the building or element as defined at the design stage (see Methodology). 	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. A thermographic survey would be carried out. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Man 04 Commissioning and handover	Handover	 CRITERIA 11 MANDATORY FOR EXCELLENT 11. Prior to handover, develop two building user guides (see Methodology) for the following users: a. A non-technical user guide for distribution to the building occupiers. b. A technical user guide for the premises facilities managers. A draft copy is developed and discussed with users first (where the building occupates are known) to ensure the guide is most appropriate and useful to potential users. 12. Prepare two training schedules timed appropriately around handover and proposed occupation plans for the following users: a. A non-technical training schedule for the building occupiers. b. A technical training schedule for the premises facilities managers. Shell & Core Notes - The guides and training schedules include, as far as possible, all relevant sections regarding the services and fabric installed. On completion of works the building owner, agent or user hands it over to the fit-out contractor, who can then complete the relevant sections based on the fit-out strategy. 	1	0.61	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.
		Subtotals	18	11.0		
Healt	th and	Wellbeing				
	Daylighting	4. Daylighting criteria have been met using either of the following options: 4.a. The relevant building areas meet good practice daylight factors and other criteria as outlined in Table 5.1 and Table 5.2 on the next page OR 4.b. The relevant building areas meet good practice average and minimum point daylight illuminance criteria as outlined in Table 5.3 on the next page.	1	0.80	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether the building will meet the required daylighting criteria. The offices are 7-9m deep. This credit is uncertain at this stage.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
/isual comfort	View out	 5. 95% of the floor area in 95% of spaces for each relevant building area provides an adequate view out. 6. In addition, the building type criteria in Table 5.6 are applicable to view out criteria. Shell & Core Notes - If it is not possible to confirm which areas of the building will contain workstations, benches or desks, all areas of the building designed for or likely to be occupied by workstations, benches or desks must comply with the relevant criteria. 	1	0.80	В	BREEAM meeting 23.05.22 - Project team confirmed that the building will meet the required view out criteria. The offices are 7-9m deep. This credit is achieved subject to evidence.
Hea 01 Visual	Internal and external lighting levels, zoning and control	External lighting 9. All external lighting located within the construction zone is specified in accordance with BS 5489-1:2013 Code for the practice for the design of road lighting. Lighting of roads and public amenity areas and BS EN 12464-2:2014 Light and lighting - Lighting of work places - Part 2: Outdoor work places. External lighting should provide illuminance levels that enable users to perform outdoor visual tasks efficiently and accurately, especially during the night. 10. Where no external light fittings are specified (either separate from or mounted on the external building façade or roof), the criteria relating to external lighting do not apply and the credit can be awarded on the basis of compliance with criteria 8 – 9.c above.	1	0.80	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 20 provides a preliminary external lighting plan. This credit is achieved subject to further evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



	Credit Title	RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
or air quality	uisite - Indoor air quality (IAC	 A site-specific indoor air quality plan has been produced and implemented in accordance with the guidance in Guidance Note GN06. The objective of the plan is to facilitate a process that leads to design, specification and installation decisions and actions that minimise indoor air pollution during occupation of the building. The indoor air quality plan must consider the following: a. Removal of contaminant sources b. Dilution and control of contaminant sources: i. Where present, consideration is given to the air quality requirements of specialist areas such as laboratories c. Procedures for pre-occupancy flush out d. Third party testing and analysis e. Maintaining good indoor air quality in-use. 	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The prerequisite criteria are achieved subject to evidence.
Hea 02 Indoor air quality	Ventilation	 2. The building has been designed to minimise the indoor concentration and recirculation of pollutants in the building as follows: a. Provide fresh air into the building in accordance with the criteria of the relevant standard for ventilation. Shell & Core Notes - If ventilation systems are not within the remit of the shell and core developer, compliance can be demonstrated through the building servicing strategy where this is predetermined by the built form or 	1	0.80	D	BREEAM meeting 23.05.22 - Project team confirmed that meeting ventilation criteria is uncertain at this stage. SBL email clarification 25.05.22 - "Hea02 criteria for separation of intakes and exhausts and ingress of pollutants is not applicable in this [shell & core] assessment." This credit is uncertain at this stage.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Hea 04 Thermal comfort	Thermal modelling	 Thermal modelling has been carried out using software in accordance with CIBSE AM11 Building Energy and Performance Modelling. The software used to carry out the simulation at the detailed design stage provides full dynamic thermal analysis. For smaller and more basic building designs with less complex heating or cooling systems, an alternative less complex means of analysis may be appropriate (such methodologies must still be in accordance with CIBSE AM11). The modelling demonstrates that: For air-conditioned buildings, summer and winter operative temperature ranges in occupied spaces are in accordance with the criteria set out in CIBSE Guide A Environmental design, Table 1.5; or other appropriate industry standard (where this sets a higher or more appropriate requirement or level for the building type) For naturally ventilated buildings: Winter operative temperature ranges in occupied spaces are in accordance with the criteria set out in CIBSE Guide A Environmental design, Table 1.5. Or other appropriate industry standard (where this sets a higher or more appropriate requirement or level for the building type) The building is designed to limit the risk of overheating, in accordance with the adaptive comfort methodology outlined in either of the following standards as appropriate; CIBSE TM59: Design methodology for the assessment of overheating in European buildings or CIBSE TM59: Design methodology for the assessment of overheating in are reported via the BREEAM assessment scoring and reporting tool. Shell & Core Notes - See refs 1.1 and 1.2. 	1	0.80	В	KBCN00035 'Air-conditioned spaces' confirms "Air-conditioned spaces are assessed to ensure appropriate thermal comfort levels are achieved. Cooling capacity should be sufficient to comply with the requirements of CIBSE Guide A, however providing sufficient space to install additional capacity to meet the requirements at a later date in line with projected climate change scenarios is also acceptable. In addition, if it can be demonstrated that the air-conditioning system can achieve the thermal comfort criteria in accordance with CIBSE Guide A, Table 1.5, thermal modelling does not need to be carried out. The "time out of range" (TOR) metric should be reported as 0%." BREEAM meeting 23.05.22 - Project team confirmed that thermal comfort modelling would be carried out and thermal comfort standards would be met in line with KBCN00035 above. REF 7 provides written confirmation from the M&E Engineer "MBA who are responsible for all the Part L modelling required as follows: - Construct thermal models using IES software (or equivalent) and populate with all fabric, HVAC systems, occupancy profiles, equipment heat gains and all other information required to output results. - Produce thermal heat loss and heat gains." This credit is achieved subject to further evidence. Pre-planning actions/evidence MBA to provide Thermal Comfort Report (latest is JC email 29.06.22).
Hea 04 Th	Design for future thermal comfort	 5. Criteria 1 to 4 are achieved. 6. The thermal modelling demonstrates that the relevant requirements set out in criterion 3 above are achieved for a projected climate change environment (see Definitions). 7. Where criterion 6 above is not met, the project team demonstrates how the building has been adapted, or designed to be easily adapted in future using passive design solutions in order to subsequently meet the requirements under criterion 6 above. 8. For air-conditioned buildings, the PMV and PPD indices based on the above modelling are reported via the BREEAM assessment scoring and reporting tool. 	1	0.80	В	KBCN00035 'Air-conditioned spaces' confirms "Air-conditioned spaces are assessed to ensure appropriate thermal comfort levels are achieved. Cooling capacity should be sufficient to comply with the requirements of CIBSE Guide A, however providing sufficient space to install additional capacity to meet the requirements at a later date in line with projected climate change scenarios is also acceptable. In addition, if it can be demonstrated that the air-conditioning system can achieve the thermal comfort criteria in accordance with CIBSE Guide A, Table 1.5, thermal modelling does not need to be carried out. The "time out of range" (TOR) metric should be reported as 0%." BREEAM meeting 23.05.22 - Project team confirmed that thermal comfort modelling would be carried out for a climate change scenario and thermal comfort standards would be met in line with KBCN00035 above. REF 7 provides written confirmation from the M&E Engineer "MBA who are responsible for all the Part L modelling required as follows: - Construct thermal models using IES software (or equivalent) and populate with all fabric, HVAC systems, occupancy profiles, equipment heat gains and all other information required to output results. - Produce thermal heat loss and heat gains." This credit is achieved subject to further evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Ð	For all building types, except Residential institutions (short term and long term stay), which have four credits available below. 1. The building meets the appropriate acoustic performance standards and testing requirements defined in the relevant table below. These tables define criteria for the acoustic principles of:	0	0.00		
	Hea 05 Acoustic performance	b. Indoor ambient noise level	1	0.80	С	BREEAM meeting 23.05.22 - Project team confirmed that, as a worst-case scenario, the required standards for indoor ambient noise levels would be achieved as a cost option (possible bldg fabric changes).
	Hea 05 Acou	 A suitably qualified acoustician (SQA) is appointed to define a bespoke set of performance requirements for all function areas in the building. The bespoke performance requirements use the three acoustic principles defined in criterion Hea 05 Acoustic performance - Criterion 1 above, setting out the performance requirements for each and the testing regime required. Shell & Core Notes - When assessing criteria 2 below for a shell and core building, only Indoor ambient noise level below should be assessed. See also Ref 1.0. 	0	0.00		One credit is cost option at this stage.
Hea 06 Security	Security of site and building	 A Suitably Qualified Security Specialist (SQSS) conducts an evidence- based Security Needs Assessment (SNA) during or prior to Concept Design (RIBA Stage 2 or equivalent). The purpose of the SNA will be to identify attributes of the proposal, site and surroundings which may influence the approach to security for the development . The SQSS develops a set of security controls and recommendations for incorporation into the proposals. Those controls and recommendations shall directly relate to the threats and assets identified in the preceding SNA. The controls and recommendations shall be incorporated into proposals and implemented in the as-built development. Any deviation from those controls and recommendations shall be justified and agreed with the SQSS. Shell & Core Notes - Speculative project - If the SQSS is unable to make complete recommendations due to the speculative nature of the assessment, then the credit may still be available. The SQSS must confirm that they have addressed all parts of the project where it is feasible to do so, based on the information available to them at the time of assessment. In relation to the influence of the occupiers on security, the SQSS shall clearly document their assumptions in the SNA. 	1	0.80	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether this credit will be pursued. SNA could be provided but security recommendations could be cost-prohibitive. SBL emailed SNA contact (NS) and outline brief 29.05.22. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. This credit is uncertain at this stage. Pre-planning actions/evidence In the first instance, Goodrich to confirm with NS whether SNA recommendations are likely to be probelmmatic or cost-prohibitive (email request 29.05.22. NSG quote by email 17.06.22).

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



		EAM Credit Assessment				
Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Hea 07 Safe and healthy surroundings	Safe ac	Where external site areas form part of the assessed development the following apply: 1. Dedicated and safe cycle paths are provided from the site entrance to any cycle storage, and connect to offsite cycle paths where applicable. 2. Dedicated and safe footpaths are provided on and around the site providing suitable links for the following: a. The site entrance to the building entrance, b. Car parks (where present) to the building entrance c. The building to outdoor space d. Connecting to off-site paths where applicable. 3. Pedestrian drop-off areas are designed off, or adjoining to, the access road and should provide direct access to other footpaths. Where vehicle delivery access and drop-off areas form part of the assessed development, the following apply: 4. Delivery areas are not accessed through general parking areas and do not cross or share the following: a. pedestrian and cyclist paths b. outside amenity areas accessible to building users and general public. 5. There is a dedicated parking or waiting area for goods vehicles with appropriate separation from the manoeuvring area and staff and visitor car parking. 6. Parking and turning areas are designed for simple manoeuvring according to the type of delivery vehicle likely to access the site, thus avoiding the need for repeated shunting.	1	0.80	В	BREEAM meeting 23.05.22 - Project team confirmed that the development will meet the required safe pedestrian and cyclist access criteria. REF 20 provides a preliminary external lighting plan. This credit is achieved subject to further evidence.
	Outside space	7. There is an outside space providing building users with an external amenity area.	1	0.80	В	BREEAM meeting 23.05.22 - Project team confirmed that suitable outdoor amenity space(s) can be provided. REF 17 provides an updated site plan confirming the provision of one outdoor amenity space and one outdoor seating area. This credit is achieved subject to further evidence.
		Subtotals	10	8.0		
Energ	01/					
	gy			0.07		
Irbon			1	0.67	B	
and carbon		FOUR CREDITS MANDATORY FOR EXCELLENT	1	0.67	B	BREEAM meeting 23.05.22 - Project team confirmed that an
use ai	nce	1. Calculate an Energy Performance Ratio for New Construction (EPR	1	0.67	B	EPR of 0.4 will be achieved. Any further improvements uncertain at this stage.
	orma	NC). Compare the EPR NC achieved with the benchmarks in Table 6.1 and award the corresponding number of BREEAM credits.	1	0.67	B	REF 7 provides written confirmation from the M&E Engineer
of en nissi	, perf	A description of how the EPR NC is calculated from a building's modelled	1	0.67	D	"MBA who are responsible for all the Part L modelling required as follows - Produce Part L2A compliance report
ction	Energy performance	operational energy performance, primary energy consumption and CO_2 emissions is provided.	1	0.67	D	and BRUKL/EPC certificate for planning purposes."
ledu	ш	Shell & Core Notes - See ref. 1.1 and 1.2.	1	0.67	D	Four credits are achieved subject to evidence. Four credits are uncertain at this stage and one credit is no
Ene 01 Reduction of energy emissions			1	0.67	D	achieved.
Ĕ			1	0.67	Е	

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
d carbon emissions	y consumption	 Four credits – Energy modelling and reporting Involve relevant members of the design team in an energy design workshop, focusing on operational energy performance (see Methodology). Undertake additional energy modelling during the design and post-construction stage to generate predicted operational energy consumption figures (see 'Prediction of operational energy consumption'). Report predicted energy consumption targets by end use, design assumptions and input data (with justifications). Carry out a risk assessment to highlight any significant design, technical, and process risks that should be monitored and managed throughout the construction and commissioning process. 	1	0.67	B	
Ene 01 Reduction of energy use and carbon emissions	operational er		1	0.67	В	BREEAM meeting 23.05.22 - Project team confirmed that additional energy modelling during the design and post- construction stage would be undertaken. Four credits are achieved subject to evidence.
Ene 01 Reduct	tio		1	0.67	В	
Ene 02 Energy monitoring	Sub-metering of end-use categories	 CREDIT MANDATORY FOR EXCELLENT Install energy metering systems so that at least 90% of the estimated annual energy consumption of each fuel is assigned to the end-use categories (see Methodology). Meter the energy consumption in buildings according to the total useful floor area:	1	0.67	В	BREEAM meeting 23.05.22 - Project team confirmed that energy monitoring by both end-use category and by area would be provided. DHW from point-of-use electric. Two credits are achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Ene 02 Energy monitoring	Sub-metering of high energy load and tenancy areas	 4. Monitor a significant majority of the energy supply with: a. An accessible energy monitoring and management system for: i. tenanted areas or ii. relevant function areas or departments in single occupancy buildings. OR b. Separate accessible energy sub-meters with pulsed or other open protocol communication outputs for future connection to an energy monitoring and management system for: i. tenanted areas or ii. relevant function areas or departments in single occupancy buildings. 5. Sub-meter per floor plate in large single occupancy or single-tenancy buildings with one homogeneous function, for example hotel bedrooms, offices. Shell & Core Notes - Meters must be installed on the energy supply to each separate tenanted unit or floor plate within the assessed development. 	1	0.67	В	
	Ene 03 External lighting	 No external lighting (which includes lighting on the building, at entrances and signs). OR External light fittings within the construction zone with: a. Average initial luminous efficacy of not less than 70 luminaire lumens per circuit Watt. b. Automatic control to prevent operation during daylight hours c. Presence detection in areas of intermittent pedestrian traffic. 	1	0.67	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 20 provides a preliminary external lighting plan. This credit is achieved subject to further evidence.
Ene 04 Low carbon design	Passive design analysis	 Achieve the first credit Assessment scope - One credit - Thermal modelling to demonstrate that the building design delivers appropriate thermal comfort levels in occupied spaces. The project team analyses the proposed building design and development during Concept Design to identify opportunities for the implementation of passive design measures (see Passive design analysis). Implement passive design measures to reduce the total heating, cooling, mechanical ventilation, lighting loads and energy consumption in line with the passive design analysis findings. Quantify the reduced total energy demand and carbon dioxide (CO₂) emissions resulting from the passive design measures. 	1	0.67	В	 BREEAM meeting 23.05.22 - Project team confirmed that a passive design analysis would be carried out. SBL email brief 29.05.22. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. This credit is achieved subject to evidence. <u>Pre-planning actions/evidence</u> MBA to provide the following: Hea04 Thermal comfort report/heating & cooling calcs confirming no overheating (latest is JC email 29.06.22). Passive design analysis study report (email request 29.05.22 to Spie et al). Spie/AJA to provide drwgs/specs confirming provision of passive systems (email request 29.05.22).

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Free cooling	 5. Achieve the passive design analysis credit. 6. Include a free cooling analysis (see Free cooling analysis on the facing page) in the passive design analysis carried out under criterion 2. 7. Identify opportunities for the implementation of free cooling solutions. 8. The building is naturally ventilated or uses any combination of the free cooling strategies listed in Free cooling analysis. 	1	0.67	E	BREEAM meeting 23.05.22 - Project team confirmed that mechanical cooling via a VRF system is provided to the offices. This credit is not achieved.
Ene 04 Low carbon design	Low zero carbon feasibility study	 9. An energy specialist (see Definitions) completes a feasibility study (see Low and zero carbon feasibility study) by the end of Concept Design. 10. Establish the most appropriate recognised local (on-site or near-site) low or zero carbon (LZC) energy sources for the building or development (see Scope of LZC systems and how they are assessed), based on the feasibility study. 11. Specify local LZC technologies for the building or development in line with the feasibility study recommendations. 12. Quantify the reduced regulated carbon dioxide (CO₂) emissions resulting from the feasibility study. 	1	0.67	В	BREEAM meeting 23.05.22 - Project team confirmed that an LZC study would be carried out and the air-source heat pumps to the VRF system specified in accordance with the study recommendations. There is also the possible addition of PV to the roof. SBL email brief 29.05.22. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 7 provides written confirmation from the M&E Engineer "MBA who are responsible for all the Part L modelling required as follows: - Produce Part L2A compliance report and BRUKL/EPC certificate for planning purposes - LZC feasibility study." This credit is achieved subject to further evidence. <u>Pre-planning actions/evidence</u> MBA to provide LZC study report (latest is JC email 29.06.22). Spie to provide drwgs/specs confirming provision of LZC systems (email request 29.05.22).
Ene 06 Energy efficient transportation systems	Energy consumption	 For specified lifts, escalators or moving walks (transportation types): Analyse the transportation demand and usage patterns for the building to determine the optimum number and size of lifts, escalators or moving walks Calculate the energy consumption in accordance with BS EN ISO 25745 Part 2(123) or Part 3(124) for one of the following:	1	0.67	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. Passenger lifts will be provided. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Energy efficient features	 Criterion 1 is achieved. Lifts Specify the following three energy efficient features for each lift: 	1	0.67	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.
		Subtotals	21	14.0		
Tran	sport					
	01 Transport assessment and travel plan	 No later than Concept Design stage, undertake a site-specific transport assessment (or statement) and draft travel plan, which can demonstrably be used to influence the site layout and built form; see Methodology. The site-specific travel assessment or statement covers as a minimum: Existing travel patterns and opinions of existing building or site users towards cycling and walking, identifying constraints and opportunities, if relevant. Travel patterns and transport impact of future building users. Current local environment for walkers and cyclists (accounting for visitors who may be accompanied by young children). Reporting of the number and type of existing accessible amenities, see Table 7.1 below, within 500m of the site. Disabled access (accounting for varying levels of disability and visual impairment). Calculation of the existing public transport Accessibility Index (AI), 	1	0.96	В	BREEAM meeting 23.05.22 - Project team confirmed that these credits will be pursued. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes.
	Tra01 Transport asse	 Claculation of the existing public transport Accessibility index (AI), see Methodology. Current facilities for cyclists. Following a transport assessment (in accordance with the requirements set out in criteria 2a-2g) develop a site-specific travel plan, that provides a long term management strategy which encourages more sustainable travel. The travel plan includes measures to increase or improve more sustainable modes of transport and movement of people and goods during the building's operation; see Methodology. If the occupier is known, involve them in the development of the travel plan. Demonstrate that the travel plan will be implemented post construction and be supported by the building's management in operation. 	1	0.96	В	Two credits are achieved subject to further evidence. <u>Pre-planning actions/evidence</u> <u>Goodrich (via Vetos) to provide the following</u> (latest is DB email 21.06.22): - Transport Assessment - Travel Plan.



BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Prerequisite	1. Achieve criteria 3-5 in the Tra 01 Transport assessment and travel plan Issue.	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The prerequisite criteria are achieved subject to evidence.
			1	0.96	В	
			1	0.96	В	BREEAM meeting 23.05.22 - Project team confirmed the following:
			1	0.96	В	Option 1 - Existing AI approx. 2.3 (1E). Option 2 - Increase in AI - 2 No new bus stops on A41 and
			1	0.96	В	diverted bus route (3B). Option 3 - Public transport information system (1D). Option 4 - EVCPs (1B). Option 5 - Car share (1B). Option 6 - Improve local cycle/pedestrian routes - Improvements to National Cycling Route on Wendlebury Road & cycle lane off A41 (2B). Option 7 - Covered cycle storage spaces - Site-wide occupancy = (11923 x 0.25 x 0.108) + (11923 x 0.75 x 0.05) = 770 staff therefore 77 cycle spaces required (1C). Option 8 - Cyclists' facilities - Possible passive shower provision (KBCN0882) in each unit (1B). Option 9 - Existing amenities (1E).
			1	0.96	В	
			1	0.96	В	
			1	0.96	В	
			1	0.96	В	
Tra 02 Sustainable transport measures	Transport options implementation	 Identify the sustainable transport measures, see Table 7.4. Award credits according to the Accessible Index (AI) of the project, and the total number of points achieved for the options implemented, see Table 7.3. 	1	0.96	В	Option 2 REF 8 provides details of the local transport improvements in the vicinity including the construction of a new bus shelter. REF 19 provides a local public transport map and timetables for the bus services operating from those bus stops. Option 6 REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 8 provides details of the local transport improvements in the vicinity of the site comprising the following: - 3m wide combined cycle footpath along the whole length of the western boundary of the site. - Construction of a new bus shelter, footpath and cycle link together with the toucan (i.e. both cycle and pedestrian) crossing over the A41. Also details of the early stage and extensive consultations



BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
			1	0.96	В	 with the LPA. REF 12 provides the pre-planning application outputs from a meeting with the LPA dated 29.08.19) re transport issues. REF 17 provides an updated site plan which confirms the upgraded 3m combined cycleway and footpath along the western boundary of the development/A41. Option 7 REF 15 provides preliminary architectural drwgs. The elevations confirm substantial glazing to all building elevations. REF 17 provides an updated site plan which confirms the location of cycle storage immediately to the soyth-east of each of the four blocks. This location is overlooked from each building. REF 20 provides a preliminary external lighting plan. Ten credits are achieved subject to further evidence (Options 2, 4, 5, 6, 7, 8, 9). Option 3 is uncertain at this stage and Options 1 & 10 are not achieved.
		Subtotals	12	11.5		

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Wate	r					
				0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that at least a 50% improvement on the notional baseline would be achieved. Any further improvements are uncertain at this stage.
		 ONE CREDIT MANDATORY FOR EXCELLENT 1. Use the BREEAM Wat 01 calculator to assess the efficiency of the domestic water-consuming components. 2. Use the standard Wat 01 method (see Methodology) to compare the water consumption (litres/person/day) for the assessed building against a baseline performance. Award BREEAM credits based upon Table 8.1. Where it is not possible to use the standard method, complete the assessment using the alternative Wat 01 method (see Methodology). 3. If a greywater or rainwater system (see Definitions on page 196) is specified, use its yield in L/person/day to offset potable water demand from components. 4. If a greywater or rainwater system is specified and installed: a. Greywater systems in compliance with BS 8515:2009+A1:2013 Rainwater harvesting systems - Code of practice. b. Rainwater harvesting systems - Code of practice. Achieve Assessment scope - Criterion 6 for Wat02 below if post occupancy stage certification is to be pursued. Shell & Core Notes - See ref 1.0 and 1.1. 	1	0.78	В	 REF 3 provides manufacturer's literature from the M&E Engineer confirming the following: Whb taps - Ideal Tesi Single Lever Basin Mixer - 5 lit/min @ 3 bar pressure. Shower - Bristan JOYTHCKH85 W - 4.5 lit/min. Disabled toilet - Armitage Shanks Doc M Contour 21+ Close Coupled Pack - WC @ 4.5 lit single flush, whb tap @ 4.5 lit/min. Kitchenette tap - Spec & flow rate TBC. WC cistern - Conceala 2 4.5/3 or 4/2.6 litre cistern, dual flush - TBC.
			1	0.78	В	
	I Water cons		1	0.78	В	REF 4 provides an Indicative Office Floor Plan drwg and written confirmation from the M&E Engineer of the following sanitaryware water consumption rates: "- Tesi mixer = 4.6l/min at 1 bar - Shower = 4.5l/min at 1 bar
	-		1	0.78	D	 Shower = 4.5Umin at 1 bar Doc M = 4.5L single flush + 1.5l/min spray tap insert at 1bar Kitchen sink = 5l/min at 1bar WC = 4/2.6 dual flush (2.95L effective flush) Layout attached we have assumed a single tea point wil be provided on the first floor." <u>Actions/evidence:</u> AJA to provide site plan and floor plans (email request 17.06.22). SBL to confirm Wat01 Calculator scoring. Four credits are achieved subject to evidence and one credit is uncertain at this stage.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Wat 02 Water monitoring	 CRITERIA 1 MANDATORY FOR EXCELLENT 1. Specify a water meter on the mains water supply to each building. This includes instances where water is supplied via a borehole or other private source. 2. For water-consuming plant or building areas consuming 10% or more of the building's total water demand: a. Fit easily accessible sub-meters OR b. Install water monitoring equipment integral to the plant or area. 3. For each meter (main and sub): a. Install a pulsed or other open protocol communication output AND b. Connect it to an appropriate utility monitoring and management system, e.g. a building management system (BMS), for the monitoring of yater consumption. If there is no BMS system in operation at Post-Construction stage, award credits provided that the system used enables connection when the BMS becomes operational. d. In buildings with swimming pools, or large water tanks and aquariums, fit separate sub-meters on the water supply of the above and any associated changing facilities (toilets, showers etc.) irrespective of their water consumption levels. S. In buildings containing laboratories, fit a separate water meter on the water supply to any process or cooling loop for 'plumbed-in' laboratory process equipment, irrespective of their water consumption levels. Additionally for those pursuing a post occupancy stage certification: 6. The water monitoring strategy used enables the identification of all water consumption for sanitary uses as assessed under Wat 01 (litres/person/day), if a post occupancy stage certification is sought. Shell & Core Notes - See ref 1.0 and 1.1. 	1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.
Wat 03 Water leak detection	Leak detection system	 Install a leak detection system capable of detecting a major water leak: a. On the utilities water supply within the buildings, to detect any major leaks within the buildings AND b. Between the buildings and the utilities water supply, to detect any major leaks between the utilities supply and the buildings under assessment. The leak detection system is: A permanent automated water leak detection system that alerts the building occupants to the leak OR an inbuilt automated diagnostic procedure for detecting leaks. b. Activated when the flow of water passing through the water meter or data logger is at a flow rate above a pre-set maximum for a pre-set period of time. This usually involves installing a system which detects higher than normal flow rates at meters or sub-meters. It does not necessarily require a system that directly detects water leakage along part or the whole length of the water supply system. c. Able to identify different flow and therefore leakage rates, e.g. continuous, high or low level, over set time periods. Although high and low level leakage rates are not specified, the leak detection equipment installed must have the flexibility to distinguish between different flow rates to enable it to be programmed to suit the building type and owner's or occupier's usage patterns. d. Programmable to suit the owner's or occupier's water consumption criteria. e. Where applicable, designed to avoid false alarms caused by normal operation of large waterconsuming plant such as chillers. Where there is physically no space for a leak detection system between the utilities water meter and the building, alternative solutions can be used, provided that a major leak can still be detected. 	1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The utility meter is likely to be located immediately outside each unit. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Wat 03 Water leak detection	v control devi	 Install flow control devices that regulate the water supply to each WC area or sanitary facility according to demand, in order to minimise undetected wastage and leaks from sanitary fittings and supply pipework. Shell & Core Notes - Assess the water supplies to WC areas or facilities as per criterion 3 regardless of whether the WC areas or facilities are fitted out or not. 	1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.
	at 04 Water efficient equipme	 Identify all water demands from uses other than those listed under - Table 8.4 that could be realistically mitigated or reduced. Where there is no water demand from uses other than domestic-scale, sanitary use components in the building, this issue is not applicable. Identify systems or processes to reduce the relevant water demand (criterion 1 above), and establish, through either good practice design or specification, a demonstrable reduction in the total water demand of the building. Shell & Core Notes - Where the only non-domestic scale, non-sanitary water demand comes from an irrigation system specified or installed by the developer, then use this system to assess compliance. 	1	0.78	В	KBCN0553 'Manual watering' confirms - "Where the design team can justify that manual watering provides a reduction in unregulated water consumption, this can be considered as an acceptable method for reducing unregulated water use." BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. A series of irrigation stand-pipes may be provided. REF 21 provides preliminary details of proposed standpipes to soft landscaping for watering purposes. This credit is achieved subject to further evidence.
		Subtotals	9	7.0		

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Mate	rials					
		Up to six credits – Superstructure	1	1.25	В	
		Comparison with the BREEAM benchmark during Concept Design (offices, industrial and retail buildings only) Superstructure (offices, industrial and retail buildings) 1. During the Concept Design, demonstrate the environmental performance of the building as follows:	1	1.25	В	BREEAM meeting 23.05.22 - Project team confirmed that
		 performance of the building as follows: a. Carry out a building LCA on of the superstructure design using either the BREEAM Simplified Building LCA tool or an IMPACT Compliant LCA tool according to the methodology (see Methodology). b. Submit the Mat 01/02 Results Submission Tool to BRE at the end of Concept Design, and before planning permission is applied for (that includes external material or product specifications). Comparison with the BREEAM benchmark during Technical Design (offices, industrial and retail buildings only) 2. During Technical Design, demonstrate the environmental performance of the building as follows: a. As criterion 1.a b. Submit the Mat 01/02 Results Submission Tool to BRE at the end of Technical Design. Where a project has not achieved criterion 1, criterion 2 may still be achieved. 	1	1.25	В	five credits will be pursued via the following: - Stage 2 - Superstructure, substructure and hard landscaping. - Stage 4 - Superstructure only.
	Mat 01 Life cycle impacts		1	1.25	В	REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 15 provides preliminary architectural drwgs (site plan & elevations). REF 16 provides the 'Outline Base Specification'.
	Mat 0	 Option appraisal during Concept Design (all building types) 3. For offices, industrial and retail building types, achieve criterion 1 (except where Notes 1.0, 1.1 and 1.2 above apply). 4. During Concept Design, identify opportunities for reducing environmental impacts as follows: a. Carry out building LCA options appraisal of 2 to 4 significantly different superstructure design options (applicable to the Concept Design) stage, see Methodology). b. Use a building LCA tool that is recognised by BREEAM (as suitable for assessing superstructure during Concept Design) according to the methodology (see Methodology). c. For each design option, fulfil the same functional requirements specified by the client and all statutory requirements (to ensure functional equivalency). d. Integrate the LCA options appraisal activity within the wider design decision-making process. Record this in an options appraisal summary document. e. Record the following in the Mat 01/02 Results Submission Tool: The differences between the design option; the design option selected by the client to be progressed beyond Concept Design; the reasons for selecting it and the reasons for not selecting the other design options. 	1	1.25	в	 REF 17 provides an updated site plan. REF 18 provides written confirmation of structures spec & quantities. Five credits are achieved subject to evidence and one credit is uncertain at this stage. One credit is not achieved. <u>Pre-planning actions/evidence</u> AJA/BMP to provide baseline info (SBL email request 14.06.22). SBL to undertake Concept Design stage LCA study.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref. Credit Title	Outline Credit Criteria	Credits Available	% Worth	Scoring	Assessment Commentary
Credi	RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Cre Avai	% W	Sco	Assessment commentary
	f. Submit the Mat 01/02 Results Submission Tool to BRE at the end of Concept Design, and before planning permission is applied for (that includes external material or product specifications). If the building LCA tool recognised by BREEAM and used for criteria 3 to 5 (and 6 to 9, if pursued) is not an IMPACT Compliant LCA tool and criteria 1 to 2 are applicable, then the BREEAM Simplified Building LCA tool (or an IMPACT Compliant LCA tool) shall be used for criteria 1 to 2.				
Mat 01 Life cycle impacts	 Options appraisal during Technical Design (all building types) 5. During Technical Design identify opportunities for reducing environmental impacts as follows: a. Carry out building LCA options appraisal of 2 to 3 significantly different superstructure design options (based on the selected Concept Design option and as applicable to the Technical Design stage, see Methodology). b. Use a building LCA tool that is recognised by BREEAM (as suitable for assessing superstructure during Technical Design) according to the methodology (see Methodology). c. As criteria 4.c to 4.e above. Where an options appraisal summary document was produced during Concept Design, update it to include the Technical Design options. d. Submit the Mat 01/02 Results Submission Tool to BRE at the end of 	1	1.25	D	
Mat 01 Life	 Technical Design. Where a project has not achieved criteria 3 and 4, criterion 5 may still be achieved. One credit – Substructure and hard landscaping options appraisal during Concept Design (all building types) 6. Criteria 3 and 4 are achieved. 7. During Concept Design identify opportunities for reducing environmental impacts as follows: a. Carry out building LCA options appraisal of a combined total of at least six significantly different substructure or hard landscaping design options (at least two shall be substructure and at least two shall be hard landscaping). b. Using a building LCA tool that is recognised by BREEAM (as suitable for assessing substructure and hard landscaping during Concept Design) according to the methodology (see Methodology). c. As criteria 4.c to 4.f above. Shell & Core Notes - See ref 1.1 and 1.2. 	1	1.25	E	

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Mat 02 Environmental impacts from construction products - Environmental Product Declarations		 Specify construction products with EPD that achieve a total EPD points score of at least 20, according to the Methodology. Enter the details of each EPD into the Mat 01/02 Results Submission Tool, including the material category. 	1	1.25	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether sufficient EPDs will be available to achieve this credit. This credit is uncertain at this stage.
ion products	Pre-requis	CRITERIA 1 MANDATORY FOR EXCELLENT 1. 100% of timber and timber-based products used on the project are 'Legal' and 'Sustainable' as per the UK Government's Timber Procurement Policy (TPP) (see Definitions). Compliance with criterion 1 is a minimum requirement for achieving any BREEAM rating. There are no prerequisite requirements for other materials.	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The pre-requisite requirements are achieved subject to evidence.
Mat 03 Responsible sourcing of construction products	nabling sustainable procur	 2. A sustainable procurement plan must be used by the design team to guide specification towards sustainable construction products. The plan must: a. Be in place before Concept Design. b. Include sustainability aims, objectives and strategic targets to guide procurement activities. Note: targets do not need to be achieved for the credit to be awarded but justification must be provided for targets that are not achieved. c. Include a requirement for assessing the potential to procure construction products locally. There must be a policy to procure construction products locally where possible. d. Include details of procedures in place to check and verify the effective implementation of the sustainable procurement plan. In addition, if the plan is applied to several sites or adopted at an organisational level it must: e. Identify the risks and opportunities of procurement against a broad range of social, environmental and economic issues following the process set out in BS ISO 20400:2017. 	1	1.25	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. SBL emailed draft SPP 29.05.22. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 11 provides the Sustainable Procurement Plan. This credit is achieved subject to further evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
ourcing of ducts	e sourcing		1	1.25	В	BREEAM meeting 23.05.22 - Project team confirmed that at
Mat 03 Responsible sourcing of construction products	suods	3. Use the Mat 03 calculator tool and methodology to determine the number of credits achieved for the construction products specified or procured. Credits are awarded in proportion to the scope of the assessment and the number of points achieved, as set out in Table 9.10.	1	1.25	В	least 20% of the available points will be achieved with any further improvements uncertain at this stage. Two credits are achieved subject to evidence and one
Mat 03 Res const	Measuring		1	1.25	D	credit is uncertain at this stage.
	Mat 05 Designing for durability and resilience	 Protecting vulnerable parts of the building from damage 1. Protection measures are incorporated into the building's design and construction to reduce damage to the building's fabric or materials in case of accidental or malicious damage occurring. These measures must provide protection against: a. Negative impacts of high user numbers in relevant areas of the building (e.g. corridors, lifts, stairs, doors, etc.) b. Damage from any vehicle or trolley movements within 1m of the internal building fabric in storage, delivery, corridor and kitchen areas. c. External building fabric damage by a vehicle. Protection where parking or manoeuvring areas are within 1 metre of the building fagade and where delivery areas or routes are within 2 metres of the façade, i.e. specifying bollards or protection rails. d. Potential malicious damage to building materials and finishes, in public and common areas where appropriate. Protecting exposed parts of the building from material degradation degradation (degradation and product achieving an appropriate quality or durability standard or design guide, see Table 9.14 on the facing page. If none are available, use BS 7543:2015 as the default appropriate standard OR A. Hoe element of the element's resilience when exposed to the applicable material degradation and environmental factors. A. Hoe the facing page. If once are available, use BS 7543:2015 as the default appropriate standard OR A. Hoe the roof and façade to provent water damage, ingress and detrimental ponding. See Table 9.14 for an example list of relevant industry durability and quality standards.	1	1.25	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Mat 06 Material efficiency	 At the Preparation and Brief and Concept Design stages, set targets and report on opportunities and methods to optimise the use of materials. These must be done for each of the following stages. See Table 9.15: Preparation and Brief Concept Design Developed Design Technical Design Construction Develop and record the implementation of material efficiency, see Table 9.15, during: Developed Design Technical Design Construction Report the targets and actual material efficiencies achieved. 	1	1.25	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether suitable material efficiency targets can be demonstrated at Stage 1. This credit is uncertain at this stage.
		Subtotals	14	17.5		
Wast						
Wst 01 Construction waste management	Pre-demolition audit	 Complete a pre-demolition audit of any existing buildings, structures or hard surfaces being considered fordemolition. This must be used to determine whether refurbishment or reuse is feasible and, in the case of demolition, to maximise the recovery of material for subsequent high grade or value applications. The audit must cover the content of Pre-demolition audit scope on the next page and: Be carried out at Concept Design stage (RIBA Stage 2) by a competent person (see Definitions) prior to strip-out or demolition works. Guide the design, consider materials for reuse and set targets for waste management. Engage all contractors in the process of maximising high grade reuse and recycling opportunities. Compare actual waste arisings and waste management routes used with those forecast and investigate significant deviations from planned targets. Make reference to the audit in the resource management plan (RMP) (see Definitions). 	0	0.00		An air photo of the Bicester Gateway site confirms that the site is greenfield with no known previous site use. Pre- demolition audit is not applicable in this development. This credit is not applicable in this assessment.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
lent	source	 3. Prepare a compliant Resource Management Plan (RMP) covering: a. Non-hazardous waste materials (from on-site construction and dedicated off-site manufacture or fabrication, see Definitions on page 246), including demolition and excavation waste. b. Accurate data records on waste arisings and waste management routes. 	1	0.78	В	
managem	nc)		1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that
tion waste	Const	 Meet or improve upon the benchmarks in Table 10.1 for non-hazardous construction waste, excluding demolition and excavation waste. 	1	0.78	В	four credits will be pursued. GIFA is 11745m2 so three resource efficiency credits = (117.5 x 3.2)/3 = approx. 125 No. 8 yard skips. Exemplary resource efficiency = approx. 75 No. 8 yard skips. Uncertain whether 95% by weight of excavation waste can be diverted from landfill. Four credits are achieved subject to evidence.
Wst 01 Construction waste management	Diversion of resources from landfill	 Meet, where applicable, the diversion from landfill benchmarks in Table 10.2 for non-hazardous construction waste and demolition and excavation waste generated. Sort waste materials into separate key waste groups as per Table 10.3, either on-site or through a licensed contractor for recovery. 	1	0.78	В	
Wet 00 Ilea of recyclad and curstainably	wst uz use or recycled and sustainably sourced aggregates	 Prerequisite If demolition occurs on site, to encourage the reuse of site-won material on site, complete a pre-demolition audit of any existing buildings, structures or hard surfaces in accordance with Assessment scope - Wst01 Criterion 1 & 2. One credit - Project Sustainable Aggregate Points leantify all aggregate uses and types on the project Table 10.5 and Table 10.6. Determine the quantity in tonnes for each identified use and aggregate type. Identify the region in which the aggregate source is located. Calculate the distance in kilometres travelled by all aggregates by transport type. Enter the information into the BREEAM Wst 02 calculator to calculate the Project Sustainable Aggregate points. The corresponding number of BREEAM credits will be awarded as shown in Table 10.4 	1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that at least 3.5 Project Sustainable Aggregate points will be achieved. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Wst 03 Operational waste	 CREDIT MANDATORY FOR EXCELLENT 1. Provide a dedicated space for the segregation and storage of operational recyclable waste generated. The space is: a. Clearly labelled, to assist with segregation, storage and collection of the recyclable waste streams. b. Accessible to building occupants or facilities operators for the deposit of materials and collections by waste management contractors. c. Of a capacity appropriate to the building type, size, number of units (if relevant) and predicted volumes of waste that will arise from daily or weekly operational activities and occupancy rates. 2. For consistent and large amounts of operational waste generated, provide: a. Static waste compactors or balers; situated in a service area or dedicated waste management space. b. Vessels for composting suitable organic waste OR adequate spaces for storing segregated food waste and compostable organic material for collection and delivery to an alternative composting facility. c. A water outlet provided adjacent to or within the facility for cleaning and hygiene purposes where organic waste is to be stored or composted on site. 	1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 17 provides an updated site plan which confirms the location of the refuse store to the front of each row of units. This is in a good location for deposit and collection of waste. This credit is achieved subject to further evidence.
Wst 05 Adaptation to climate change	Resilience of structure, fabric, building services and renewables installation	 Conduct a climate change adaptation strategy appraisal using: A systematic risk assessment to identify the impact of expected extreme weather conditions arising from climate change on the building over its projected life cycle. The assessment covers the installation of building services and renewable systems, as well as structural and fabric resilience aspects and includes (see Methodology):	1	0.78	С	BREEAM meeting 23.05.22 - Project team confirmed that a climate change adaptation study could be carried out as a cost option. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. One credit is a cost option at this stage.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD	Credits Available	% Worth	Scoring	Assessment Commentary
Č	Cre	ТЕХТ	A A	%	S	
Wst 06 Design for disassembly and adaptability	Design for disassembly and functional adaptability - recommendations	 Conduct a study to explore the ease of disassembly and the functional adaptation potential of different design scenarios (see Methodology below) by the end of Concept Design. Develop recommendations or solutions (see Methodology) based on the study (criterion 1 above), during or prior to Concept Design, that aim to enable and facilitate disassembly and functional adaptation. 	1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. SBL email brief 29.05.22. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. This credit is achieved subject to further evidence. <u>Pre-planning actions/evidence</u> AJA/Spie/BMP to provide ease of disassembly/functional adaptation study (email request 29.05.22). AJA/Spie/BMP to provide drwgs/specs to confirm implementation of study findings (email request 29.05.22).
Wst 06 Design	Disassembly and functional adaptability – implementation	 Achieve criteria 1 and 2 Provide an update, during Technical Design, on: How the recommendations or solutions proposed by Concept Design have been implemented where practical and cost effective. Omissions have been justified in writing to the assessor. Changes to the recommendations and solutions during the development of the Technical Design. Produce a building adaptability and disassembly guide to communicate the characteristics allowing functional adaptability and disassembly to prospective tenants. 	1	0.78	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. This credit is achieved subject to further evidence.
		Subtotals	9	7.0		
Land	l Use ar	nd Ecology				
LE 01 Site selection	Previously occupied land	1. At least 75% of the proposed development's footprint is on an area of land which has previously been occupied (see Definitions).	1	1.15	E	BREEAM meeting 23.05.22 - Project team confirmed that the site is greenfield with no known previous site use. This credit is not achieved.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary				
LE 01 Site selection	Contaminated land	 A contaminated land professional's site investigation, risk assessment and appraisal has deemed land within the site to be affected by contamination. The site investigation, risk assessment and appraisal have identified: The degree of contamination. The contaminant sources or types. The options for remediating sources of contamination which present an unacceptable risk. The client or principal contractor confirms that remediation of the site will be carried out in accordance with the remediation strategy and its implementation plan as recommended by the contaminated land professional (see Definitions). 	1	1.15	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether there is any significant ground contamination requiring remediation. There is possible pesticide contamination. Also possibility of surplus fill material being placed over the site previously. This credit is uncertain at this stage.				
Ecological risks and opportunities	Prerequisite - Statutory obligations	1 The client or contractor confirms compliance is monitored against all relevant UK and EU or international legislation relating to the ecology of the site.	0	0.00	N/A	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. Legislation will be complied with. SBL emailed BREEAM Ecology brief 23.05.22. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms the following: - P4 - Relevant legislative compliance. - P13&14 - Jacob Hepworth-Bell is an SQE. The pre-requisite criteria are achieved subject to further evidence. 				
LE02 Ecological risks	Survey and evaluation	 Foundation route (Route 1) 2. The site is evaluated using the BREEAM Ecological Risk Evaluation Checklist (Guidance Note 34) confirming that the Foundation route can be used (see Methodology and Definitions). Comprehensive route (Route 2) 3. A Suitably Qualified Ecologist (SQE) carries out a survey and evaluation (see Methodology) for the site early enough to influence site preparation works, layout and, where necessary, strategic planning decisions (typically Preparation and brief stage) (see Definitions). 4. The SQE's survey and evaluation determines the site's ecological baseline (see Definitions), including: a. Current and potential ecological value and condition of the site and related areas within the Zone of Influence. b. Direct and indirect risks to current ecological value from the project. c. Capacity and feasibility for enhancement of the site's ecological value and, where relevant, areas within the Zone of Influence. 5. Recommendations and data collected from the survey and evaluation are shared with appropriate project team members to influence decisions made for activities during site preparation, design and construction works, which can support ecological features (see Methodology and Definitions). 	1	1.15	в	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms (P14-16) 'Survey and Evaluation' criteria is met. This credit is achieved subject to further evidence. 				



BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Determining ecological outcomes (Routes 1 & 2)	Foundation and Comprehensive routes (Routes 1 and 2) 6. Survey and evaluation criteria relevant to the chosen route (criterion 2 if following the Foundation route or Criteria 3–5 above for the Comprehensive route). 7. The project team liaise and collaborate with representative stakeholders (see Methodology) early enough to influence key planning decisions (typically Concept Design stage), to: a. Identify the optimal ecological outcomes for the site. b. Identify, appraise and select measures to meet the optimal ecological outcomes for the site (criterion 7.a), in line with the mitigation hierarchy of action, according to the route being used (see Definitions).	1	1.15	в	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms (P16&17) 'Determining the Ecological Outcomes' criteria is met. This credit is achieved subject to further evidence.
LE03 Managing impacts on ecology	Prerequisite – Ecological risks and opportunities	1. LE02's 'Survey and evaluation and Determining ecological outcomes' criteria have been achieved using the Foundation route (Route 1) or the Comprehensive route (Route 2).	0	0.00	N/A	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms (P19) Prerequisite Ecological Risks and Opportunities criteria is met. The prerequisite criteria are achieved subject to further evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
ts on ecology	Planning and measures on-site	 Foundation and comprehensive route (Routes 1 and 2) 2. Further planning to avoid and manage negative ecological impacts on-site is carried out (see Methodology) early enough to influence the concept design and design brief as well as site preparation planning (typically Concept Design stage). 3. On-site measures for managing negative ecological impacts during site preparation and construction are implemented in-practice (e.g. mitigation measures to protect existing ecological features) (see Methodology). 4. Criteria 2-3 are based on input from the project team in collaboration with representative stakeholders and data collated as part of the 'Determining ecological outcomes' in LE 02 Ecological risks and opportunities (see Methodology). 	1	1.15	В	 BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms (P19) 'Planning and Measures On-Site/Liaison, Implementation and Data' criteria is met. This credit is achieved subject to further evidence.
LE03 Managing impacts on ecology	/e impacts	 Foundation route (Route 1) (one credit) 5. Criteria 2 and 3 have been achieved. 6. Negative impacts from site preparation and construction works are managed according to the mitigation hierarchy (see Methodology on the next page) and no overall loss (see Definitions) of ecological value has occurred. 	1	1.15	E	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether 'minimising loss' will be achieved. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes.
	Managing negative impacts	 Comprehensive route (Route 2) (up to two credits) 7. Criteria 2-4 have been achieved. 8. Negative impacts from site preparation and construction works have been managed according to the mitigation hierarchy, in line with the SQE's recommendations (see Methodology) and, either: a. No overall loss of (see Definitions) ecological value has occurred (two credits). OR where criterion 8.a is not possible: b. The loss of ecological value has been minimised (Minimising Loss) (one credit). 	1	1.15	В	REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms (P20) 'Managing Negative Impacts' criteria is met with the loss of ecological value limited as far as possible. One credit is achieved subject to further evidence and one credit is not achieved.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	Prerequisite - Managing negative impacts on ecology	 Criterion 6 (for Foundation route) or 8 (for Comprehensive route) in LE03 has been achieved. The client or contractor confirms compliance is monitored against all relevant UK, EU or international legislation relating to the ecology of the site. 	0	0.00	N/A	 BREEAM meeting 23.05.22 - Project team confirmed that the prerequisite is uncertain at LE03 pt 8 is uncertain at this stage. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms (P21) Prerequisite 'Managing Impacts on Ecology' criteria is met. The prerequisite criteria is achieved subject to further evidence.
LE04 Ecological change and enhancement	Ecological enhancement	 Foundation route (Route 1) only 3. Locally relevant ecological measures have been implemented that enhance the site's ecological value. The measures adopted are based on (see Methodology). a. Recommendations from recognised 'local' ecological expertise and specialist input and guidance. b. Input from the project team in collaboration with representative stakeholders and data collated as part of 'Determining ecological outcomes' in LEO2. Comprehensive route (Route 2) only 4. Measures have been implemented that enhance ecological value, which are based on input from the project team and SQE in collaboration with representative stakeholders and data collated as part of the 'Determining ecological outcomes' in LEO2 (see Methodology). Measures are implemented in the following order: a. On site, and where this is not feasible, b. Off site within the Zone of Influence. 5. Data collated are analysed and where potentially valuable, provided to the local environmental records centres nearest to, or relevant for, the site. 	1	1.15	В	 BREEAM meeting 23.05.22 - Project team confirmed that this credit is uncertain as the prerequisite is uncertain at this stage. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms (P22) 'Ecological Enhancement' criteria is met with off site within the zone of influence. This credit is achieved subject to further evidence.



BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	>		1	1.15	D	BREEAM meeting 23.05.22 - Project team confirmed that these credits are uncertain as the prerequisite is uncertain at this stage. The site will also not achieve a high net gain. REF 5 provides the following from PM - Development
	ecolog		1	1.15	Е	programme with two options for concurrent and consecutive planning and tender processes.
	Change and enhancement of ecology	Comprehensive route (Route 2) only 6 Up to three credits are awarded based on the change in ecological value occurring as a result of the project. This must be calculated in accordance with the process set out in GN36 - BREEAM, CEEQUAL and HQM Ecology Calculation Methodology – Route 2. Credits are awarded in line with the Reward Scale table in GN36 where there are no residual impacts on protected sites or irreplaceable habitats.	1	1.15	E	REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report. The covering email confirms that the BNG calculation relies on off-site enhancement and so is not compliant. One credit is uncertain at this stage and two credits are not achieved.
	utory obligat implementa	 The client or contractor has confirmed that compliance is being monitored against all relevant UK, EU and international standards relating to the ecology of the site. The following must be achieved, according to the route being assessed: a. Foundation route (Route 1) - Criterion 6 in LE03 has been achieved. Comprehensive route (Route 2) - Criterion 8 in LE03 has been achieved, and at least one credit under LE04 for 'Change and Enhancement of Ecology' has been awarded. 	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that compliance is and will be monitored against all relevant UK, EU or international legislation relating to the ecology of the site. It is uncertain whether the prerequisite criteria will be met as LE04 credit above is uncertain. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. REF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms that all criteria is met but the prerequisite LE04 BNG is not achieved. The pre-requisite requirements are uncertain at this stage.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
LE05 Long term ecology management and maintenance	ment and maintenance throughout the n and Comprehensive routes (Route 1	 Measures have been implemented to manage and maintain ecology throughout the project. These measures are based on input from the project team in collaboration with representative stakeholders and data collated as part of the 'Determining ecological outcomes' in LE 02 (see Methodology). To ensure the optimal ecological outcomes agreed in LE 02 are met in-practice, these measures must monitor and review the effectiveness of the mitigation and enhancement measures in place for LE 03 & LE 04 to ensure they are implemented. A section on Ecology and Biodiversity has been included as part of the tenant or building owner information supplied, to inform the owner or occupant of local ecological features, value and biodiversity on or near the site (see Methodology). This should include detailed management and maintenance plans as required by landscape and asset managers as well as relevant parts of the handover information for occupiers written in a format that encourages understanding and supportive behaviours. 	1	1.15	D	BREEAM meeting 23.05.22 - Project team confirmed that: - Suitable measures will be implemented to manage and maintain ecology throughout the project. - A section on Ecology and Biodiversity will be included as part of the tenant or building owner information. - These credits are uncertain due to the LE05 prerequisite above. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated
	andscape and ecology management plan	 A Landscape and Ecology Management Plan, or equivalent, has been developed in accordance with BS42020:2013 Section 11.1(205) covering at least the first five years after project completion as a minimum and including: Actions and responsibilities of relevant individuals prior to handover. The ecological value and condition of the site at handover and how this is expected to develop and change over time. Identification of opportunities for ongoing alignment with activities beyond the development project, which support the aims of BREEAM's Strategic Ecology Framework. Identification and guidance to trigger appropriate remedial actions to address previously unforeseen impacts. Clearly defined and allocated roles and responsibilities for delivering the plan. The landscape and management plan or similar will be updated to support maintenance of the ecological value of the site (see sections relating to Maintenance and Monitoring in CIEEM, CIRIA, IEMA, for helpful guidance). 	1	1.15	D	AEF 13 provides a detailed landscape pack which comprises detailed landscape planting plans, detailed hard surface plans, tree pit details, landscape management report & landscape specification report. REF 14 provides the GN40 BREEAM Ecology Report which confirms that all criteria is met but the prerequisite LE04 BNG is not achieved. Two credits are uncertain at this stage.
<u> </u>		Subtotals	13	15.0		
		000101013	10	10.0		

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Pollu	ition				1	
		 Three credits - No refrigerant use 1. No refrigerant use within the installed plant or systems. OR alternatively, where the building does use refrigerants, the three credits can be awarded as follows: Prerequisite 2. All systems with electric compressors comply with the requirements of BS EN 378:2016(203) (parts 2 and 3). Refrigeration systems containing ammonia comply with the Institute of Refrigeration Ammonia Refrigeration Systems code of practice. 	1	0.75	D	
	Pol 01 Impact of refrigerants	Impact of refrigerant Two credits 3. The direct effect life cycle CO_2 equivalent emissions (DELC) of ≤ 100 CO_2 -eq/kW. For systems which provide cooling and heating, the worst performing output based on the lower of kW cooling output and kW heating output is used to complete the calculation. To calculate the DELC, refer to the relevant definitions in Methodology and Additional information. OR 4. All refrigerants used have a global warming potential (GWP) ≤ 10 . OR One credit 5. Systems using refrigerants have a DELC of $\leq 1000 \text{ kgCO}_2$ -eq/kW cooling and heating capacity.	1	0.75	В	BREEAM meeting 23.05.22 - Project team confirmed that VRF will provide space heating and cooling. It is assumed that one credit will be achieved for DELC of $\leq 1000 \text{ kgCO}_2$ - eq/kW cooling and heating capacity. One credit is achieved subject to evidence. Two credits
	Pol 01 In	 One credit - Leak detection 6. All systems are hermetically sealed or only use environmentally benign refrigerants (see 'Leak detection and Hermetically sealed systems'). OR 7. Where the systems are not hermetically sealed: a. Systems have: i. A permanent automated refrigerant leak detection system, that is robust and tested, and capable of continuously monitoring for leaks. OR ii. An inbuilt automated diagnostic procedure for detecting leakage is enabled. b. In the event of a leak, the system must be capable of automatically responding and managing the remaining refrigerant charge to limit loss of refrigerant (see 'Automatic isolation and containment of refrigerant'). Shell & Core Notes - If the building is designed to avoid the need for refrigerant-containing building services, so no refrigerant use will be specified for the fit-out, the available credits can be awarded by default.	1	0.75	D	are uncertain at this stage and unlikely to be achieved.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	l air quality	 All heating and hot water is supplied by non-combustion systems. For example, only powered by electricity. OR alternatively; Emissions from all installed combustion plant that provide space heating and domestic hot water do not exceed the levels set in Table 12.4 	1	0.75	В	BREEAM meeting 23.05.22 - Project team confirmed that space heating and DHW are from mains electric.
	Pol 02 Local air quality	 and Table 12.5 on the next page. The measurements must be provided by manufacturers, following the labelling requirements of the European directive 2009/125/EC. No credits can be awarded for Pol 02 if any of the combustion appliances are not covered in Table 12.4 and Table 12.5. 3. Emissions from all installed combustion plant that provide space heating and domestic hot water do not exceed the levels set in Table 1.21 and Table 1.22. 	1	0.75	В	Two credits are achieved subject to evidence.
	Prerequisite	 An appropriate consultant is appointed to carry out and demonstrate the development's compliance with all criteria. 	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The prerequisite requirements are achieved subject to evidence.
03 Flood and surface water management	resilience	 Two credits - Low flood risk 2. A site-specific flood risk assessment (FRA) confirms the development is in a flood zone that is defined as having a low annual probability of flooding. The FRA takes all current and future sources of flooding into consideration (see 'Sources of flooding'). One credit - Medium or high flood risk 3. A site-specific FRA confirms the development is in a flood zone that is defined as having a medium or high annual probability of flooding and is not in a functional floodplain. The FRA must take all current and future sources of flooding'). For 	1	0.75	В	BREEAM meeting 23.05.22 - Project team confirmed that these credits will be pursued. The FRA will show low flood risk from all sources.
Pol 03 Flo	Flood	smaller sites refer to 'Level of detail required in the FRA for smaller sites', which overrides criterion 2 above. 4. To increase the resilience and resistance of the development to flooding, one of the following must be achieved: a. The ground level of the building and access to both the building and the site, are designed (or zoned) so they are at least 600 mm above the design flood level of the site's flood zone (see '600 mm threshold'). b. The final design of the building and the wider site reflects the recommendations made by an appropriate consultant in accordance with the hierarchy approach outlined in section 5 of BS 8533:2017.	1	0.75	В	Two credits are achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
igement	isite for run-off c	5. Surface water run-off design solutions must be bespoke, i.e. they must take account of the specific site requirements and natural or man-made environment of and surrounding the site. The priority levels detailed in the Methodology must be followed, with justification given by the appropriate consultant where water is allowed to leave the site.	0	0.00	N/A	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The prerequisite criteria are achieved subject to evidence.
Pol 03 Flood and surface water management	Surface Water Run-Off - Rate	 6. For brownfield sites, drainage measures are specified so that the peak rate of run-off from the site to the watercourses (natural or municipal) shows a 30% improvement for the developed site compared with the predeveloped site. This should comply at the 1-year and 100-year return period events. 7. For Greenfield sites, drainage measures are specified so that the peak rate of run-off from the site to the watercourses (natural or municipal) is no greater for the developed site than it was for the pre-evelopment site. This should comply at the 1-year and 100-year return period events. 8. Relevant maintenance agreements for the ownership, long term operation and maintenance of all specified Sustainable Drainage Systems (SuDS) are in place. 9. Calculations include an allowance for climate change. This should be made in accordance with current best practice planning guidance (see Definitions). 	1	0.75	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. BREEAM surface water runoff rate criteria will be met. This credit is achieved subject to evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core) Ŷ

Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Pol 03 Flood and surface water management	Surface Water Run-Off - Volume	 10. Flooding of property will not occur in the event of local drainage system failure (caused either by extreme rainfall or a lack of maintenance); AND EITHER 11. Drainage design measures are specified so that the post-development run-off volume, over the development lifetime, is no greater than it would have been prior to the assessed site's development. This must be for the 100-year 6-hour event, including an allowance for climate change (see criterion 14). 12. Any additional predicted volume of run-off for this event is prevented from leaving the site by using infiltration or other SuDS techniques. OR (only where criteria 10 and 11 cannot be achieved): 13. Justification from the appropriate consultant indicating why the above criteria cannot be achieved, i.e. where infiltration or other SuDS techniques are not technically viable options. 14. Drainage design measures are specified so that the post-development peak rate of run-off is reduced to the limiting discharge. The limiting discharge is defined as the highest flow rate from the following options: a. The pre-development one-year peak flow rate. b. The mean annual flow rate (Obar). c. 2L/sha. For the one-year peak flow rate, the one-year return period event criterion applies. 15. Relevant maintenance agreements for the ownership, long term operation and maintenance of all specified SuDS are in place. 16. For either option, above calculations must include an allowance for climate change; this should be made in accordance with current best practice planning guidance. 	1	0.75	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. BREEAM surface water runoff volume criteria will be met. An infiltration surface water drainage solution is not possible but compliance will be achieved via pt 14. This credit is achieved subject to evidence.
	Minimising watercourse pollution	 There is no discharge from the developed site for rainfall up to 5 mm (confirmed by the appropriate consultant). Areas with a low risk source of watercourse pollution, an appropriate level of pollution prevention treatment is provided, using appropriate SuDS techniques. Areas with a high risk of contamination or spillage of substances, such as petrol and oil, have separators (or an equivalent system) are installed in surface water drainage systems. Chemical or liquid gas storage areas have a means of containment fitted to the site drainage system (i.e. shutoff valves). This is to prevent the escape of chemicals to natural watercourses in the event of a spillage or bunding failure. All water pollution prevention systems have been designed and installed in accordance with the recommendations of documents such as the SuDS manual(211) and other relevant industry best practice. They must be bespoke solutions taking account of the specific site requirements and natural or man-made environment of and surrounding the site. A comprehensive and up to date drainage plan of the site will be made available for the building or site occupiers. Relevant maintenance agreements for the ownership, long term operation and maintenance of all specified SuDS must be in place. All external storage and delivery areas are designed and detailed in accordance with the current best practice planning guidance. 	1	0.75	E	BREEAM meeting 23.05.22 - Project team confirmed that pt 17 will not be met. An infiltration surface water drainage solution is not possible. This credit is not achieved.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Pol 04 Reduction of night time light pollution	 External lighting pollution has been eliminated through effective design that removes the need for external lighting. This does not adversely affect the safety and security of the site and its users. OR alternatively, where the building does have external lighting, one credit can be awarded as follows: All external lighting (except for safety and security lighting) can be automatically switched off between 23:00 and 07:00. If safety or security lighting is provided and will be used between 23:00 and 07:00, this part of the lighting system complies with the lower levels of lighting recommended during these hours in Table 2 of the ILP guidance 	1			
Pol 04 Re	notes. 4. Illuminated advertisements are designed in compliance with ILP PLG05 The Brightness of Illuminated Advertisements.		0.75	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. REF 20 provides a preliminary external lighting plan. This credit is achieved subject to further evidence.
Pol 05 Reduction of noise pollution	 There are no noise-sensitive areas within the assessed building or within 800 m radius of the assessed site. OR Where there are noise-sensitive areas within the assessed building or noise-sensitive areas within 800 m radius of the assessed site, a noise impact assessment compliant with BS 4142:2014(218) is commissioned. Noise levels must be measured or determined for: Existing background noise levels: at the nearest or most exposed noise-sensitive development to the proposed assessed site. Including existing plant on a building, where the assessed development is an extension to the building. Noise rating level from the assessed building. The noise impact assessment must be carried out by a suitably qualified acoustic consultant. The noise level from the assessed building, as measured in the locality of the nearest or most exposed noise sensitive development, must be at least 5dB lower than the background noise throughout the day and night. If the noise sources from the assessed building are greater than the levels described in criterion 4, measures have been installed to attenuate the noise at its source to a level where it will comply with the criterion. 	1	0.75	В	BREEAM meeting 23.05.22 - Project team confirmed that this credit will be pursued. The hotel adjacent to Units A & B are the nearest NSRs. There id rooftop plant in a plant well. It is assumed that if required, noise mitigation can be provided. This credit is achieved subject to evidence.
	Subtotals	12	9.0		

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Exemplary Man03	esponsible construction management	 A Innovation Credits 23. Achieve all items in Table 4.1. Note: GN33 confirms that a CCS score of at least 35 plus the following Table 4.1 items will achieve the Exemplary credit: g. Ensure clear and safe access in and around the buildings at the point of handover. p. The fleet operators undertakes driver training and awareness to promote safety within the development footprint and off site. q. The fleet operators, captures and investigates any road accidents, incidents and near misses and reports them back to the principal contractor. The principal contractor analyses these items. Fleet operator is defined as - "A fleet operator is responsible for groups of motor vehicles owned or leased by a business, government agency or other organisation rather than by an individual or family. Transportation to the project is likely to be by several fleet operators many of which will not be under the control of the constructor. The criteria relate to all fleet operators nonetheless." 	1	1.00	D	BREEAM meeting 23.05.22 - Project team confirmed that the principal contractor will achieve a minimum CCS score of 35/50 (with no less than 7/10 in each category) together with GN33 Table 4.1 pts g. It is unlikely that points p & q for fleet management will be met. This credit is uncertain at this stage and unlikely to be achieved.
Exemplary Hea01	Daylighting	To achieve an exemplary performance credit for daylighting: 14. Daylighting criteria have been met using either of the following options: a. Relevant building areas meet exemplary daylight factors and the relevant criteria in Table 5.8 on the facing page. b. Relevant building areas meet exemplary average and minimum point daylight illuminance criteria in Table 5.9 on the facing page.	1	1.00	E	BREEAM meeting 23.05.22 - Project team confirmed that BREEAM exemplary daylighting performance will not be achieved. This credit is not achieved.
Exemplary Hea 06	Security	 A compliant risk based security rating scheme has been used. The performance against the scheme has been confirmed by independent assessment and verification. 	1	1.00	E	BREEAM meeting 23.05.22 - Project team confirmed that the security performance of the project will not be confirmed via the SABRE scheme. This credit is not achieved.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
		Up to two credits - Beyond zero net regulated carbon 6. The building achieves an EPR NC \geq 0.9 and zero net regulated CO ₂ emissions (see Definitions).	1	1.00	E	
	S	 Energy generation from on-site and near-site LZC sources is sufficient to offset carbon emissions from regulated energy use plus a percentage of emissions from unregulated energy use. 	1	1.00	Е	
	energy use and carbon emissions	8. Award the exemplary credits based on the percentage of additional emissions from unregulated energy that are offset by LZC sources (see Table 6.2).	1	1.00	E	
le01	d carbo	Three credits - Carbon negative 9. The building is deemed carbon negative where > 100% (see Table 6.2)	1	1.00	Е	BREEAM meeting 23.05.22 - Project team confirmed that the building will not achieve an EPRNC ≥0.9 and have zero
Exemplary Ene01	/ use and	of carbon emissions from unregulated (and regulated) energy use are offset by energy generated from on-site and near-site LZC sources (see Definitions).	1	1.00	E	net CO2 emissions. The credits for post-occupancy energy modelling will be pursued in order to achieve the required Excellent rating.
Exen	of energ)	Two credits – Post-occupancy stage 10. Achieve maximum available credits in Ene 02 Energy monitoring. In addition, preschools, primary schools, law courts, prisons and multi-	1	1.00	В	Two credits are achieved subject to evidence and five credits are not achieved.
	Reduction of	residential buildings must separately monitor relevant function areas or departments in accordance with Assessment scope - Criterion 4. 11. The client or building occupier commits funds to pay for the post occupancy stage. This requires an assessor to be appointed and to report on the actual energy consumption compared with the targets set in criterion 4 above. 12. The energy model (criterion 3 above) is: a. Submitted to BRE and b. Retained by the building owner.	1	1.00	В	
Exemplary Wat01	Water consumption	 7. Achieve criteria 1 to 4 of Wat01. 8. The water consumption (litres/person/day) for the assessed building achieves the 65% improvement described as exemplary performance in Table 8.1. 	1	1.00	E	BREEAM meeting 23.05.22 - Project team confirmed that a 65% improvement on the notional baseline will not be achieved. This credit is not achieved.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
	at 01	One credit – Core building services options appraisal during Concept Design (all building types) 8. Criteria 3 to 4 are achieved. 9. During Concept Design identify opportunities for reducing environmental impacts as follows: a. Carry out building LCA options appraisal of at least 3 significantly different core building services design options. b. Use a building LCA tool that is recognised by BREEAM (as suitable for assessing core building services during Concept Design) according to the methodology (see Methodology). c. As criteria 4.c to 4.f above.	1	1.00	D	BREEAM meeting 23.05.22 - Project team confirmed that it is unlikely that the services design will be included in the LCA study. This credit is uncertain at this stage and unlikely to be achieved.
	Exemplary Mat 01	 One credit – LCA and LCC alignment (all building types) 10. Achieve criteria 3 to 5. 11. Achieve Elemental LCC plan and Component Level LCC options appraisal credits (Man 02 Life cycle cost and service life planning). 12. Include design options appraised for criteria 3 to 4 (and 6 to 7 and 8 to 9, if pursued) during Concept Design in Assessment scope - The elemental LCC plan. 13. Include the design options appraised for criterion 5 during Concept Design in the 'Component level LCC option appraisal' (in Man 02 Life cycle cost and service life planning). 14. Integrate the aligned LCA and LCC options appraisal activity within the wider design decision-making process. Record this in an options appraisal summary document including the relevant cost information from the 'elemental LCC plan' and 'Component level LCC option appraisal'. 	1	1.00	D	BREEAM meeting 23.05.22 - Project team confirmed that it is unlikely that the LCC will be aligned with the LCA study. This credit is uncertain at this stage and unlikely to be achieved.
	Exemplary Mat 01	 One credit – Third party verification (all building types) 15. Criteria 1 to 7 (as applicable to the building type) are achieved. 16. A suitably qualified third party (see Definitions) carries out the building LCAs or produces a report verifying the building LCAs accurately represent the designs under consideration during Concept Design and Technical Design with reference to the requirements of criteria 1 to 7 (and 8 to 14 if pursued). 17. For each LCA option, itemise the findings of the verification checks made by the suitably qualified third party in the report including, as a minimum, the quality requirements show in Table 9.4. 18. Include details of the suitably qualified third party independence from the project client and design team in the report. 	1	1.00	В	BREEAM meeting 23.05.22 - Project team confirmed that a 3rd party verification of the LCA study will be pursued in order to achieve the required Excellent rating. REF 5 provides the following from PM - Development programme with two options for concurrent and consecutive planning and tender processes. REF 6 provides the following from PM - Updated development programme with concurrent planning and tender processes. This credit is achieved subject to further evidence.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Exemplary Mat03	Responsible sourcing of materials	3. Use the Mat 03 calculator tool and methodology to determine the number of credits achieved for the construction products specified or procured. Credits are awarded in proportion to the scope of the assessment and the number of points achieved, as set out in Table 9.10.	1	1.00	E	BREEAM meeting 23.05.22 - Project team confirmed that BREEAM exemplary responsible sourcing criteria will not be achieved. This credit is not achieved.
Exemplary Wst01	Construction waste management	 Non-hazardous construction waste generated, excluding demolition and excavation waste, is less than or equal to the exemplary level resource efficiency benchmarks (see Table 10.1). The percentage of non-hazardous construction, demolition and excavation waste (if relevant) diverted from landfill meets or exceeds the exemplary level percentage benchmarks in Table 10.2. All key waste groups in Table 10.3 for diversion from landfill are covered in the RMP. Waste data obtained from licensed external waste contractors is reliable and verifiable, by using data from EA/SEPA/EA Wales/NIEA Waste Return Forms or from a PAS 402:2013 compliant company (see Definitions). 	1	1.00	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether exemplary Wst01 criteria will be met. This credit is uncertain at this stage.
Exemplary Wst02	Use of recycled and sustainably sourced aggregates	7. The Project Sustainable Aggregate Points score meets or exceeds the exemplary level performance benchmark in Table 10.4.	1	1.00	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether exemplary BREEAM criteria will be met. This credit is uncertain at this stage.
Exemplary Wst05	Responding to climate change	Achievement of the following criteria demonstrates a holistic approach to the design and construction of the building's life cycle to mitigate against the impacts of climate change. To achieve an exemplary performance credit: 4. Meet criteria 1 to 3 above. 5. Meet the criteria or achieve credits of the assessment issues given in Table 10.11.	1	1.00	D	BREEAM meeting 23.05.22 - Project team confirmed that it is uncertain whether BREEAM exemplary Wst05 criteria will be achieved. Uncertain whether six credits for Ene01 will be achieved. This credit is uncertain at this stage and unlikely to be achieved.

BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Credit Ref.	Credit Title	Outline Credit Criteria RIBA STAGE 1 & 2 ACTIONS HIGHLIGHTED IN RED BOLD TEXT	Credits Available	% Worth	Scoring	Assessment Commentary
Exemplary LE02	Wider site sustainab	 8. Achieve criterion 7 above. 9. Wider sustainability related activities and potential ecosystem service benefits (see Definitions) are considered as part of determining the optimal ecological outcomes for the site (criterion 7), including the areas outlined in the Methodology below. 10. Achieve the credits of the assessment issues outlined below: a. Hea 07 Safe and healthy surroundings - Both credits. b. Pol 03 Flood and surface water management - Achieve credits for 'Surface water run-off' and 'Minimising watercourse pollution'. c. Pol 05 Reduction of noise pollution. 	1	1.00	E	BREEAM meeting 23.05.22 - Project team confirmed that credit Pol03 'Minimising watercourse pollution' will not be achieved. This credit is not achieved.
Exemplary LE04	Change and enhancement of ecological value	7. The change in ecological value calculated under criterion 6 above confirms significant net gain has been achieved as set out in GN36 - BREEAM, CEEQUAL and HQM Ecology Calculation Methodology – Route 2.	1	1.00	ш	BREEAM meeting 23.05.22 - Project team confirmed that a significant net gain in ecological value will not be achieved. This credit is not achieved.
Innovations	Approved Innovations	One innovation credit can be awarded for each innovation application approved by BRE Global, where the building complies with the criteria defined within an Approved Innovation application form.	1	1.00	E	BREEAM meeting 23.05.22 - Project team confirmed that no innovations will be applied for. This credit is not achieved.
		Subtotals	21	21.0		



APPENDIX 1 - DETAILS OF THE BREEAM METHODOLOGY

breeam

BREEAM is a tool that allows professionals with a vested interest in buildings to review and improve environmental performance throughout their life cycle. In the UK, BREEAM has been accepted as representing best practice and is now being used extensively by property professionals to provide a benchmark for the environmental performance of buildings that they are designing, refurbishing or operating. BREEAM is flexible and can be applied to provide a benchmark of environmental performance at any stage of the building's life cycle.

Using BREEAM, a building is assessed against a range of environmental issues covering impacts of a global, regional, local and indoor scale. For each issue, there are a number of credits available. Where a building attains or exceeds various benchmarks of performance, an appropriate number of credits are awarded.


Although a wide range of credits is available for each assessment, each credit does not carry equal importance to the overall score. The findings are weighted based upon their perceived importance as determined by consensus, achieved through detailed research and consultation by BRE with a variety of interest groups including:

Government Policy Makers	Developers and Investors
Construction Professionals	Environmental Groups and Lobbyists
Local Authorities	Academics
Materials Producers	

The weightings obtained as a result of this research are applied to the individual issue categories to provide an overall BREEAM Assessment score.



BREEAM 2018 New Construction Pre-assessment Report Bicester Gateway, Wendlebury Road, Bicester (shell & core)



Depending upon the number of credits attained in the various issue categories, the results are translated into a corresponding overall rating as follows:

Outstanding (85%+); Excellent (70%+); Very Good (55%+); Good (45%+), or; Pass (30%+).