



- Key**
- Application Site Boundary
 - Asphalt surfacing to all public roads (installed with road gulleys to engineers specifications).
 - Asphalt surfacing to all public pathways with standard pre-cast concrete HB2 kerb in grey, and a pre-cast concrete back edging.
 - Marshalls Tegula Priora Block Paving in colour Pennant Grey to be laid in a stretcher bond pattern, or similar approved.
 - Brell Quomdon 600mm x 600mm paving slabs in colour Buff, or similar approved, to be laid in a stretcher bond pattern according to manufacturer's recommendations.
 - Decorative gravel laid to a depth of 50mm over a geotextile membrane.
 - 1.8m high timber close-board fence with matching pedestrian gates to rear gardens.
 - Timber post & rail fence: 1.2m high 4-bar.
 - 1.8m high coursed local ironstone boundary walling.
 - HH Hedgehog Access - Small gaps to be created in rear garden fence panels to create a corridor for hedgehogs to have free access through sections of the development. Gaps to be 13cm x 13cm, lined up so that hedgehogs can wander in a straight line.
 - HB Hibernacula to ecologist specification.
 - 1B Vivara Pro Swift Nest box (integrated) to be installed on buildings in line with the manufacturers guidance. As supplied by NHBS Ltd (www.nhbs.com) or similar approved.
 - 2F Vivara Pro Woodstone Bat tube (integrated) to be installed on buildings in line with the manufacturers guidance. As supplied by NHBS Ltd (www.nhbs.com) or similar approved.

Project: Hempton Road Phase 2, Deddington
 Drawing No: Hard Landscape Proposals (Sheet 1 of 1)
 Client: Burrington Estates
 Scale: 1:200 @ A0
 Date: 04/05/2022
 Checked: JW
 Number/Date: GL1714 02C